HFR-237

A DESCRIPTIVE CATALOG AND DIRECTORY OF 187 ARMORY DWELLING HOUSES, 1841 - 1852, OF THE U.S ARMORY AT HARPER"S FERRY, VIRGINIA, Including Rents Collected, 1823 to 1851

Harpers Ferry National Historical Park,
West Virginia

by

Charles W. Snell

A History of Armory Dwelling Houses, Volume II.

Denver Service Center
National Capital Team
National Park Service
United States Department of the Interior
Denver, Colorado

September 1981

PREFACE

This volume, the second of a projected two volume history of armory dwelling houses at the Harper's Ferry Armory from 1798 to 1884, is divided into two parts. Part I is a descriptive catalog and a directory of all armory owned dwelling houses standing during the years 1841 to 1852. In Part I an effort has been made to bring together all documentary evidence relating to the physical appearance, construction, location, and users of these residences from 1841 to 1852. Data is also presented on the rents paid on each house and also of the estimated value of each dwelling during this period.

An index of renters(see pages 282- 290) also makes it possible to trace in which armory dwelling house each of the 383 renters of the 1841-52 period resided during those years.

A second index (see Appendix No. 1, pp. 264- 272), also presents the names of and the actual rents paid by 215 renters of armory dwelling houses during the years 1823 to 1828 inclusive.

Part II of this report is a study of War Department plolicies regarding the renting of Armory-owned dwelling houses at the U.S. Armory at Harper's Ferry, Virginia, from 1812 to 1852. The actual amount of rents collected annually from 1822 to 1851 is also presented.

Appendix No. 2 of this study gives the exact location(file number) of all extant Harper's Ferry Armory rent rolls for the years 1822 to 1851 in National Archives Record Group No. 217, Washington, D.C., as well as the amount of rents collected quarterly during those years.

Rent rolls for the years 1852 to April 19, 1861 were destroyed by the staff of the National Archives during the 1940's in order to save space. The information on the renting of Armory dwelling houses for these years has been lost forever.

Charles W. Snell
September 30, 1981

TABLE OF CONTENTS

Page

PREFACE..... i

INTRODUCTION..... 1

Number of Armory Dwelling House and Occupants, 1810-52..... 2

Population of Harper's Ferry, Virginia, 1810 - 1860..... 3

Number and types of Armory Dwelling Houses in 1811, 1821, 1843, 1850, and 1861..... 4

PART I

A DESCRIPTIVE CATALOG AND DIRECTORY OF 188 ARMORY DWELLING HOUSES, 1841 to 1852..... 9

Sources of Information..... 10

A. Armory Dwelling Houses No. 1 to 52, Shenandoah Street, from Arsenal Square(Block A) west via Blocks B, C, D, E, and F, to Virginius Island 12

B. Armory Dwelling Houses No. 53 to 61, Washington Or High Street, from Wager Six Acre Reservation line up to Camp Hill..... 70

C. Armory Dwelling Houses No. 62-65, on side of Camp Hill adjacent to Harpers Graveyard..... 80

D. Armory Dwelling Houses No. 66 to 89, on north side of Camp Hill overlooking the U.S. Musket Factory and located below High Street and fronting on "Crooked Lane Street" and North Cliff or Potomac Street..... 85

E. Armory Dwelling Houses No. 90 to 152 , located on top of Camp Hill and also on Bank of the Potomac River..... 111
Washington and Fillmore Streets.

F. Armory Dwelling Houses No. 153 to 155, located on the South Bank of the Shenandoah River, opposite to Harper's Ferry..... 194

G. Armory Dwelling Houses No. 156 and 169, located on the Upper and Lower Hall Islands, at the U.S. Rifle Factory..199

H. Armory Dwelling Houses No. 170-173, rental sites of stables and slaughter houses along the north bank of the Shenandoah River, Block G and Ferry Lot, Shenandoah Street..... 219

I. Armory Dwelling Houses No. 174 to "183", located in the Wager Six Acre Reservation, High Street..... 225

J. Armory Dwelling Houses No. "184" to "188", Five Quarters built 1846 to 1859 for use of Armory officers..... 237

TABLE OF CONTENTS

Page

PART I(Continued)

K. Armory Dwelling Houses No. " 189" - "190", Arsenal Square Rentals, 1848-52, Shenandoah Street,Blocks A and B..... 246

PART II

RENTAL POLICIES AT HARPER'S FERRY ARMORY, VIRGINIA, 1812 to 1852, AND THE RENTS COLLECTED FROM 1822 to 1851..... 249

A. Armory Policy on renting U.S. owned dwelling Houses,1812-21.. 250

B. Ordnance Department Policy on Collecting Rents, 1822 -1829... 251

Rents Collected, 1822-1829..... 253

C. Policy and Rents Collected, 1830 - 1841..... 254

Rents collected, 1830 - 1835..... 258

Rents collected, 1836 -1841..... 259

D. Policy and Rents Collected, 1842 - 1851..... 260

E. Summary and Conclusions, 1822 - 1851..... 262

F. Rents of the 1852- 1861 period..... 263

APPENDIXES

No. 1 -Statement of rents collected on dwelling houses, 1823 to 1828, at Harper's Ferry Armory, including names of the renters..... 264

Index for the names of the 215 renters, 1823-28..... 268

No. 2. Location of Extant Harper's Ferry Armory Rent Rolls,1822-1851 in the National Archives, Washington, D.C. and the Quarterly Totals of Rents Collected from 1822 to 1851..... 273

No. 3. Major John Symington's Detailed Description of December 12,1844 for the buildings located on Wager Lots No. 17 to 34. (See Map No. 20, page 226)..... 280.

NAME INDEX OF THE 383 RENTERS OF ARMORY DWELLING HOUSES OF THE 1841 - 1852 period.....282

TABLE OF CONTENTS

List of Location Maps

No.		Page
1.	Shenandoah Street in 1835	13
2.	Shenandoah Street in 1834	14
3.	Shenandoah Street in 1848	15
4.	Shenandoah Street House Lots and Reserved Land in 1852	16
5.	Shenandoah Street House Lots in 1869	17
6,	North Cliff or Potomac Street Houses in 1838	86
7.	1848 Map of area around Harper's Graveyard and overlooking the U.S. Musket Factory	87
8.	1869 House Lot Map of area around Harper's Graveyard and the area overlooking the U.S. Musket Factory	88
9.	Camp Hill Houses and Lots in 1848	112
10.	Camp Hill Houses and Lots, detail, in 1850	113
11.	Camp Hill House Lots in 1848, General	114
12.	Camp Hill in 1852, lots for sale and land reserved	115
13.	Camp Hill House Lots in 1869	116
14.	Front elevation of Brick Dwelling Houses built in 1833 on Fillmore Street	151
15.	Floor Plan of Brick Dwelling Houses built in 1833	152
16.	1833 Map showing the location of 12 brick houses to be built on Fillmore Street, Camp Hill	153
17.	Upper Hall Island, Shenandoah River, in 1835	200
18.	Upper Hall Island in 1834	201
19.	Upper and Lower Hall Islands in 1848	202
20.	Map showing buildings on Wager Lots 16 to 34 in the Wager Six Acre Reservation in 1844	226
21.	1848 Map of Commanding Officers and Paymaster's Quarters and Grounds in 1848	238
22.	1852 Map showing land reserved for grounds of Officers' Quarters	239
23.	1869 Map of lots for Officer's Quarters	240

INTRODUCTION

The present town of Harpers Ferry is comprised of approximately 435 acre of land. In 1796-97, the United States purchased 428½ acres for $ 17,016.66 for the purpose of establishing a national armory and arsenal at Harpers Ferry. From 1797 to 1836 the remaining 6 and 3/4 acres of land in Harpers Ferry were owned by one family, the heirs of John Wager, Sr., who refused to sell any of their inholding, but leased out lot at high rate of rents to merchants as sites for commerical structures. Not until 1836 was it possible for wealthy persons to acquire title to any land in Harper's Ferry. In 1836 one of the Wager heirs went bankrupt and one-third of the 6 and 3/4 acres were sold at public auction at high prices. The United States retained title to its 428 acres of land in Harpers Ferry until 1852, when it finally subdivided part of its holdings and offered 312 building lots and 57 dwelling houses for sale at public auctions. The land ownership situation at Harpers Ferry from 1797 to 1852 meant that the average workman and citizen was unable to purchase a lot on which to erect his own residence, thus most of the employees were forced to live in Armory-owned dwelling houses, where the rents were reasonable, or if they wanted to own their own lot and house, they were forced to reside in Bolivar. Not until the land reforms of September 1852, could an Armory employee own land and houses in Harpers Ferry.

Number of Armory Dwelling Houses and Occupants at Harper's Ferry, Virginia, 1810 - 1852

Year	No. of Dwellings	No. of Familes	Town Population	Remarks
1810	14	35 (1)	751	Several more families living in log huts built in 1799.
1811	20	41 (2)		" " " " "
1821	87	115 (3)	1,377	87 dwelling plus 2 school houses valued at $ 48,350.00
1829	113	120 (4)	1,474	
1841	169	171 (5)	1,801	
1848	160	171 (6)		1 parsonage and 4 schools $ 107,960-Value
1850	141	131 (7)	1,747	Value= $ 78,550. 4 as schools and parsonage.
Jan.1 1852	124	(8)		3 as schools

1." Public buildings at Harper's ferry, Virginia, 1st January 1810," prepared by Samuel Annin, Military Storekeeper and Paymaster, Harper's Ferry, Virginia. National Archives Record Group No. 107, Secretary of War Letters Received, A-29(5). Copy in Harpers Ferry NHP Photostat Collection.

2." Public buildings at Harper's ferry, Virginia, 1 October 1811." prepared by Samuel Annin, Military Storekeeper and Paymaster, Harper's Ferry, Virginia. National Archives, Washington, D.C., Record Group 107, Secretary of War Letters Received, A-72(5). Photostat of list in Harpers Ferry NHP Photostat Collection.

3."Statement of the number and dimensions of the buildings at the United States' Armory at Harper's Ferry, Virginia, together with the materials of which they are built, and their estimated value.", on December 31st,1821.prepared by George Bomford, Lieutenant Colonel and Chief of Ordnance, November 30, 1822. from American State Papers- Military Affairs, Vol. II, 482-483.
Number of occupants is for 1823 from "Statement of rents collected on dwelling-houses belonging to the United States armory, Harper's Ferry, Virginia, and occupied by workmen employed in said armory,from the year 1823 until the close 1828, and the names of persons from whom collected," prepared by Armory Supt. James Stubblefield, February 1, 1829, in American State Papers-Military Affairs, Vol. IV,pp. 146-148. Reel 21,Vol. 7, pp.696-698,Setpt.6,1823, 115 familes in 84 houses

4. Number of renters from American State Papers, MA-IV, pp. 146-48.
Number of Houses,1829 from Ibid, p.145.

5. "Rent Roll-Statement of Dwelling Houses beloonging to the United States, at Harper's Ferry Armory, and of the Rents due thereon on 31st March 1841." National Archives Record Group 217- Record of the Second Auditor of the Treasury, First Series, File No. 6195.

6."List of United States Dwelling Houses at Harper's Ferry, June 30, 1849, " National Archives Group Group 156-Ordnance Department, Harpers Ferry NHP Microfilm Reel No. 18, Vol. 12, pp. 1184-1191. This includes data also as of June 30, 1848.

7."List of Dwelling Houses belonging to the United States at Harpers Ferry, December 31, 1850," Harpers Ferry NHP Photostat Collection,National Archives.

8.List of Dwelling Houses at Harper's Ferry per Inventory 30 June 1851. Reel 18,Vol.18 pp.1177-1183.

POPULATION OF HARPER'FERRY AND VIRGINIUS Island , VIRGINIA, 1810- 1860

	1810	1820	1830	1840	1850	1860
White Males	386	681	656	879	806	619
White Females	275	574	598	696	745	593
Total Whites	661	1,255	1,254	1,575	1,551	1,212
Free Black Males	0	13	21	40	50	20
Free Black Females	0	11	43	50	37	19
Total Free Blacks	0	24	64	90	87	39
Slave Back Males		47	61	68	37	33
Slave- Black Females		51	95	68	72	55
Total-Slaves	90	98	155	136	109	88
Total=Blacks	90	122	220	226	196	117
GRAND TOTAL POPULATION	751	1,377	1,474	1,801	1,747	1,339
No. Armory Houses	14	89	113	169	142	33
No. of Families	100	196	224	277	279	217
BOLIVAR: Whites	0	0	233	459	948	1,029
BOLIVAR Free Blacks	0	0	16	51	60	74
Black Slaves	0	0	20	5	46	27
Total, Bolivar Blacks	0	0	36	56	106	101
GRAND TOTAL BOLIVAR	0	0	269	515	1,054	1,130
GRAND TOTAL HARPERS-FERRY-BOLIVAR	751	1,377	1,743	2,316	2,801	2,469

TYPES OF ARMORY DWELLING HOUSES, 1811

Material	Two story	two story & cellar kitchen	twostory, cellar & adjoining kitchen	One story and cellar k itchen	one story	TOTAL
Brick	2	1	1	7	1	12
Brick & Frame	1	1				2
Stone & Frame	1					1
Frame				1	3	4
Log (boarded)			1			1
TOTAL	4	2	2	8	4	20

These 20 dwellings provided housing for 41 families. Total work force numbered 210 men. Many of the single men slept in the second floors of the Musket Factory workshops and storehouses.

TYPES OF ARMORY DWELLING HOUSES, 1821

The 1821 inventory of Armory buildings indicates that there were a total of 87 Armory dwellings and two school houses on the public land. Althrough the dimensions and estimated value of these residences are listed, the locations of these structures is not given.

Material	2story & cellar	2 story	one story	Total No.	Total Value
Brick	3	4	15	22	$ 20,700
Stone	1	0	2	3	2,200
Wood	0	6	56	62	24,650
Total	4	10	73	87	47,550

By value:

Material	2 story & cellar	2 story	one story	total	
Brick	4- $9,200	3 - $ 4700	15- $ 20,700	22	$ 20,700
Stone		1 - 800	2 - 1,400	3	2,200
Wood		6 - 8,200	56 - 16,450	62	24,650
Total	4 - $9,200	10 - $ 13,700	73 - $ 38,550	87	$ 47,550

Both school houses were one-story frame buildings, one measuring 40 by 20 feet, was valued at $ 550 and the other, 24 by 16 feet in size, was valued at $ 250. Total Value-89 bldgs. $ 48,350.00

In 1823 115 families were housed in 84 Armory Dwelling Houses. Number of armorers in 1823 was 253 men.

TYPES OF ARMORY DWELLING HOUSES, JANUARY 1, 1843

Materials Built of	One-Story Houses	Two-Story Houses	Total No. of 1843 A.
Wood	74	9	83
Stone	15	18	33
Brick	15	38	53
Total:	104	65	169

A. From National Archives Record Group 217, 2nd Auditor's Account, 3rd Series, File 1934, Rent rolls for period ending December 31,1844, with one house, Dwelling No. 34, one-story, wood, which was demolished in 1843, added to the December 31,1844 total of 168 houses.

TYPES OF ARMORY DWELLING HOUSES, DECEMBER 31, 1850

Materials Built of	One Story Houses	Two-story houses	Total No. of Houses (B)
Wood	49	9	58
Stone	10	19	29
Brick	15	39	54
Total	74	67	141 (C)
Value of Houses:			$ 78,550.00 (C)

In 1850 there were 15 "Free Houses": Three school houses (64, 96 and 102); one Methodist Parsonage (144), one armory office(1), and 10 dwellings occupied by clerks, inspectors, and the master armorer(2, 16, 103, 107, 112, 119, 140, 177, 179, and 180). 110 houses were rented by 119 armory workmen; six houses were rented by other than armory employess; and ten houses were vacant. Total, 141 houses(including the armory office Bldg. No. 1).

The estimated value of these 141 building in 1850 was $ 81,550.00.

"LIST OF DWELLING HOUSES AT HARPER'S FERRY, DECEMBER 31, 1850."(A)

Value of each house in class	Class	Brick 2-story	Brick 1-story	Stone 2-story	Stone 1-story	Wood 2-story	Wood 1-story	Total of Houses in class
$ 2,700	1	3 (1)						3
2,500	2	0						0
2,000	3	3		4				7
1,200	4	1		2				3
900	5	8						8
800	6	15		1				16
600	7	4		3		1		8
500	8	1	1	4	1	2	3	12
450	9	1	1	1	1	2	5	11
400	10	0	4	1		1	5	11
300	11	1	2	1	4	1	10	19
250	12	1	6		1	5		13
200	13	1	1	2	2		7	13
150	14						3	3
100	15						3	3
50	16						8	9
Total:	-	39	15	19	10	9	49	141 (B)
Estimated Value	-	$ 38,600	$ 4,850	16,550	2,800	4,450	11,300	$ 78,550

Figures do not include Commanding Officer's House, brick, 2 story, and Paymaster's Quarters, brick, 1 story, built in 1846-48 at a cost of $ 21,708.80.

(A) from National Archives, R.G. 153, Military Reservation File, HFNHP Photostatic Collection, Map Case, Drawer No. 4.

(1) One of the two-story brick houses is the Old Superintendent's House in the Musket Factory Yard, which since 1848, had been used as the Armory Office Building. Not included in the list is the Old Supt."s Office and Old Pay Office, both 1-story brick houses that were located on Arsenal Square.

B. From "List of Dwelling Houses belonging to the United States at Harpers Ferry, December 31,1850(National Archives R.G. 153, Judge Advocate General, Abandoned Military Reservation File No. 34,-Harpers Ferry NHP Photostatic Collection, Map Case Drawer No. 4.

During 1851 17 of the old Armory Dwelling Houses were demolished, leaving 124 old residences standing on December 31, 1851 that were valued at $ 78,200.

Number and Type of Armory-Owned Dwelling Houses Standing on April 19, 1861.

Materials Built of:	One-Story Houses	Two-Story Houses	Total No. of Houses	1852 Value
Wood	1	1	2	$ 650.00
Stone	1	10	11	11,700.00
Brick	0	20	20	17,500.00
Total:	2	31	33	$ 29,850.00

PART I

A DESCRIPTIVE CATALOG AND DIRECTORY OF 188 ARMORY-OWNED DWELLING HOUSES OF THE U.S. ARMORY AT HARPER'S FERRY, VIRGINIA

1841 to 1852

The creation of this town directory for Harpers Ferry for the years 1841 to 1852 is due in large part to the actions of Major Henry K. Craig, Superintendent of the Harper's Ferry Armory, who, in August 1841, ordered Armory painter John P. Kennedy to paint numbers on each public dwelling house for identification purposes and further directed that these house numbers were to be utilized in the Armory rent rolls. Kennedy completed his task during August and was paid $ 10.00 for his services on September 2, 1841.[1] This set of house identification numbers was retained in use in the rent rolls from 1841 to about 1859, when the few (33) remaining Armory-owned dwelling houses were given a new set of identification numbers. Because of the 1841 house numbers used in the rent rolls, it is possible to determine who was living in each house from 1841 to 1851. Rent rolls prior to October 1,1841 have no house identification numbers and rent rolls for the period January 1,1852 to April 18, 1861 were destroyed by the staff of the National Archives during the 1940's in order to save space.

The sources of information for this directory are as follows:

1. For 1841: "Rent Roll- Statement of Dwelling Houses belonging to the United States at Harper's Ferry Armory, and of the Rents due thereon on 31st March 1841," National Archives Record Group 217, 2nd Auditor, 2nd Series, File No. 6195, Washington, D.C.

2. For 1844 : From "RENT ROLLS-Statement of Dwelling Houses Belonging to the United States, at the National Armory, Harper's Ferry, Va., and of the amount of Rents due thereon, on the 31st December 1844." National Archives R.G. 217, 2nd Auditor, 3rd Series, File 1934.

3. For 1846: "RENT ROLL- Statement of Dwelling Houses belonging to the United States, at the National Armory, Harper's Ferry, Va., and of the amount of Rents due thereon on the 31st December 1846," from National Archives R.G. 217, 2nd Auditor, 3rd Series, File 4967.

4. For 1849: "List of United States Dwelling Houses at Harpers Ferry, 30 June 1849," National Archives material on Harpers Ferry National Historical Park Microfilm Reel 18, Volume 12, pp. 1184-1191. Includes data for 1848.

1. National Archives Record Group 217, Records of the U.S. General Accounting Office, Washington, D.C. Records of the Second Auditor of the Treasury Department, Second Series, File No. 6465, Voucher No. 49. The numbers painted on the houses in 1841 conformed to the numbers then in use in the rent rolls.

5. For 1850: "List of Dwelling Houses belonging to the United States at Harper"s Ferry, December 31, 1850," National Archives Record 153, Judge Advocate General, Abandoned Military Reservation File No. 34. Copy in Harpers Ferry NHP Photostat Collection, Park Map Case, Drawer No. 4.

6. For 1851 and 1852: "List of Dwelling Houses at Harper's Ferry Per Inventory June 30,1851, Corrected to December 31, 1852," National Archives, on Harpers Ferry NHP Microfilm Reel 18, Volume 12, pp. 1177-1183.

Location of most houses sold, 1852:

7. Legend Exhibiting the Corresponding Numbers of the Houses, as Per the Inventory of the 30th June 1852, with the Lots of Land as per Brown's Map of the same, Where Correspondence exists (, and in other cases, an Approximation, a printed broadside or one sheet, printed at Knodles Extensive Book & Job Office, Boonsboro , Maryland. No date, but 1852. From National Archives R.G. 156. War Department, Ordnance, Letters - H-330, August 28, 1852. Copy in Harpers Ferry NHP Photostat Collection, Park Map Case, Drawer No. 3, Map No. 82.

8." Appraised Value of Lots & Houses Occupied by Armory Workmen, Harper's Ferry Armory, August 21, 1852," and "Account Sales at Valuation, Lots and Dwelling Houses- Harper's Ferry Armory, 31 August, 1852," National Archives Material from Harpers Ferry NHP Microfilm Reel 24, Volume 7, pp.609-11 and 616-617..

9. Data on 33 Armory-owned Dwelling Houses of 1859-61 period in 1865: From Inspection Report of Brigadier General Edward D. Ramsay to Brigadier General A. B. Dyer, Chief of Ordnance, July 27, 1865. From National Archives Record Group 156; Copy in Harpers Ferry NHP Photostat Collection, Park Map Case, Drawer No. 10.

10. Data on deeds for 54 Armory Dwelling Houses sold in 1852: National Archives Record Group No. 121, Public Buildings Service, Entry No. 76, Washington, D.C. "Deeds from United States, Harpers Ferry, Ordnance Department,"(2 volumes), Volume I.

11. Data on deeds for Armory Dwelling Houses sold 1869-1880: National Archives R.G. 121, Public Buildings Service, Entry No. 76, Washington, D.C. "Deeds from United States, Harpers Ferry, Ordnance Department,"(2 volumes), Volume II.

12. Data on Deeds for Armory Dwelling Houses sold in 1884: National Archives R.G. 121, Public Buildings Service, Entry 58, Washington, D.C. :Warrenty Deeds to Land Conveyed by the Ordnance Department, 1830-1827." (4 vols.), Volume III, pp. 555-626.

SECTION A

ARMORY DWELLING HOUSE NO. 1, U.S. MUSKET FACTORY YARD.

ARMORY DWELLING HOUSES No. 2 to 52, Located Along Shenandoah Street and Between that Street and the Shenandoah River.

Note: The brick Armory Dwelling Houses along Shenandoah Street were all probably constructed prior to 1830.

MAP NO. 1

MAP of HARPER"S FERRY Shewing the Location of the Winchester and Potomac Rail-road, Map No. 2- 1835. Drawn by Lieuts. White, Allen, and R.S. Smith, U.S. Army under the Direction of James Kearney, Lt. Col. and T.E., Scale 100 feet to one inch. Approved by President Andrew Jackson, 27th January 1835."

National Archives Record Group 77, Records of the Office of the Chief of Engineers, Fortifications Map File, Drawer 150, Sheet 82, part 2, in Cartographic Division, Washington, D.C.

Harpers Ferry NHP Park Maps 28, 29, and 30, in Map Case, Drawer No. 12.

Armory dwelling houses have been marked by Charles W. Snell with their probable 1841-1859 identification rent roll numbers.

Buildings numbered by the engineers in 1835 were as follows:

1. Carriage House of Supt., value $ 40. [on Arsenal Square].

2. Carriage House and Stable of the Paymaster, value of $ 50. [located adjacent to House No. 43].


3. Carriage House and Stable of Master Armorer, value $ 150. [located on east side of Globe Inn Alley, near House 44].

4.(or A)-A Armory Dwelling House on which George F, Butler has a claim for $ 140 in improvements he made to the house. Total value $ 240. "House cannot be removed." [Located on Koonce's Lane in middle of right of way of railroad]. This was a frame house and kitchen.


Arsenal Square(Block A, Shenandoah Street, westward via Blocks B, C, D, E, and F, to Virginius Island.

The locations of Armory Dwelling Houses No. 27,28,29, and 51 on this map are largely hypothetical.

13A


Shenandoah Street.
Potomac St.
Wagon's Bridge
Fire Engine house? Lot 11
Lot 12
Supt's Office
National Hotel
Harpers Ferry Hotel- Lot 15
Lot 50
Lot 51
Lot 49
Lot 48
Bldg 40
Free Church
Catholic Church
Bldg. 45
Small Arsenal
Supt.'s Old Office
Stock House
Lot 2
Old Arsenal
Lumber Shed
Pay Office
Armourer
Bldg. 35
Globe Inn
Supplies
Koontz's Lane
Landing
Ware house--
Frame stables, (Armory).
Proof House
Frame Stables (Private)
Slaughter House(?)
Iron(7), 1834
Quarters 1808-09 enlarged, 1828-29
Line between U.S. and Va.
N

MAP


Magnetic
Mud
Foot bridge
Armory frame stables
Private stables, frame.
slaughter house
Kearney's Lane
26
25
24
23
22
21
20
19
18
17
16
15
14
13
12
11
10
9
8
6
27
28
29
51
52
49-48
47
46
50
35
40
41
42

MAP NO 2

MAP A

"Plot of Harpers Ferry Exhibiting the limits of the ground requisite for the passage of the Winchester & Potomac Rail Road through the Town. Scale 100 Feet to the Inch." Undated map, but completed by engineers of the railroad company prior to August 12,1834.

National Archives Record Group No. 77, Records of the Office of the Chief of Engineers, Fortifications Map File. Drawer No. 150, Sheet 78, Part 1, Cartographic Division, Washington, D.C.

Harpers Ferry NHP Map No. 24, Park Map Case, Drawer No. 12.

Shows area of Shenandoah Street from Arsenal Square(Block A, Shenandoah Street) at right, westward via Blocks B, C, D, E, and F, to Virginius Island.

The Armory Dwelling Houses have been marked by Charles W. Snell with their probable 1841-59 rent roll identification numbers. The locations of Houses No. 27, 28, 29, and 51 on this map are largely hypothetical.

Buildings numbered by the engineers in 1834 were as follows:


1. Frame carriage house of the Supt.(Arsenal Square, south of the large arsenal.

2. Carriage House and Stable of the Paymaster, frame(located just west of House No. 43, the Paymaster's Quarters.).

3. Carriage House and Stable of Master Armorer, located on east side of Globe Inn Alley.

4. Frame house and kitchen, fence, stable, privy, and smoke house on which George F. Butler, as of October 1831, had a claim of $ 140.00 for the listed improvements he had made to the house and lot. Total value of house, $ 240. House located on west side of Middle Alley, directly in railroad company's right of way.

Note that Map A is not as complete as "Map No.2-1835" of the same area. Houses No. 9, 39, 40, 41, and 42, shown on Map 2, do not appear on Map A.



PLOT OF HARPERS FERRY

14B

Shenandoah Street

Winchester & Potomac R.R.R.

N 85° 30 E.

Rod Alley

Channel dividing Foot Bridge

Harpers Ferry & Virginia

Back Lane

Armory frame stables

Frame Stables private

Rope Ferry

Small Arsenal

Office

Pay Office

Master Armorer

Arsenal

Gate

Main Alley

East Alley

1811 Warehouse

slaughter house

Shenandoah River

26 25 24 23 22 21 20 19 18 17 16 15 14 13 12 11 10 9 8 6 5 4 3 2 27 28 29 51 52 50 49 48 47 46 45 44 43

PLOT

MAP NO. 3

MAP OF HARPER'S FERRY(1848-51)

Prepared in Compliance with Letter to Major(John) Symington, April 22, 1848,' Drawn by S. Howell Brown in 1848. The section of the map relating to Virginius Island was revised and updated by Superintendent Symington(in red inck) in January 1851. Scale 165 feet to inch.

Original linen map, only existing copy is Harpers Ferry NHP Map No. 77, in Park Map Case, Drawer No.4.


While Brown fails to include the numbered Armory Dwelling Houses on this detailed map, he does indicate the house lot system and streets as they existed in 1848.

Section of Brown's 1848 map showing the Shenandoah Street area.

Armory Dwelling House numbers have been added to the map by Charles W. Snell. The lot or yard system for the houses, however, is by S. Howell Brown.

Brown's Legend reads as follows:

A. The Presbyterian Church.
B. The Catholic Church.
H. St. John's Protestant Episcopal Church(Park Bldg. 48A)
P. Pumps.
T. Public Stables(New,built in 1847-48, Lot 2, Block F,Shenandoah Street).
U. Market House (New, built 1846-47, on Block B, Shenandoah St.).
Z. Old Stables, Wood Yard, &c.(Block G, Shenandoah Street.
X. "Old Office" (on Lot 6, Block D, Shenandoah Street).


Pay Master's Quarters
Public Grave Yard
62
64
65
H.
B
Jefferson Rock
N
= Armory Stable
site of Bldg. No. 45
30
31
32
33
35
36 37
A
38
39 40 41 42
7
Shenandoah STREET
Old Powder Magazine
2
3
5
6
8
9
10
11
12
13
14
15
16
17
18
19
20
21
22
23
24
25
26
Pumps
W & ARR
11
52
49-48
47
46
45
V
43
P
Virginia Island
3
6
Z
Shenandoah
RIVER
153

MAP NO 4


"Map of Harpers Ferry, 1852,
by S. Howell Brown," Approved by Col. Benjamin Huger,
Superintendent, Harper's Ferry Armory, April, 1852.
Scale 165 feet to the inch. The working copy made by
A. M. Kitzmiller, Superintendent's Clerk. This MS linen
map is the only known extant copy of Brown's 1852 map.

Harpers Ferry NHP Map No. 89, Park Map Case, Drawer No. 3.

On June 10, 1852, Secretary of War C. M. Conrad approved this map or plat on which surveyor S. Howell Brown laid out 312 house lots from the U.S. Armory land at Harpers Ferry. These were offered for sale on August 31 and September 1-2, 1852.

The map shows the new street systems that were established and all the public lands and boundaries thereof that were reserved from the 1852 sale for continued U.S. use. Two hundred and twenty-four building lots were sold in 1852.

Section showing lots offered for sale and land reserved for U.S. use, 1852- 1869.


GRAVE YARD.
ST.
MARKET
HAMILTON
WOOD
ROAD
"MAP OF HARPERS FERRY
by
S. Howell Brown D.S.
1852"
N
Scale of Perches
0 10 20 30
Scale of Feet

MAP NO. 5

" Map of HarperS Ferry - Plat of the
Harpers Ferry Armory Property laid off into lots
for sale in pursuance of the Act of December 15th, 1868.
Approved November 16th 1869 by Wm. W. Belknap, Secretary of
War. Map completed by S. Howell Brown, Nov. 1,1869.
Scale 165 feet per inch."

Copied by Architect Archie W. Franzen from an original linen drawing in color, which in turn had been copied from the original by Pusey & Jone Company, Nov.26, 1901.

Harpers Ferry NHP Map No. 83, Map Case, Drawer No. 10.

On his 1852 map, Surveyor S. Howell Brown had subdivided part of the U.S. Armory lands in to 312 building lot. In 1869 he subdivided the remaining undivided U.S. owned land into 188 additional building lots, thus bringing the grand total of lots to 500. Two hundred and twenty-four of these lots had been sold in 1852; 31 additional lots were donated in 1869, and the balance were to be offered at public auction in December 1869.

Section of map showing Shenandoah Street area.

The probable locations of all Armory dwelling houses standing from 1841 to 1852 has been indicated.

17 A

LAY ST.
YOUNG ST.
ST.
M.P.CH.
CHURCH
M.E.CH.
HIGH ST.
ALLEY
RER COLLEGE
HARPER
GRAVE YARD
4 ACRES
P.E.CH
EE
DD
A
B
C
D
E
F
G
H
CATHOLIC SCHOOL LOT
PRESBYTERIAN CHURCH
JEFFERSON'S LOT
MARKET
MARKET HOUSE
BRIDGE ST.
WOOD ST.
HAMILTON ST.
FERRY LOT
YORK
ROAD
P.P.C.P.
SCH

ARMORY DWELLING HOUSE NO. 1 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , MUSKET FACTORY YARD, line of workshops. Eastern head of southern

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	brick	(2)	(slate)	-		Edward Lucas, Jr. Supert.	Free	Free	
Dec. 31, 1844	Brick	-	-	-	-	Richard Parker, Paymaster	Free	Free	
Dec. 31, 1846	Brick	-	-	-	-	Richard Parker, Paymaster	Free	Free	
June 30, 1849	Brick	2		1	2,700	remodelled in 1847-48 for use as Armory Central Office Bldg.	-	-	
Dec. 31, 1850	Brick	2	slate	1	$ 2,700	Central Office Bldg.	-	-	
June 30, 1851	Brick	2	slate	1	$ 2,700	Central Office Bldg.	-	-	
June 30, 1852	Brick	2	slate	1	$ 2,700	Central Office Bldg.	-	-	

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	not sold	none	not sold in 1852

Photo HF-628(oil painting ca. 1826); HF- 51 (1857 lithograph); HF-27(1865 photo).

Remarks: Armory Dwelling No. 1 was designed and erected by Superintendent James Stubblefield in 1808-09 as a two-story brick residence, about 36 by 30 feet, with a cellar kitchen and wood shingle gable roof. The house served as the residence of the Armory superintendents from 1808 to 1844 and then of Paymaster Richard Parker from 1844 until his death in 1847. In 1828 a large brick wing, which included a kitchen, was added to the east gable end of the main house at a cost of $ 2,429.75. The main house had been valued at $ 3,000 in 1821. The roofs were slated and copper gutters and downspouts added in 1841. In 1847-48 the old residence was remodelled at a cost of $ 850 for use as a central office building for the armory and it served this purpose from 1848 to April 18, 1861. The U.S. sold the building to Thomas H. Savery on October 22,1884 and he demolished the structure ca. 1887-89.

NPS Land

House No. A (1852)
House No. 2(1859-65)

ARMORY DWELLING HOUSE NO. 2 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No.3 , Shenandoah Street (PARK BLDG. No. 34-35):
S. Howell Brown's 1852 Map of Harpers Ferry - on Lot 4 in 1852.
S. Howell Brown's 1869 Map of Harpers Ferry - on Lot 3 in 1869.

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick			-		Benjamin Moor, Master Armorer	Free	Free	
Dec. 31, 1844	Brick					Benjamin Moor, Master Armorer	Free	Free	
Dec. 31, 1846	Brick					Benjamin Moor, Master Armorer	Free	Free	
June 30, 1849	Brick	2		1	2,700	Benjamin Moor, M. Armorer	Free	Free	
Dec.31, 1850	Brick	2	slate	1	$ 2,700	James H. Burton,Master Arm.	Free	Free	
June 30, 1851	Brick	2	Slate	1	$ 2,700	J. H. Burton, Master Armorer	Free	Free	
June 30, 1852	Brick	2	Slate	1	$ 2,700	James H. Burton. M.A	Free	Free	

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	None	none	not sold in 1852

Photo HF-361 (1865). HF-141(1865);HF-92(1892-95),

Remarks: House erected by Dr. Joseph Annin in 1812, under a lease from the U.S., for use as his drug store and residence. The two-story brick house had a cellar kitchen and wood shingle gable roof. In 1821 the U.S. paid Annin $ 2,500 for the structure. The dwelling served as the residence of the Master Armorer from 1818 to 1858. In 1821 the house was two stories, with cellar, measured 36 by 30 feet, and was valued at $ 2,500. In 1827 a one-story brick kitchen wing, 22 by 20 feet was added to the southwest rear corner of the main house at a cost of $ 500. In 1837 the residence was repaired and enlarged at a cost of $ 307.13, when six dormer windows were installed in the gable roof to make the edifice 2½ stories. The roof of the house was probably slated in 1833. The brick wing was also apparently enlarged in 1837. In 1850 $ 174.12 was spent repairing and painting the house and lightning rods were attached to the building in 1851. Property sold by U.S. to James C. McGraw & family on December 6,1869 for $1,200,deed issued Feb.5,1880

NPS Land

ARMORY DWELLING HOUSE NO. 3 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 1, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry. House No. 3 fronted on Market Street
S. Howell Brown's 1869 Map of Harpers Ferry. and set in rear(south) of House No.4.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick & Stone					Richard Parker, Paymaster	Free	Free	
Dec. 31, 1844	Brick Stone					James Fitzsimmons William H. Moor, Inspector	20.00 Free	20.00 Free	
Dec. 31, 1846	Brick					Jno.E.P. Daingerfield, Clerk	Free	Free	
June 30, 1849	Brick	2	includes Bldg.4	1	2,700	Joseph Smith-store part A. M. Kitzmiller, Clerk James Garry -store part	9.00 Free 7.50	Free	
Dec.31, 1850	Brick	2	slate	1	$ 2,700	Daniel Young-part of (armorer) A.H. Vanhorn " " (laborer) James Young " "	10.50 25.00 7.50	10.50 25.00 15.00	value includes House 3 and 4.
June 30, 1851	Brick	2	slate			James Geary A. H. Vanhorn			" " " all on Lot 1.
June 30, 1852	Brick	2	slate	1	$ 2,700	James Geary A. H. Vanhorn			" " "

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Public auction 9/1/52	$ 2,505.00	Edward Lucas, Jr.	December 12, 1856	Purchase included Houses No. 3 and 4, both on same lot.

Photos: HF-249(18570; HF-68(1858 or 1883?); HF- 361(1865), HF-99(1892-95).

Remarks: House No. 3, a two and one-half story brick boarding house and tavern, about 50 by 20 feet, was erected by William Graham about 1818-20, together with House No. 4. Graham leased this property: House No. 4 as a store and dwelling and House No. 3 as a tavern and boarding house. From 1832 to 1835 House No. 3 was leased by John Fitzsimmons for use as a tavern which was known as the "Globe Inn". On July 21,1837, the U.S. Armory purchased Houses No. 3 and 4 from the William Graham Estate for $ 4,000. In 1838, on his arrival in Harpers Ferry, Paymaster Richard Parker took up residence in House No. 3 on Shenandoah Street rather than the old Paymaster House(See House No. 43), which dated from 1802 and was located on the bank of the Shenandoah River on Lot No. 5, Block B, Shenandoah Street. Parker lived in House 3 from 1838 to 1844, when he took up residence in House No. 1.

NPS Land

ARMORY DWELLING HOUSE NO. 4 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 1, Shenandoah Street

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

House No. 4 fronted on Shenandoah Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John Rockenbaugh (merchant)	31.25	31.25	
Dec. 31, 1844	Stone - store room					Thomas Hughes (merchant)	10.00	20.00	delinquent $ 10.(
Dec. 31, 1846	Store room part of					Thomas Hughes (merchant)	10.00	10.00	
June 30, 1849	Part of Bldg.3 Stone			1	2,700	Thomas Hughes (merchant)	10.00		P.O. Littlejohn owed 86.95; Jeremiah Stevens owed19
Dec.31 1850	Brick (sic)	2	slate	1	2,700	T. J. W. Sullivan (merchant) tailor).	15.00	15.00	had been rented by P.O.Littlejohn who owed $ 86.96
June 30, 1851	Brick (sic)	2	slate			T.J. Earnshaw (& Benjamin Ott) Dry Goods merchants).			
June 30, 1852	Stone	2	slate	1	2,700	included as part of House No. 3-both on same lot.			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	Auction 9/1/52	$ 2,505.00	Edward Lucas, Jr.	December 12, 1856	Purchase included Houses 3 and 4, both on Lot No. 1

Photos: HF- 361(1865); HF- 82 (1889); HF-111(1889); HF-99(1892-95).

Remarks: House No. 4, a 2½ story stone store and dwelling about 43 by 33 feet, was erected by William Graham about 1818-20. From ca.1820 to 1824, leased to Daniel A. Wood as dry goods store and dwelling; 1824-27, dry goods and grocery store of H. K. Wartman; 1828-30, store of Hamilton and Lewright, clothing, shoes, hats; 1830-34, dry goods and grocery store of Thomas Hughes; 1835-39 dry goods and grocery store of John G. Wilson. On July 21,1837, the U.S. Armory purchased the rights to Houses No. 3 and 4 from the William Graham Estate for $ 4,000. Jeremiah Stevens leased House 4 as his dry goods, grocey, and liquior store from 1839 to March 1840. John Rockenbaugh's "White Store", dry goods, hardware and liquor, located in 4 from April 1840 to Dec. 1841. 1842 to April 1843, dry good store of P.)O. Littlejohn, who left owing $ 86.95 in rent

NPS Land

ARMORY DWELLING HOUSE NO. 5 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 2, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					George Reed, Engr.	25.00	33.33	
Dec. 31, 1844	Brick					John E. P. Daingerfield, Clerk	Free	Free	
Dec. 31, 1846	Brick					William H. Moor, Inspector	Free	Free	
June 30, 1849	Brick	2		6	800	Benjamin Russell, laborer	12.50	12.50	
Dec. 31, 1850	brick	2	wood shingle	11	300.00	Ralph Cleveland, armorer	12.50	12.50	
June 30, 1851	Brick	2	shingle			Ralph Cleveland			
June 30, 1852	Brick	2	shingle		650.00	Ralph Cleveland			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 650.00	Ralph Cleveland	December 7, 1858

Photos: HF-82(1889); HF-99(1892-95).

Remarks: A two-story brick house about 25 by 28 feet, with wood shingle gable roof. Constructed in period 1811-33. Ralph H. Cleveland, a machinist at the Armory, was born in England and was 37 years old in 1860. The brick house was demolished by 1892.

House fronted on Shenandoah Street.

NPS Land

ARMORY DWELLING HOUSE NO. 6 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 3, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Milton Garrett (merchant)	15.00	15.00	departed owing U.S. $ 37.50.
Dec. 31, 1844	Brick					Henry Stipes, Armorer	14.35	14.35	
Dec. 31, 1846	Brick					Henry Stipes, "	14.35	14.35	
June 30, 1849	Brick	2		7	600.00	Henry Stipes, "	14.50	14.50	
Dec. 31, 1850	Brick	1	wood shingle	10	400.00	Henry Stipes, "	12.00	12.00	
June 30, 1851	Brick	1				Benjamin Stipes,			
June 30, 1852	Brick	2*	wood shingle		600.00	Benjamin Stipes			m *see HF- 82 photo, 1869.

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 600.00	Catherine E. Stipes, wife of Henry Stipes	Feb. 20, 1868 To Henry & Catherine Stipes

Photos: HF-247(1857); HF-68(1858 or 1883); HF-82(1889); HF-99(1892-95).

Remarks: 2-story brick house, 24 feet wide and 17 feet deep, with wood shingle gable roof. Erected 1811-33 as dwelling. House was still standing in 1932.

Milton Garrett had rented House No. 6 in January 1840 and opened a grocey store. He also kept for hire two horses and wagons, carts, and sleights. He departed owing the Armory $ 37.50 in unpaid rent.

House fronted on Shenandoah Street.

NPS Land

ARMORY DWELLING HOUSE NO. 7 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. 1, North of Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry PARK BLDG. No. 45

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Henry Ward, clerk to Supt. William J. Stevens (merchant) John G. Wilson (part of)	Free 31.25 10.00	Free 31.25 10.00	Upper floors first floor-stor Post Office(1st f
Dec. 31, 1844	Stone					Henry Ward, Clerk David Koonce, (merchant)	Free 31.25	Free 57.21	Upper floors, store, 1st floor
Dec. 31, 1846	Stone					Ward, George H., clerk vacant (Jacob Brown owed $18.00)	Free (David Koonce owed 57.21)	Free	Upper floors store, 1st floor
June 30, 1849	Stone	2		2	2,500	David Koonce David McFarden	50.75	57.21 30.00	Jacob Brown owed 18.00.
Dec. 31, 1850	Stone	2	wood shingle	3	2,000	Charles W. Button, store J. T. Whaley, armorer	18.75 20.00	18.75 20.00	Post Office, saddl & harness maker
June 30, 1851	Stone	2	shingle			Charles W. Button-saddle maker John Price, dry goods and grocery store. Jessie Grimes, armorer			
June 30, 1852	Stone	2	shingle	3	2,000	Charles Button John Price Jessie Grimes			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	nold sold	Not sold in 1852

Photos: HF- 249(1857); HF-361(1865); HF-82(1889); HF-99(1892-95).

Remarks: Large 2½ story stone bldg. 50 feet 7 inches by 35 feet 4 inches with wood shingle gable roof, erected by John G. Wilson in 1825-26. First story contained two stores and the upper floors were a dwelling, used by John G. Wilson from 1826 to 1829. From April 1830 to March 1837, the upper floors were Stage Coach Inn, operated by James Stephenson and his wife Ann, and Fontaine Beckham. About 1834, a 16 foot long 2½ story addition was made to the east end of the bldg. The Stephensons purchased house no. 7 in July 1834 and on March 25, 1837, sold it to the Armory for $ 3,000. First story contained, 1826-30-dry goods store of Maslin & McKim; 1830-31, D.G. Store of Ford & Chapman; 1831-32-D.G. S of Smith & Patteron; 1832, D.G.S of Samuel K. White; Sept.1836- February 1839, sheet metal shop of tinsmith Benjamin M. Snook . House renumbered as Armory Dwelling No. 3 in 1860. The house and lot were sold by the U.S. to Josiah Cavalier for $ 850.00. The deed was issued on June 1, 1880.

NPS Land

ARMORY DWELLING HOUSE NO. 8 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 4, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					William S. Smith	8.00	8.00	
Dec. 31, 1844	Brick					James Caton	9.20	9.20	
Dec. 31, 1846	Brick					James Caton	9.20	9.20	
June 30, 1849	Brick	1		10	400	Noah Gannon	9.25		owed 30.00
Dec.31, 1850	Brick	2	wood shingled	13	200	Noah H. Gannon +, laborer	9.25	9.25	
June 30, 1851	Brick	2	shingle			Noah H. Gannon +			
June 30, 1852	Brick	2	shingle		400	Noah H. Gannon			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 400.00	Thomas Mathews **	Sept. 5,1856 to John B. Johnson

** Acting for John B. Johnson

Remarks: 1½ story brick house with wood shingle gable roof, erected ca. 1811-33. House about 24 feet wide and 32 feet deep. House No. 8 probably destroyed in 1889 flood. House fronted on Shenandoah Street.

Photos: HF-249(1857); HF-68(1858 or 1883);, HF- 361(1865).

+ or Cannon/.

NPS Land

ARMORY DWELLING HOUSE NO. 9 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 5, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Samuel Shewbridge	9.00	9.00	
Dec. 31, 1844	Brick					Isaac Fleming	10.35	10.35	
Dec. 31, 1846	Brick					Isaac Fleming	10.35	10.35	
June 30, 1849	Brick	1		10	400	Isaac Fleming	10.50	10.50	
Dec.31, 1850	Brick	1	wood shingle	11	300	George P. Marquett	10.50	10.50	
June 30, 1851	Brick	1	shingle			George Marquett			
June 30, 1852	Brick	1	shingle		675.00				

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 675.00	George P. & Emily Marquett	July 26, 1866

Photos: HF-361(1865); HF-68 (1858 or 1883).

Remarks: 1½ story brick dwelling house about 20 feet wide and 32 feet deep, built 1811-33. Wood shingle roof. The house was apparently destroyed in the 1889 flood. Emily Marquett, in 1860, was 38 years old and had been born in Maryland. Value of her personal property was $ 150.00. She had three boys, aged 7, 8, and 12.

House fronted on Shenandoah Street.

NPS Land

ARMORY DWELLING HOUSE NO. 10 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 6A, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Timothy Herrington*	12.50	12.50	
Dec. 31, 1844	Brick					T. A. Herringto n	14.35	17.55	delinquent $ 3.00
Dec. 31, 1846	Brick					T. A. Herrington	14.35	14.35	
June 30, 1849	Stone	2	shingle	8	500	Orison Harrison	14.50		owed U.S. 30.00 in rent
Dec.31, 1850	Stone	2	wood shingle	10	400	Thomas Earnshaw, armorer	14.50	14.50	
June 30, 1851	Stone	2	shingle			Thomas Earnshaw "			
June 30, 1852	Stone	2	shingle		800.00	Thomas Earnshaw			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 800.00	Andrew J. Wright	December 12, 1856

Remarks: Built 1811-21 a two story stone house about 30 feet wide and 32 feet deep, with wood shingle gable roof. House probably destroyed in great flood of 1870 and by 1892 had been replaced by a three-story brick building.

House fronted on Shenandoah Street.
*On August 24,1824, Timothy Herrington was paid $ 301.18 for furnishing the material and building the upper story of a stone dwelling 40 by 24 feet.

NPS Land

ARMORY DWELLING HOUSE NO. 11 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 1, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Adam Brown	8.00	8.00	
Dec. 31, 1844	Brick					Adam Brown	9.20	9.20	
Dec. 31, 1846	Brick					Adam Brown	9.20	9.20	
June 30, 1849	Brick	1		10	400	Adam Brown	9.25		
Dec.31, 1850	Brick	1	wood shingle	11	300	Adam Brown	9.25	9.25	
June 30, 1851	Brick	1	shingle			Adam Brown			
June 30, 1852	Brick	1	shingle		375.00	Adam Brown			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 375.00	Armistead M. Ball	February 20, 1857.

Photos: HF-249(1857).

Remarks:

Built 1811-32, a 1½ story brick house with wood shingle gable roof, about 22 feet wide and 18 feet deep. The house was still standing in 1913. Armistead M. Ball, a master machinist at the Musket Factory, served as Master Armorer of the Armory from November 3,1859 to April 18, 1861. House fronted on Shenandoah Street.

S Land

ARMORY DWELLING HOUSE NO. 12 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 2, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					James Claspy	5.00	5.00	
Dec. 31, 1844	Wood					James Claspy	7.15	7.15	
Dec. 31, 1846	Wood					James Claspy	7.15	7.15	
June 30, 1849	Wood	1	wood shingle	14	150	James Claspy	7.50	7.50	
Dec. 31, 1850	Wood	1	shingle	15	100	James Claspy	7.50	7.50	
June 30, 1851						House demolished and material sold at auction May 31, 1851	-	-	Vacant Lot
June 30, 1852	0				0	Not standing	-	-	

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	leased by U.S.			

Remarks: one-story wood house with wood shingle roof, erected 1811-33, about 22 by 24 feet in size. Demolished in May 1852. Vacant lot then leased by U.S. to the Roman Catholic Church for use as a parsonage lot.

Old house fronted on Shenandoah Street.

NPS Land

ARMORY DWELLING HOUSE NO. 13 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 2, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Michael Gomph	8.00	8.00	
Dec. 31, 1844	Wood					Michael Gomph	14.35	14.35	
Dec. 31, 1846	Wood					Michael Gompf (sic)	14.35	14.35	
June 30, 1849	Wood	2	wood shingle	9	450	Michael Gompf	14.50	14.50	
Dec.31, 1850	Wood	2	shingle	12	250	Vacant			
June 30, 1851						House demolished and materials sold 31 May 1851.			
June 30, 1852	-	-	-	-	0	Vacant lot			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold			

Remarks: Two story wood house with wood shingle roof, built 1811-33, 18 feet wide and about 50 feet deep, fronting on Shenandoah Street. House demolished in May 1851. Vacant lot leased by U. S. to Roman Catholic Church in 1852 for use as a parsonage lot.

NPS Land

ARMORY DWELLING HOUSE NO. 14 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 3, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Jacob Gomph	5.00	5.00	
Dec. 31, 1844	Wood					Jacob Gomph (1 month) John Roderick (2 months)	5.75 5.75	5.75	owed for 1 month then living in House no. 36.
Dec. 31, 1846	Wood					John Roderick	5.75	5.75	Two men traded houses in 1844.
June 30, 1849	Wood	2	wood shingle	9	450	John W. Roderick	5.75	5.75	
Dec.31, 1850	wood	2	shingle	12	250	house vacant			
June 30, 1851						House demolished and materials sold on May 31,1851			
June 30, 1852						vacant lot			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	leased lot			

Remarks: Built 1811-33, a two-story frame house with wood shingle roof, about 28 by 34 feet, fronting on Shenandoah Street. House demolished in May 1851. Vacant lot leased by U.S. for Presbyterian Church for use as a parsonage lot.

NPS Land

ARMORY DWELLING HOUSE NO. 15 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 3, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Benjamin F. Beelers	5.00	5.00	
Dec. 31, 1844	Wood					Lewis E. Gore	5.75	5.75	
Dec. 31, 1846	Wood					William A. Roderick	5.75	5.75	
June 30, 1849	Wood	1	wood shingle	13	200	W. A. Roderick	5.75	5.75	
Dec.31, 1850	Wood	1	shingle	13	200	Vacant			
June 30, 1851						House demolished and materials sold May 31, 1851.			
June 30, 1852						vacant lot			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Lot leased				

Remarks: A one-story frame house with wood shingle roof, about 20 by 28 feet, and fronting on Shenandoah Street. Built 1811-33 and demolished in May 1851. Vacant lot leased by the U.S. to the Presbyterian Church in 1852 for use as a parsonage lot.

NPS Land

ARMORY DWELLING HOUSE NO. 16 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 4, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Philip Hoffman, Inspector *	Free	Free	
Dec. 31, 1844	Brick					Philip Hoffman, Inspector	Free	Free	
Dec. 31, 1846	Brick					Philip Hoffman, Inspector	Free	Free	
June 30, 1849	Brick	2	slate	4	1,200	Philip Hoffman, Inspector	Free	Free	
Dec.31,1 1850	Brick	2	slate	4	1,200	Philip Hoffman, Foreman	Free	Free	
June 30, 1851	Brick	2	slate			Philip Hoffman, Foreman	Free	Free	
June 30, 1852	Brick	2	slate		1,100	Philip Hoffman			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 1,100.00	Philip Hoffman	September 5, 1856.

Remarks: 2½ story brick house about 19 feet wide and 39 feet deep, fronting on Shenandoah Street. Built 1811-33, House No. 16 had a slate roof. The house was still standing, enlarged, in 1936.

*On December 31,1823, Philip Hoffman was paid $ 339.37 for adding an story and also a cellar to a brick house. R.G. 217-1st Series, File 7624, Voucher 164A.

ARMORY DWELLING HOUSE NO. 17 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block D Lot No. 5, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					William Chambers	10.00	10.00	
Dec. 31, 1844	Brick					William Chambers	11.50	11.50	
Dec. 31, 1846	Brick					William Chambers	11.50	11.50	
June 30, 1849	(sic) Stone	(sic) 2		8	500	J. Y. O'Laughlin	11.50	11.50	
Dec. 31, 1850	Brick	1	wood shingle	10	400	J. Y. O'Laughlin	11.50	11.50	
June 30, 1851	Brick	1	shingle			J. Y. O'Laughlin			
June 30, 1852	Brick	1	shingle		500.00	J. Y. O"Laughlin			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 500.00	Joseph Mathews	January 18, 1858

Remarks: Built 1811-33, House No. 17 was a 1½ story brick house with a wood shingle roof, about 21 feet wide and 42 feet deep. The house fronted on Shenandoah Street. The house was still standing in 1932.

NPS Land

ARMORY DWELLING HOUSE NO. 18 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 5, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Samuel Kilham	4.00	4.00	
Dec. 31, 1844	Wood					Daniel O'Boyle	4.60	4.60	O'Boyle left owing $ 9.20.
Dec. 31, 1846	Wood					Joseph Mathews	4.60	4.60	
June 30, 1849	Wood	1	wood shingle	14	150	Joseph Mathews	450	4.50	
Dec.31, 1850	Wood	1	shingle	13	200	Joseph Mathews	4.50	4.50	
June 30, 1851	Wood	1	shingle			Joseph Mathews			
June 30, 1852						House No. 18 demolished prior to August 30, 1852 to create a new street, Tell Street.			sale in order

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	8/31/52	$ 500.00	Joseph Mathews	January 18, 1858. included House	No. 17, brick, & lot.

Remarks: House No. 18, one-story frame house erected 1811-33. Had wood shingle roof, fronted about 42 feet on Shenandoah Street and was about 28 feet deep. The U.S. apparently demolished House No. 18 prior to the August 30, 1852 sale in order to create Tell Street.

ARMORY DWELLING HOUSE NO. 19 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block E Lot No. 1, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John Marquett	15.00	15.00	
Dec. 31, 1844	Brick					William Bilson	17.25	33.60	
Dec. 31, 1846	Brick					John Marquett	17.25	17.25	
June 30, 1849	Brick	2	wood shingle	7	600	John Marquett	17.50	17.50	
Dec.31, 1850	Brick	2	shingle	8	500	W. H. Martin, armorer	17.50	17.50	
June 30, 1851	Brick	2	shingle			Wm. H. Martin			
June 30, 1852	Brick	2	shingle		600.00	Wm. H. Martin			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 600.00	William H. Martin	December 12, 1856

Remarks: Bldg. 19 erected 1811-33, about 19 by 30 feet in size, a two-story brick dwelling with wood shingle roof. The house was destroyed prior to 1913. In 1860, William H. Martin, born in England and 43 years old, was an inspector at the Armory.

The house fronted on the south side of Shenandoah Street.

NPS Land

ARMORY DWELLING HOUSE NO. 20 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 2, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Anthony Storm	5.00	5.00	
Dec. 31, 1844	Wood					John Sheeler	5.75	5.75	
Dec. 31, 1846	Wood					John Sheeler	5.75	5.75	
June 30, 1849	Wood	1	wood shingle	11	300	John Sheeler	6.00	6.00	
Dec.31, 1850	Wood	1	wood shingle	13	200	S. J. Lindsay	5.00	5.00	
June 30, 1851	Wood	1	shingle			House demolished and materials sold 31 May 1851.			
June 30, 1852	vacant lot								

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	leased			

Remarks: House No. 20, a one-story frame house with a wood shingle roof, fronted about 20 feet on Shenandoah Street and was 18 feet deep. Erected 1811-33 and demolished in May 1851.

Vacant Lot 2, Block E, Shenandoah Street, leased to the Harpers Ferry School District, No. 24, by the Secretary of War, on September 3, 1852, as the site for a Free School.

A brick school house was completed on the lot in 1856. This structure was destroyed by Union soldiers during the Civil War. The soldiers used the bricks for build their winter camps.

NPS and

ARMORY DWELLING HOUSE NO. 21 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 3, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Dickeys	5.00	5.00	
Dec. 31, 1844	Wood					John Dickey	5.75	5.75	
Dec. 31, 1846	Wood					John Dickey	5.75	5.75	
June 30, 1849	Wood	1	wood shingle	11	300	John Dickey	6.00	6.00	
Dec. 31, 1850	Wood	1	shingle	13	200	W. W. Roderick	6.00	6.00	
June 30, 1851	Wood	1	shingle			House demolished and materials sold May 31, 1851.			
June 30, 1852	vacant lot								

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	9/1/52	$ 237.00	Michael Doran	November 25, 1854.

Remarks: House No. 21, erected 1811-33, a one-story frame house with a wood shingled roof, fronting on Shenandoah Street about 20 feet by 20 feet in depth. Residence demolished in May 1851/.

This vacant lot was purchased at the public auction held on September 1 and 2, 1852 by Michael Doran, a Harper's Fery merchant. Doran may have erected a dwelling house on the lot prior to the Civil War.

NPS Land

ARMORY DWELLING HOUSE NO. 22 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No.4 , Shenandoah Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Town Pump Lot

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					William Medlars	7.50	0	
Dec. 31, 1844	Stone					George Crowl	8.60	8.60	
Dec. 31, 1846	Stone & wood					Elias Arvin	8.60	8.60	
June 30, 1849	Stone	2	Shingle	9	450	Elias Arvin	8.75	8.75	
Dec.31, 1850	Stone	2	wood shingle	10	400	Abm. Roderick	8.75	8.75	
June 30, 1851	Stone	2	shingle			Abraham Roderick			
June 30, 1852	Stone	2	shingle		400.00	Abraham Roderick			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 400.00	Mary & Anthony Nunnamaker	February 20, 1868

Remarks: Built 1822-33, a 2½ story brick house with wood shingle roof, fronted about 18 feet on Shenandoah Street and was about 22 feet deep. The house was still standing in 1913. In 1860 Mary M. Nunnamker, born in Maryland, was 53 years old. Anthony Nunnamker, born in Virginia, was 30 year old and a armory employee.

NPS Land

ARMORY DWELLING HOUSE NO. 23 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 5, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Rezin Cross *	7.50	7.50	
Dec. 31, 1844	Stone & wood					Reason Cross	8.60	8.60	
Dec. 31, 1846	Stone & wood					Reason Cross	8.60	25.80	delinquent 17.20
June 30, 1849	Wood	2	shingle	9	450	James T. Adams	8.75	8.75	
Dec.31, 1850	Wood	2	wood shingle	10	400	J. T. Adams	8.75	8/75	
June 30, 1851	Wood	2				James C. Claspy			
June 30, 1852					550.00	James C. Claspy including also House No. 24 which stood on same lot.			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	8/31/52	$ 550.00	William Snook	February 20, 1857	

Remarks: House No. 23, a two-story frame and stone dwelling with a wood shingle roof. With House No. 24, House No 23 fronted about 38 feet on Shenandoah Street and was 20 feet deep. House No. 24 was a one-story frame house with a wood shingled roof.

A double or duplex house. Houses 23-24.

* "R. Cruzen" filed an 1829 claim for $ 299.98 for erecting a wooden house in 1829.

NPS Land

ARMORY DWELLING HOUSE NO. 24 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 5, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Samuel J. Lindsay *	7.50	7.50	
Dec. 31, 1844	Wood					Addison Pollock	8.60	44.20	
Dec. 31, 1846	Wood					William Snook	8.75	8.75	
June 30, 1849	Wood	1	shingles	9	450	William Snook	8.75		
Dec. 31 1850	Wood	1	wood shingle	9	450	William Snook	8.75	8.75	W.A.J.Pollock Est. owed $ 86.06 rent.
June 30, 1851	Wood	1	shingle			William Snook			
June 30, 1852					550.00	House No. 24, with House 23, both on same lot, jointly valued at $ 550.00			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 550.00	William Snook	February 20, 1857 includes House No. 23.

Remarks: House No. 24, built 1811-33, a one-story frame house with wood shingled roof. With House No. 23(2-stories), fronted about 38 feet on Shenandoah Street and were 20 feet deep. A double or duplex house.

* Samuel J. Lindsay was paid $ 83.42 on December 24, 1823 for making repairs to a wooden house.R.G. 217-1st Series, File 7624-Voucher 100A.

NPS Land

ARMORY DWELLING HOUSE NO. 25 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block F Lot No. 1, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Armst. Ball	15.00	15.00	
Dec. 31, 1844	Brick					Armistead M. Ball	17.25	17.25	
Dec. 31, 1846	Brick					A. M. Ball	17.25	17.25	
June 30, 1849	Brick	2	shingle	6	800	A. M. Ball	17.50	17.50	
Dec. 31, 1850	Brick	2	shingle	7	600	Durett Coates	17.50	17.50	
June 30, 1851	Brick	2				Durett Coates			
June 30, 1852	Reserved from sale in 1852 for use as Armory Dwelling House. Henry Reed(?)								

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	0	none	reserved for U.S. use

Remarks: Built 1811-33, a 2-story brick house with wood shingle roof, fronting about 38 feet on Shenandoah Street and 21 feet deep. The house was used as an Armory dwelling house from 1852 to 1861 and about 1859 was renumbered as Armory Dwelling House No. 4. In July 1865 it was described as "Dwelling House No. 4, two-story, brick, located on Shenandoah Street - In bad condition." The house may have been standing in 1913. The U.S. sold House No. 25, or No.4, with Lot No. 1 to Alexander Murphey on May 22, 1880 for $ 250.00 and issued the deed to Murphy on June 1, 1880.

NPS Land

ARMORY DWELLING HOUSE NO. 26 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block F Lot No.1 , Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Philip Engles	10.00	10.00	
Dec. 31, 1844	Brick					Philip Engle	11.50	11.50	
Dec. 31, 1846	Brick					Philip Engle	11.50	11.50	
June 30, 1849	Stone (sic)	2(sic)	shingle	8	500	Philp Engle	11.50	11.50	
Dec.31, 1850	Brick	1	shingles	10	400	George Nunnamkaer	11.50	11.50	
June 30, 1851	Brick	1	shingles			George Nunnemaker			
June 30, 1852						George Nunnamaker House No. 26 reserved from 1852 sale for use as dwelling house.			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Reserved	0	none	reserved for U.S. use.

Remarks: Built 1811-33, a one-story brick house with wood shingled roof, fronting about 50 feet on Shendndoah Street and 40 feet deep(according to 1834 maps). House reserved from U.S. sale of 1852 and was used as an armory dwelling house from 1852 to about 1859, when House No. 26 was demolished by the Armory.

Lot No. 1, Block F, Shenandoah Street, with Armory Dwelling House No. 25, purchased by Alexander Murphy for $ 250.00 from the U.S. in May 1880. U.S. deed to property issued June 1,1880.

NPS Land

ARMORY DWELLING HOUSE NO. 27 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block D. Lot No. 5, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					James Rollins	5.00	5.00	
Dec. 31, 1844	Wood					Wm. Steadman	1.25	1.25	
Dec. 31, 1846						House torn down in 1846			
June 30, 1849						Broken up in 1846.			
Dec. 31, 1850	wood	1	shingle	-	-	broken up in 1846			
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	

Remarks:

The one-story frame house with wood shingled roof was erected in the period 1811-33 and probably stood on the southern end of Lot 5, Block D, front-ing on what became Hamilton Street, at its junction Tell Street. (See 1834 maps).

NPS Land

ARMORY DWELLING HOUSE NO. 28 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 3, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Roderick*	5.00	5.00	
Dec. 31, 1844	Wood					Wm. Shewbridge	1.25	1.25	
Dec. 31, 1846						House demolished in 1846			
June 30, 1849						Broken up in 1846.			
Dec.31, 1850	Wood	1	Single			Broken up in 1846			
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: One-story frame house with wood shingle roof, built 1811-33, probably located on the south end of Lot 3, Block D, fronting on Hamilton Street (see 1834 maps).

*John Roderick was paid $ 25.00 in 1827 for making repairs to a wooden dwelling.

NPS Land

ARMORY DWELLING HOUSE NO. 29 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 3, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					William Decker	6.25	6.25	
Dec. 31, 1844	Stone Wood					James Rollins 1 month	7.15	15.78	
Dec. 31, 1846						House demolished in 1845			James Rollins sti owed 14.44 for 29
June 30, 1849						Broken up in 1845.			
Dec.31, 1850	Wood	1	shingles			Broken up in 1845			J. Rollins still owed 14.44 for ~~29. rent.~~
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: One-story house, probably stone, erected 1811-33 with wood shingled roof, probably located on the southern end of Lot No. 3, Block D, thus fronting on Hamilton Street. (see 1834 maps).

ARMORY DWELLING HOUSE NO. 30 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. 2, North of Shenandoah Street(probably)
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry House may also have been located on Block F, Shenandoah Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John Nichols	6.25	6.25	
Dec. 31, 1844	Stone					John Nichols	7.15	7.99	
Dec. 31, 1846	Stone					John Nichols	7.15	7.15	
June 30, 1849	Stone	2		7	600	John Nichols	7.50		
Dec.31, 1850	Stone	2	wood shingles	8	500	John Nichols	7.50	22.50	
June 30, 1851	Stone	2				Mrs. Nichols "located on Shenandoah Street"			
June 30, 1852	reserved	from 1852 sale				Mrs. Nichols			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	0	none	House and lot reserved for U.S. use.

Remarks: Two-story stone house with wood shingled roof, erected 1811-33. House was demolished by the Armory in the period 1855-59, and was not standing when U.S. owned Armory dwelling houses were renumbered in 1859.

NPS land

ARMORY DWELLING HOUSE NO. 31 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No.2 , North of Shenandoah Street (Probably)
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone & Wood					Samuel McKinsey	5.00	0	
Dec. 31, 1844	Wood					Samuel McKinzie	5.75	5.75	
Dec. 31, 1846	Wood					Absalem Riley	5.75	5.75	
June 30, 1849	Wood	1		12	250	Absalem Riley House torn down in 1849.	6.00	6.00	in 1848
Dec.31,1 1850	Wood	1	wood shingle	12	250	Demolished and materials sold in 1849			
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	

Remarks:

ARMORY DWELLING HOUSE NO. 32 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. 2, North of Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Park Bldg. No. 48

NPS Land

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Augustus Shope	16.25	16.25	
Dec. 31, 1844	Stone					John Berlin (part of house)	8.60	8.60	a two-family house.
	Stone					James O'Laughlin(part of house	8.60	8.60	
Dec. 31, 1846	Stone					John Berlin (part of house)	8.60	8.60	two-family house
	Stone					Wm. H. Wentzle (Part of House)	8.60	8.60	
June 30, 1849	Stone	2	shingle	6	800	John Berlin	8.75		
						W. H. Wentzle	8.75		
Dec. 31, 1850	Stone	2	wood shingle	7	600	A. M. Ball	8.75	8.75	
						J. W. Roderick	8.75	8.75	
June 30, 1851	Stone	2	shingle			A. M. Ball			
						J. W. Roderick			
June 30, 1852						" " " " House and land reserved from 1852 sale for U. S. use.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	0	none	Reserved for U.S. use in 1852

Remarks: House No. 32 was erected 1822-31, perhaps by armorer William Smallwood in 1825. If so, the house was valued at $ 720.00 in 1831 and described as a "Stone House, 19 by 29 feet, 2 stories high.. porch, smoke house, stone wall, kitchen, privy, and fence. The Armory paid Smallwood $ 629.32 for the dwelling, $ 400.00 in 1826 and $ 229.32 on May 17, 1837. In 1859 the two-story stone house fronted 19 feet 1½ inches on the north side of Shenandoah Street and was 33 feet deep. It had six rooms, 2 on each floor, plus two in the attic. A two-story wing adjoined the main house on the east side. Two-stories, built of stone, the wing fronted 20 feet 3 inches on Shenandoah Street and was 17 feet 1½ inches deep. The main house was 17 feet 1½ inches high to the eave line and the east wing 14 feet 3 inches high. The house continued to be used as an Armory dwelling house, 1852-61 and was renumbered as House No. 5. The U.S. sold Lot 2 and house for $ 405.00 to Gabriel L. Myers on May 25, 1880, issuing the deed on January 1, 1881.

NPS Land

ARMORY DWELLING HOUSE NO. 33 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , JEFFERONS LOT, North of Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone & Brick					Solomon Snook	6.50	6.50	
Dec. 31, 1844	Stone					Solomon Snook	7.45	7.45	
Dec. 31, 1846	Stone					Joshua T. Lewis	7.50	7.50	
June 30, 1849	Stone	1	wood shingle	11	300	Joshua T. Lewis	8.00	8.00	
Dec.31, 1850	Stone	1	shingle	13	200	Absalom Riley	8.00	8.00	
June 30, 1851	Stone	1				Absalom Riley			
June 30, 1852						House demolished in 1852 and material sold Aug.14,1852			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	0	none	Vacant lot reserved for use of U.S.	in 1852.

Remarks: Jeffersons Lot, a vacant lot, donated by U.S. to the town of Harper's Ferry in 1870.
House No. 33, a one-story stone house with wood shingled roof, was erected 1811-21.

ARMORY DWELLING HOUSE NO. 34 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. , JEFFERSONS LOT, North side of Shenandoah Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Wm. I.(?) Stipes	5.00	30.00	Delinquent from 4 quarter of 1840
Dec. 31, 1844						House demolished in 1843			
Dec. 31, 1846									
June 30, 1849						Broken up in 1845.			
Dec.31, 1850	Wood	1	Wood shingle			"Broken up in 1845"			
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Vacant lot reserved for U.S. use in 1852.

Remarks: One-story frame house with wood shingle roof, erected 1811-1833 and demolished in 1843.

Vacant lot reserved for U.S. use, 1852-61, and donated to town of Harper's Ferry in 1870.

ARMORY DWELLING HOUSE NO. 35 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS land.

Location: Block Lot No. , JEFFERSONS LOT, North of Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick & wood					Hesikiah Roderick	9.00	9.00	
Dec. 31, 1844	Wood					Hesekiah Roderick	10.35	20.70	
Dec. 31, 1846						not listed - vacant ?			Hezekiah Roderick delinquent $ 37.4
June 30, 1849	Wood	1	shingle	9	450	William Earle	10.50	10.50	Hezehiah Roderick owed 23.06.
Dec.31, 1850	Wood	1	wood shingle	11	300	J. W. Stover	8.50	8.50	William Earle owe $ 7.00; H.Roderic owed $ 23.06.
June 30, 1851	Wood	1	shingle			John W. Stover			
June 30, 1852						John W. Stover House and lot reserved from demolished by May 1854.	1852 sale	and House No. 35	

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved for U.S. use in 1852.

Remarks: House No. 35, a one-story frame house with wood shingled roof, was erected ca. 1811-33 and demolished in period 1853-May 1854.

Vacant lot used by U.S. 1852 to 1861 and demoted to the town of Harpers Ferry in 1870.

NPS Land

ARMORY DWELLING HOUSE NO. 36 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , PRESBYERIAN CHURCH LOT, North of Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					, James Copeland	7.50	7.50	
Dec. 31, 1844	Wood					Jacob Gomph (2 months)	8.60	0	James Copeland delinquent $ 7.50
Dec. 31, 1846	Wood					Jacob Gompf	8.60	8.60	
June 30, 1849	Wood	1	shingle	12	250	Jacob Gompf	8.75	8.75	
Dec.31, 1850	Wood	1	wood shingle	12	250	Jacob Gompf	8.75	8.75	
June 30, 1851	Wood	1				Jacob Gompf			
June 30, 1852						Jacob Gomph			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House & lot reserved from 1852 sale for use of U.S.

Remarks: One-story frame house with wood shingle roof erected ca. 1811-33. The house and lot were reserved from the U.S. sale of lots and houses held in 1852. House No. 36 was demolished and its materials sold by February 12, 1853.

Lot donated by the U.S. to the Presbyterian Church in 1870.

ARMORY DWELLING HOUSE NO. 37 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. , PRESBYTERIAN CHURCH LOT, North of Shenandoah Stree
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Wiggington *	7.50	7.50	
Dec. 31, 1844	Wood					John Wigington	8.60	8.60	
Dec. 31, 1846	Wood					John Wigington	8.60	8.60	
June 30, 1849	Wood	2(sic)	shingle	8	500	James Wigington	8.75	8.75	
Dec.31, 1850	Wood	1	shingle	11	300	J. W. Arvin James Wiggington	4.50 4.50	4.50 4.50	
June 30, 1851	Wood	1				J. W. Arvin James Wigington			
June 30, 1852						J.W. Arvin James Wigington			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: One-story frame house with wood shingle roof erected 1811-1833. Dwelling House demolished and material sold in May 1854.

Vacant lot donated by U.S. to Presbyterian Church in 1870.

*"John Wegginton" was paid $ 19.00 on March 31,1826 for making repairs to a wooden house. R.G.217-1st Series, File 9851-Voucher 85A.

ARMORY DWELLING HOUSE NO. 38 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. , PRESBYTERIAN CHURCH LOT, North of Shenandoah Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Samuel Stabbs	7.50	7.50	
Dec. 31, 1844	Wood					Armistead Hobbs	8.60	8.60	
Dec. 31, 1846	Wood					Armistead Hobbs	8.60	8.60	
June 30, 1849	Wood	2(sic)	Shingle	8	500	Armistead Hobbs	8.75	8.75	
Dec.31, 1850	Wood	1	shingle	11	300	A. Hobbs	8.75	8.75	
June 30, 1851	Wood	1				A. F. Hobbs			
June 30, 1852	Wood	1				A. F. Hobbs			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved for U.S. use in 1852.

Remarks: One-story frame house with wood shingle roof, erected 1811- 1833. House was reserved for U.S. use in 1852 and in May 1854 the edifice was demolished and its materials sold.

Vacant lot donated to the Presbyterian Church by the U.S. in 1870.

ARMORY DWELLING HOUSE NO. 39 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. , ROMMAND CATHOLIC SCHOOL LOT, North of Shenandoah Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone	*Wilson for making 12 counters	paid $ 10.00 on July 30,1841 to fit up shelves & 2	a store room (1)		John G. Wilson *	15.00	15.00	Delinquent from 4 qr. of 1840, owed 168.86 (1)
Dec. 31, 1844	Stone					Jerone B. Young	14.35	14.35	John G. Wilson delinquent 23.97 39.
Dec. 31, 1846	Stone					Jerone B. Young	14.35	14.35	
June 30, 1849	Stone	1	shingle	7	600	Jerome B. Young	14.50	14.50	
Dec. 31, 1850	Stone	1	wood shingle	8	500	A. J. Wright	14.50	14.50	James Foley Est. owed $ 6.00
June 30, 1851	Stone	1				A. J. Wright			
June 30, 1852	Stone	1				Benjamin Ott			using it as a store & dwelling

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House and lot reserved from U.S. 1852 sale for U.S. use.

Remarks: House No. 39, a one-story stone building with wood shingle roof, built 1811-21, fronted about 44 feet on north side of Street and was about 16 feet deep(see 1834 maps). Prior to 1841 the house was rented by James Foley, a master carpenter, who left owing $ 6.00 in rent. His estate had failed to settle this debt by 1850. House No. 39 and lot were reserved from the 1852 sale of lots by the U.S. for Armory use. House No. 39 was demolished and its material sold in May 1854.

(1) R.G. 217, 2nd Series, File 6454,Voucher 17.Shelves were 2 feet 8 inches by 17 feet 6 inches. The vacant lot was donated by the U.S. to the Roman Catholic Church in 1870 for use as a school lot.

(1) (Total owed included $ 10.00 per quarter rent for par t of Bldg. No. 7 for use as Post Office,as well as House No. 39).

ARMORY DWELLING HOUSE NO. 40 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. ROMAN CATHOLIC SCHOOL Lot, North of Shenandoah Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John M. Barnes	7.50	7.50	
Dec. 31, 1844	Brick					John M. Barnes	8.60	17.20	
Dec. 31, 1846	Brick					Daniel Young	8.60	8.60	John N. Barnes delinquent 28.66
June 30, 1849	Brick	2	shingle	7	600	Daniel Young, Jr.	10.00	10.00	
Dec.31, 1850	Brick	2	wood shingle	9	450	George L. Augur	10.00	10.00	Barnes still owed 28.66
June 30, 1851	Brick	2				J. T. Adams			
June 30, 1852						J. T. Adams			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: A two-story brick house with wood shingled roof, erected 1811-33, and fronting about 18 feet on street and 24 feet deep.(See 1834 maps). House and lot were reserved from 1852 sale of U.S. lots for Armory use. House No. 40 was demolished and its materials sold in May 1854.

The U.S. donated the vacant lot to the Rommand Catholic Church in 1870 for use as a school lot.

ARMORY DWELLING HOUSE NO. 41 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. , ROMAN CATHOLIC SCHOOL LOT, North of Shenandoah Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry (Also see House No. 42)

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone and wood					James Fisher	10.00	10.00	
Dec. 31, 1844	Stone & wood					Samuel Shewbridge	11.50	11.50	
Dec. 31, 1846	Stone & wood					Samuel Shewbridge	11.50	11.50	
June 30, 1849	Wood	1	shingle	7	600	Thomas Whaley, Jr.	12.50	12.50	
Dec.31, 1850	Wood	2	shingle	8	500	William Kirby	12.50	12.50	
June 30, 1851	Wood	2				William Kirby			
June 30, 1852						William Kirby			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 41 and its 1-story wing(House 42) were built in 1826 by John S. Gallagher for use as a dwelling house (No. 41) and print office(No. 42). Described in 1829 as "frame house plastered outside." Estimated value was $ 600. Had cellar, 10 rooms, kitchen and smoke house. The house fronted about 24 feet on the street and was about 38 feet deep. House No. 42, a 1-story wing adjoined the main house on the east side and was 18 feet wide and 22 feet deep.(See 1834 maps). The Armory purchased Gallagher's title to Houses 41 and 42 for $ 835.00 on March 11, 1830. Uses: Gallagher's dwelling and print office, 1826-1828; rented by P.C. McCabe in 1828. Gallagher was editor and published of Harper's Ferry Free Press. 1830 shoe storeof N. Buckmaster. July 1840-41 Houses 41-42 rented by James R. Hayman, editor and publisher of Harpers Ferry Constitutionalist,which was printe in shop. House 41, a two-story frame building with wood shingle roof, was demolished in June 1853.

ARMORY DWELLING HOUSE NO. 42 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. , ROMAN CATHOLIC SCHOOL LOT' ,north of Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
(Also see House No. 41)

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					not occupied			
Dec. 31, 1844	Wood					Albert Beale	2.50	2.50	
Dec. 31, 1846	Wood					Albert Beale	2.50	2.50	
June 30, 1849	Wood	1	shingle			frame addition to House No. 42. House 41 demolished in 1848.			
Dec.31, 1850						broken up in 1848			
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	none	none	Lot reserved from 1852 sale for U.S.	use.

Remarks: House No. 41 and its 1-story wing(42) were built in 1826 by John S. Gallagher, editor and publisher of the Harper Ferry Free Press, in 1826 and used as his dwelling and printing office from 1826 to 1828. Plant described in 1829 "as frame house plastered outside", valued at $ 600. Had cellar, 10 rooms, kitchen, and smoke house. No.41, 2-story frame house with wood shingle roof, fronted about 24 feet on street and was 38 feet deep. No.42, 1-story east frame addition, fronted about 18 feet on street and was 22 feet deep.(See 1834 maps). rented by P. C. McCabe as dwelling in 1829 and by N. Buckmaster as a shoe store(42) in 1830. Armory purchased Gallagher's title to 41-42 for $ 835.00 on March 11,1830. 41-42 rented as dwelling and print shop for Harpers Ferry Constitutionalist by its editor and publisher, James R. Hayman, from July 1840-41. The print shop, Bldg. No. 42, was demolished and its materials were sold in 1848. Vacant lot donated by the U.S. in January 1870 to the Roman Catholic Church for use as a school lot.

ARMORY DWELLING HOUSE NO. 43 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No.5 , Shenandoah Street

S. Howell Brown's 1852 Map of Harpers Ferry

S. Howell Brown's 1869 Map of Harpers Ferry Paymaster's Old(1802) House

NPS Land

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick Brick					Samuel Traile Elias Dearing	9.37 9.37	9.37 9.37	a two-family house
Dec. 31, 1844	Brick Brick					Samuel Traile Elias Dearing	10.75 10.75	10.75 17.92	two-family house
Dec. 31, 1846	Brick Brick					Samuel Trail George Atkinson 2 months	10.75 10.75	10.75 7.16	two-family hous Earing owed 31.20
June 30, 1849	Brick	2	slate	6	800	Samuel Trail George Atchinson	10.75 10.75	10.75 10.75	2 family house
Dec.31, 1850	Brick	2		7	600	Samuel Trail George W. Gompf	10.75 10.75	14.50 10.75	
June 30, 1851	Brick	2				Samuel Trail George W. Gompf			
June 30, 1852					900	Samuel Trail George W. Gomgf			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	Photos:HF-21(1803); HF-249(1857),HF-361 (1865),HF-68(1858 or 88)
1852 Sale	8/31/52	$ 900.00	Gorge W, Gompf	December 12, 1856	

Remarks: House No. 43 was designed and erected by Armory Paymaster Samuel Annin as his residence in 1801-02. In 1810 described as a two-story brick house with cellar and adjoining kitchen, 28 by 19 feet. In 1821 the house was described as brick, 2 stories and cellar, 40 by 24 feet, and valued at $ 2,500.00. The house was repaired in 1825 at a cost of $ 300.00 and in 1826 small well house and a frame addition were made to his residence at a cost of $ 55.75. The house served as the residences of the following paymasters: Samuel Annin, 1802-1815; Major Lloyd Beall, 1815-17; William McGuire, 1817-20; William Little, 1820-22; John McGuire, 1822-23; William P. Craighill, 1823-24; William Broadus, 1824-30; and Daniel Bedinger, 1830-38. After 1838 the house was rented as a two-family dwelling to armorers until August 1852. The roof of the house was slated in 1834. Dimensions of bldg. in 1894 were 44 by 30 feet. House still standing ca. 1942.

ARMORY DWELLING HOUSE NO. 44 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block B Lot No. , MARKET HOUSE LOT, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Ashfield Jones	7.50	7.50	
Dec. 31, 1844	Wood					Ashford Vories, 1 month Joseph Mathews ,1 month	8.60 8.60	2.86 5.93	
Dec. 31, 1846						Vacant (not listed)			
June 30, 1849	Wood	1		12	250	demolished in 1847			
Dec.31, 1850	Wood	1		12	250	Broken up in 1847			
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	

Remarks: A One-story frame house erected 1811-33 and demolished in 1847. Its dimensions were about 35 by 25 feet(see 1834 maps).

The two-story brick market house, 60 by 40 feet, with slate roof was constructed on this lot by the Armory in 1846-47. Old House No. 44 was probably demolished to clear the lot for use of new market house as the town market.

ARMORY DWELLING HOUSE NO. 45 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block C Lot No. 1, Shenandoah Street (Southern end)
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry or on northern end of Lot 11, Block C, Shenandoah Street

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood	Stipes paid $ 215.85 for erecting a wooden house 24 by 18 feet on December 22, 1823 (1)				Henry Stipes*	5.00	10.00	1) R.G.217-1st S. File 7624-V.87A.
Dec. 31, 1844	Wood					Daniel Young	5.75	5.75	
Dec. 31, 1846	Wood					J. T. Adams	5.75	5.75	
June 30, 1849	Wood	1		12	250	William Medlar	6.25	6.25	
Dec. 31, 1850	Wood	1		14	150	William Medlar	6.25	6.25	
June 30, 1851	Wood	1				William Medlar			
June 30, 1852						Broken up in 1852 William Medlar			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

either Henry Stipes in 1823 or by

Remarks: A one-story frame house with wood shake roof erected by William Graham between 1829 and 1831, when his property was described in October as including a "Stone Store House(Bldg. 4)- Brick Dwelling House (Bldg. 3) & Frame House(No. 45, Stable-Ice House--privy. " These were valued at $ 4,000. The U.S. Armory paid William Graham's Estate $ 4,000 for his title to these structures on July 21, 1837. House No. 45 was located on the southern end of Lot 1, Block C, and fronted on what later became Hamilton Street. Dimensions about 14 by 18 feet.

Bldg. No. 44 was demolished during the summer of 1852, prior to the sale of Lot 1, Block C , on September 1, 1852 to Edward Lucas, Jr., for $ 2,505.00 at public auction. Houses 3 and 4 still stood on Lot 1 in 1852. (See 1834 maps for location and size of House No. 45).

ARMORY DWELLING HOUSE NO. 46 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block C Lot No.10, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John E. P. Daingerfield, Clerk	Free	Free	
Dec. 31, 1844	Stone					Samuel Kilham	17.25	17.25	
Dec. 31, 1846	Stone					Samuel Kilham	17.25	17.25	
June 30, 1849	Stone	2		6	800	Samuel Kilham	18.00	18.00	Albert Ridnman owed 37.44(?)
Dec.31, 1850	Stone	2		8	500	Samuel Kilham	15.00	15.00	
June 30, 1851	Stone	2				J. T. Earnshaw			
June 30, 1852	Stone	2			800	J. T. Earnshaw			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	9/1/52	$ 805.00	Samuel Trail	April 24, 1866	Property sold at public auction in 1852.

Remarks: A two-story stone house with wood shingle roof, erected 1811-1833, about 20 by 38 feet in size(see 1834 maps). House still may have been standing in 1813 as the west wing of the German Brewing Company building.

Photos: HF-249(1857); HF-68(1858 or 1888), HF-99(1892-95).

ARMORY DWELLING HOUSE NO. 47 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block C Lot No. 9, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Joseph G. Johnson	12.50	12.50	
Dec. 31, 1844	Stone					George Dugan	14.35	14.35	
Dec. 31, 1846	Stone					George W. Dugan	14.35	14.35	
June 30, 1849	Stone	2		7	600	George W. Dugan	14.50	14.50	
Dec. 31, 1850	Stone	2		8	500	George W. Dugan	14.50	14.50	
June 30, 1851	Stone	2				George W. Dugan			
June 30, 1852	Stone	2			600	George W. Dugan			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	8/31/52	$ 600.00	Francis McCabe	May 11, 1860	

Remarks: A two-story stone house about 18 by 28 feet in size (see 1834 maps), with wood shingle roof, erected 1822-33. McCabe's heirs owned the property until April 19,1875, when the sold the house and lot for $ 800. The dwelling was no longer standing in 1913.

Photo: HF-249(1857).

ARMORY DWELLING HOUSE NO. 48 (1841-1858) HARPER'S FERRY, ARMORY, VA.

NPS Land

Location: Block C Lot No. 8, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Levi Steadman	7.50	15.00	
Dec. 31, 1844	Brick					Bilson, William	8.60	8.60	Levi Steadman delinquent 17.20
Dec. 31, 1846	Brick					Levi Steadman	8.60	8.60	
June 30, 1849	Brick	2		11	300	William Bilson(or Bilsan)	8.75		
Dec. 31 1850	Brick	2		12	250	William Bilson	8.75	8.75	
June 30, 1851	Brick	2				William Bilson			
June 30, 1852	Brick	2			400	William Bilson			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 400.00	Bernard McCabe	December 12, 1856

Photo HF- 249(1857).

Remarks: A two-story brick house which abutted on one-story brick house No. 49. (See 1834 Maps). Together the two brick houses measured about 18 by 54 feet. Both houses were gone by 1894.

ARMORY DWELLING HOUSE NO. 49 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block C Lot No. 7, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John Baylis	7.50	7.50	
Dec. 31, 1844	Brick					John Baylis	8.60	8.60	
Dec. 31, 1846	Brick					John Baylis	8.60	8.60	
June 30, 1849	Brick	1		11	300	John Baylis	8.75	8.75	
Dec.31, 1850	Brick	1		12	250	John Baylis	8.75	8.75	
June 30, 1851	Brick	1				John Baylis			
June 30, 1852					275.00	John Baylis			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	8/1/52	275.00	James Watson	October 5, 1853	Watson sold the property to Joseph Davis in 1853

Remarks: A one story brick house which abutted on two-story brick house No. 48. Together the two brick houses measured about 18 by 54 feet.(See 1834 maps). Both dwellings were gone by 1894.

Photo HF- 249(1857).

ARMORY DWELLING HOUSE NO. 50 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block D Lot No. 7, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry (probably on Lot 7, but in Block D).

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Slaughter House					Philip Coons ,(butcher)	12.50	12.50	
Dec. 31, 1844						vacant			John H.Strider delinquent 80.23
Dec. 31, 1846						(destroyed by fire in 1845)			
June 30, 1849						Burned in 1845.			
Dec.31, 1850	Wood	1		-	-	Burned up in 1845			
June 30, 1851	Wood	1		-	-	Burned up in 1845			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	

Remarks: A one-story frame building, used as a slaughter house. On April 6,1826, Philip Coons received a lease to Lot 7, Block D, from the U.S. and in 1826 erected "Stone, rough cast" house that was used "as a dwelling house, boarding House, and butchery." The value of these improvements was estimated to be $ 2,500 in 1829. In October, 1831, Coons property was described as consisting of "a Stone House, stable, Kitchen- slaughter house- ice house." The appraised value was set at $ 3,500.00. In March 1827, Coons received permission from the Armory to erect a slaughter house . This one-story frame structure, Bldg. No.50, was probably located on Lot 7 on the banks of the Shenandoah River and measured about 22 by 22 feet(see 1834 maps). The U.S. purchased Philip Coons title to these buildings for $ 3,298.00 on December 27, 1836.

ARMORY DWELLING HOUSE NO. 51 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block D Lot No. 2, Shenandoah Street

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Located on Block D, probably on southern end of Lot 2.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Joseph Mathews	4.00	4.00	Must be small house for so littl rent.
Dec. 31, 1844	Wood					Joseph Mathew	4.60	4.60	
Dec. 31, 1846						demolished in 1845			
June 30, 1849						"Broken up in 1845."			
Dec. 31, 1850	Wood	1		-	-	Broken up in 1845			
June 30, 1851	Wood	1				Broken up in 1845			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	

Remarks: One-story frame dwelling house, apparently small, built 1811-33, and probably located on the southern end of Lot 2, Block D, so as to front on what later became Hamilton Street (See 1834 maps).

ARMORY DWELLING HOUSE NO. 52 (1841-1858) HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block D Lot No. 7, Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Wm. Wood	43.77	174.97	
Dec. 31, 1844	Stone					Notley W. Dearing(Part of) William Kirby(part of)	11.25 11.25	11.25	Wm Wood owed $ 72.12. Wm. Woo
Dec. 31, 1846	Stone					Notley W. Dearing (part of) William Kirby (part Of)	11.25 11.25	11.25 11.25	Wm. Wood still owed 72.12.
June 30, 1849	Stone	2				N.W. Dearing William Kirby	12.50 12.50	12.50 12.50	
Dec.31,1 1850	Stone	2		4	1,200	A. R. Dewey George W. Dudran	12.50 12.50	12.50 12.50	
June 30, 1851	Stone	2				G. W. Berry G. W. Dudran			
June 30, 1852					900.00	G.W. Berry G.W. Dudran			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	Photos HF-249(1857), HF-44 (1876).
1852 Sale	9/1/52	$ 912.00	John Mason	December 12, 1856 sold at public	auction.

Remarks: A two-story stone rough cast house about 28 by 39 feet in size erected by Philip Coons in 1826-27 as a dwelling house and boarding house. The building was still standing in 1892-96, but was gone by 1913. April 6,1826, Philip Coons, a butcher, received a lease to lot 7 from the U.S. and 1825-26 erected House No.52. In 1827 he also erected a slaughter house, House No. 50 on the lot. In October 1831 the appraised value, for a "Stone House, stable, Kitchen, slaughter house - ice house-" all built by Coons, was $ 3,500.00. The U.S. purchased Coons' title to these structures for $ 3,298.00 on December 27, 1836. David and Philip Coons apparently lived in House No. 52 from 1827 to about 1834, when Coons offered the property for sale.

SECTION B

ARMORY DWELLING HOUSES No. 53 to 61,

Located along Washington or High Street on way up from Shenandoah Street to Camp Hill.

The exact locations of Houses No. 53, 54, 56, 57, 58, 59, 60, and 61 along the north and south sides of High or Washington Street is unknown. The exact site of House No. 55 is fixed by Brown's maps of 1852 and 1869.

Data on Houses built in this area:

1. In 1816 the President of the U.S. granted Col. Jamieson, a officer in the U.S. Army a lease to a lot of ground. Jamieson erected a wooden storehouse and dwelling on this plot in 1816. In 1829 his buildings were estimated to be worth $ 800.00. This lease and building were apparently sold between 1829 and 1830 to William Anderson. In October 1831 the appraised value of Anderson's stone storehouse and "lease" was set at $ 1,200.00. The location of Anderson's Holding was given as "on the north side of Camp Hill, overlooking the Musket Factory. The U.S. purchased Anderson's building and lease for $ 1,162.00 on January 25, 1837.

2. In 1826 Michael Garry erected a 3-story stone dwelling(House No. 55),a 1½ story frame store house, and stable, located on the south side of High Street. In 1831 these structures were appraised as worth $ 2,450. On June 31,1831, Garry sold his rights to Jacob, Charles, Thomas, and Baltzell, Baltimore merchants, for $ 3,000. On June 30,1837, the U.S. purchased the Baltzells title for $ 2,375.00.

3. In 1831 Samuel Strider filed a claim of $ 285.00 for a frame store house and dwelling, smoke,"located on the Potomac side, near the Superintendent's house, the latter being located in the Musket Factory yard at the east end. The U.S. purchased Strider's title to this store for $ 285.00 on January 16, 1837.

4. Block AA, Lot 1, fronting on High Street 35 feet, lease to Lot H on 1844 Map.Dr. Nicholas Marnion held a lease from U.S. from June 3,1829. In 1829 he erected a 2-story stone house with basement and gallery, 35 by 22 feet, and also a frame one-story house 16 by 14 feet. Appraised value of buildings was $ 2,300. U.S. purchased property from Dr. Marmion on November 30, 1847 for $ 2,000.00.(See House No. "183" for further details).

ARMORY DWELLING HOUSE NO. 53 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Perhaps Methodist Episcopal Church
Block Lot No. , Lot
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Washington Street, between Shenandoah Street and Camp Hill. on South side of High Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Michael Foley, carpenter	4.50	4.50	
Dec. 31, 1844	Wood	Nelson	Faulkner owed $		12.00	Alexander Fossett in house	9.00	22.00	George W.Cox owed $ 1.79; Michael Foley-owed 18.00
Dec. 31, 1846	Wood					(being used as School room).			G.W. Cox- $ 1.79 Nelson Faulkner-1 M.Foley- 18.00
June 30, 1849	Wood	1				School Room	7.50	5.00	
Dec.31,1 1850	Wood	1		16	50	School Room	7.50	5.00	
June 30, 1851	Wood	1				John Zimmerman			
June 30, 1852						Reserved from 1852 sale			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	

Remarks: Small one-story frame house . House and lot reserved from 1852 sold for U.S. use and House No. 53 demolished and materials sold, 1855-59 period. Constructed prior to 1833.

Perhaps located near C on 1848 map, the Methodist Episcopal Church.

ARMORY DWELLING HOUSE NO. 54 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Perhaps near Methodist Episcopal Church. Lot No. , South side of Washington Street between west boundary of Six Acre Reservation and top of Camp Hill.

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					William Apsey	25.00	16.66	
Dec. 31, 1844	Stone					John Marquett 1½ months	7.15	3.57	
Dec. 31, 1846	Stone					Michael Crowl	7.15	7.15	
June 30, 1849	Stone	1		7	600	Michael Crowl	7.50		
Dec.31,1 1850	Stone	1		8	500	Albert Cline	7.50	7.50	Michael Crowl estate owed 7.50
June 30, 1851	Stone	1				Albert Cline			
June 30, 1852						Reserved from 1852 sale for U.S. use			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	

Remarks: House No. 54, a one-story stone house erected in the period 1822-33. Reserved from the 1852 sale for U.S. use. House apparently demolished in period 1855-59.

Probably located near the Methodist Episcopal Church Lot C on 1848 map.

ARMORY DWELLING HOUSE NO. 55 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. ,South Side of Washington Street, adjacent to west boundary of Wager 6 acre Reservation.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
directly north Methodist Episcopal Church.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					George Mauzy, Clerk	Free	Free	
Dec. 31, 1844	Stone					James Krepps Marine J. Krepps	11.50 11.50	63.00 11.50	2-family house
Dec. 31, 1846	Stone					Marine J. Kreps Joseph Martin	11.50 11.50	11.50 11.50	
June 30, 1849	Stone	2		4	1,200	M.J. Kreps W.D. Ward William Simpson	11.50 11.50 11.50		
Dec.31,1 1850	Stone	2		4	1,200	Martin J. Kreps William Simpson	11.50 11.50	11.50 11.50	
June 30, 1851	Stone	2				Martin J. Kreps William Simpson			
June 30, 1852					1,100.00				

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	1,100.00	James Mills	November 29, 1856

Remarks: This two-story stone house over elevated basement was erected by Michael Garry in 1826. In October 1831 the property, appraised as worth $ 2,450.00, was comprised of a three-story stone dwelling, a 1½ story log & frame store, and a stable", "located on the street leading up the hill towards Charlestown." Garry sold these bldgs. to Jacob, Charles, Thomas, and Philip Baltzell, Baltimore merchants, on June 31, 1831 for $ 3,000. The U.S. purchase the houses from the Baltzells on June 30, 1837 for $ 2,375.00.

ARMORY DWELLING HOUSE NO. 56 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , on Washington Street,going up to Camp Hill.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Daniel O'Boyle	5.00	5.00	
Dec. 31, 1844	Wood					, Vacant			
Dec. 31, 1846						Demolished in 1845.			
June 30, 1849						"Broken up in 1845."			
Dec.31,1 1850	Wood	1		-	-	"Broken up in 1845."			
June 30, 1851	Wood	1				Broken up in 1845.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: One-story frame house built prior to 1833. Demolished in 1845.
Probably located near Methodist Episcopal Church (C on 1848 map.)

ARMORY DWELLING HOUSE NO. 57 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , Washington Street, on way to Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood & Brick					Wm. Gannon *	6.25	6.25	
Dec. 31, 1844	Wood					Henry Gannon	7.15	7.15	
Dec. 31, 1846	Wood					Henry Gannon	7.15	7.15	
June 30, 1849	Brick	1		9	450	Henry Gannon	7.50		
Dec.31,1 1850	Brick	1		9	450	Henry Gannon	7.50	7.50	
June 30, 1851	Brick	1				Henry Gannon			
June 30, 1852						George W. Wearing			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Reserved from 1852 sale for U.S. use.

Remarks: One-story wood and brick house erected prior to 1833(1811-33). House demolished in period 1855-59.

* William Gannon filed a claim in 1829 of $ 93.00 for building a wooden house.

ARMORY DWELLING HOUSE NO. 58 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , Washington Street, on way up to Camp Hill.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Benjamin Snook, tinsmith	12.00	72.00	
Dec. 31, 1844	Stone					Benjamin Snook	13.80	13.80	
Dec. 31, 1846	Brick					William D. Copeland 2 months Peter Jones 1 month	7.50 7.50	5.00 2.50	
June 30, 1849	Brick	1		9	450	Peter Jones	7.50		
Dec.31,1 1850	Stone	2		13	200	Material sold and bldg. demolished May 31, 1851.			
June 30, 1851	Stone	2				sold May 31, 1851			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: A two-story stone house erected 1822-33 and demolished in May 1851.

ARMORY DWELLING HOUSE NO. 59 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , Washington Street, on way up to Camp Hill.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Henry Krout (Crout-sic)	6.25	6.25	
Dec. 31, 1844	Brick					Henry Krout	7.15	7.15	
Dec. 31, 1846	Brick					Henry Krout	7.15	7.15	
June 30, 1849	Brick	1		9	450	Henry Krout	7.50		
Dec.31,1 1850	Brick	1		12	250	John Slippy	7.50	7.50	
June 30, 1851	Brick	1				John Sleppy			
June 30, 1852						John Sleppy			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	n ot sold	none	none	Reserved from sale in 1852 for U.S. use.

Remarks: One story brick house erected in period 1798-1833. House demolished in period 1855-59.

ARMORY DWELLING HOUSE NO. 60 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block Lot No. , Washington Street, on way to Camp Hill.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Hyatt, carpenter	4.50	4.50	
Dec. 31, 1844	Wood					John Hyatt	5.15	23.80	
Dec. 31, 1846						house vacant			John Hyatt owed 28.95
June 30, 1849						House demolished in 1845.			
Dec. 31, 1850	Wood	1		-	-	"Broken up in 1845."			John Hyatt owed 28.95
June 30, 1851	Wood	1				broken up in 1845.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: One story frame house built 1798-33 and demolished in 1847.

ARMORY DWELLING HOUSE NO. 61 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , Washington Street, on way up to Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Francis Wentzle	7.50	7.50	
Dec. 31, 1844	Wood					Jose ph Wentzle	8.60	17.20	
Dec. 31, 1846	Wood					Joseph Wentzle	8.60	8.60	
June 30, 1849	Wood	2		8	500	Joseph Wentzle	9.50		
Dec.31,1 1850	Wood	1		11	300	John Wentzle	9.50	9.50	
June 30, 1851	Wood	1				William McDaniel			
June 30, 1852						William McDaniel			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	not sold	none	none	Reservade from 1852 sale for U.S. use.

Remarks: one-story frame house erected 1798-1833, Reserved from 1852 sale for U.S. use and demolished in period 1855-59.

ARMORY DWELLING HOUSES NO. 62 - 65

Located near Harper's Gravevard and Jefferson's Rock, Camp Hill.

Locations of Houses No. 63 and 64 is probable. Location of House No. 65 is definite and site of House No. 63 is unknown because the structure was demolished in 1847, prior to the making of Brown's 1848 map.

Data on Houses in the vicinity of Harper's Graveyard

On February 23, 1829, Superintendent James Stubblefield reported:"There are three or four buildings erected on the hill between the two rivers.... one of them occupied by a Mrs. Beston as a female school establishment; three other small huts occupied by free blacks, named as follows, viz. William Prim, Adam Jones, and Jack Wood, who perform the duties of sextons and gravediggers; also two churches; all of which are located on a lot of four acres, reserved in the will of Robert Harper... for the purpose of erecting a graveyard, chruch, &c..." (1)

1. 1831 Claim of William Bester of $ 575.00 for building a brick dwelling 20 by 30 feet, kitchen and cellar, also a fence (House No. 65), "located on side of hill near Free Chruch(Park Bldg. No. 48A). Sarah Bester, the administrator of Bester's estate received $ 550.00 from the Armory for title to this residence on January 16, 1837.

2. Willia, Prim,as of October 1831, had claim of $ 80.00 "for building a stone dwelling 16 by 20 feet, located on Camp Hill near Harpers Graveyard"

(1) American State Papers- Military Affairs, Vol. IV, p. 142. The two churches were the Free Church and the Methodist Episcopal Churches, built 1825-30.

ARMORY DWELLING HOUSE NO. 62 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , Camp Hill near Harpers Grave Yard
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Weaning	5.00	5.00	
Dec. 31, 1844	Wood					John Weaning	5.75	11.50	
Dec. 31, 1846	Wood					John Weaning	5.75	5.75	
June 30, 1849	Wood	1		13	200	John Weaning	6.00		
Dec.31,1 1850	Wood	1		13	200	John Weaning	6.00	6.00	
June 30, 1851	Wood	1				John Weaning			
June 30, 1852						John Weaning			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	not sold	none	none	Reserved from 1852 sale for U.S.	use.

Remarks: One-story frame house erected 1798-33 . House was reserved from the 1852 sale for U.S. use and the dwelling, renumbered as Armory Dwelling No. 33 (probably) was still standing in 1861. Armory Dwelling House No. 33, "one-story, frame," however, was torn down by the soldiers during the Civil War and used for firewood. House was gone prior to July 27, 1865.

ARMORY DWELLING HOUSE NO. 63 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , on Camp Hill near Harper's Grave Yard
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Thomas Johnson	4.00	4.00	
Dec. 31, 1844	Wood					Jerry Harris, a plasterer	4.60	9.20	
Dec. 31, 1846						Vacant			
June 30, 1849						"Broken up in 1847."			
Dec. 31, 1850	Wood	1		16	50	Broken up in 1847			
June 30, 1851	Wood	1				Broken up in 1847.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: One-story frame house erected 1798-1833 and demolished in 1847.

ARMORY DWELLING HOUSE NO. 64 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On Camp Hill Near Harpers Grave Yard
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					(Rhua) Ruth Carlisle (Sic)	6.25	25.00	De;inquent since 4th qr of 1840.
Dec. 31, 1844	Stone					Rhua Carlisle	7.15	120.55	
Dec. 31, 1846						Vacant			Rhua Carlisle ow 120.55
June 30, 1849	Stone	1				School Room	Free		
Dec.31,1 1850	Stone	1		16	50	School Room	Free	Free	Ruth Carlisle ow 120.55.
June 30, 1851	Stone	1				School Room	Free	Free	
June 30, 1852	Stone	1				School Room	Free	Free	

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Bldg. and land reserved from 1852 sale for U.S. use.

Remarks: 1 story stone house, built 1822-33 and demolished, probably in 1856, when new brick schoolhouses were erected by the Harpers Ferry school district.

ARMORY DWELLING HOUSE NO. 65 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , Camp Hill, near Harpers Grave Yard and Park
S. Howell Brown's 1852 Map of Harpers Ferry Bldg. No. 48-A,
S. Howell Brown's 1869 Map of Harpers Ferry St. Johns Methodist Episcopal Church

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John W. Krepps	7.50	7.50	
Dec. 31, 1844	Brick					John W. Krepps	8.60	8.60	
Dec. 31, 1846	Brick					John W. Kreps	8.60	9.06	
June 30, 1849	Brick	2		6	800	J. W. Krepps	13.50		
Dec.31,1 1850	Brick	2		7	600	J. W. Kreeps	11.50	11.50	
June 30, 1851	Brick	2				J. W. Kreps			
June 30, 1852	Brick	2				J. W. Kreps			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	Photos HF-249(1857); HF-65(1865); HF-68(1858 or 1888), HF-64(1859).
	Not sold	none	none	Reserved from 1852 sale for U.S. use	

Remarks: Two-story brick house erected 1798-1833, reserved from U.S. sale of lots and houses in 1852. House renumbered as Armory Dwelling House No. 21. Described in July .1865 as "House No. 21, near Jefferson's Rock, Two-story brick house, in bad condition and vacant." House No. 21 was demolished by the Armory prior to the December 1869 sale of Armory lots and houses. This house may have been built by William Bester, 1829-31. In October 1831 his dwelling was described as "Brick dwelling 20 by 30 feet, appraised at $ 550.00; kitchen, cellar, & fence, appraised at $ 25.00, located on side of hill near the Free Church." Total value $ 575.00. On January 16, 1837, the U.S. paid Sarah Bester, the administrator of the William Bester Estate, $ 550.00 for title to the brick house. An additional claim of William Bester for improvements, in the amount of $35.00, had been previously settled.

SECTION D

ARMORY DWELLING HOUSES NO.66 to 89

Located Between Washington(or High) Street and

the Musket Factory (North Cliff or Potomac Street),

A study of S. Howell Brown's 1848 Map of Harper's Ferry indicates that a no longer extant street then ascended the side of the hill overlooking the Musket Factory, leaving the street later known as North Cliff or Potomac Street at a point near Lot 2 or 3, Block AA (on 1869 Map) and crossing in its ascent Lots 4 to 10 Block AA and Block BB, Lot 1 to 10, to form a junction with Washington or High Street at York Street(on 1869 map).

The armory dwelling house lot or yard system for Blocks AA and BB, as indicated on Brown's 1848 map, suggests that Armory Dwelling Houses No. 66 to 89 were arranged in two tiers across Block AA.

The first or lowest tier, Armory Dwelling Houses No. 66 to say No. 76, fronted on the south side of the street later known as North Cliff Street or Potomac Street, and stood on Lots 1 to 10, Block AA.

The second or upper tier fronted on one(or perhaps both) sides of the non-extant street that then ascended the side of the hill to connect with Washington or High Street. This street is called "Crooked Lane Street" (which may also be its historic name), in this report.

Houses No. 77 to 89 probably fronted on "Crooked Lane Street."

During the years 1849 to 1851 all of the Armory Dwelling Houses on the side of this hill, except for House No. 67, located on Lot 2, Block AA and fronting on North Cliff Street, were demolished by order of Superintendent John Symington and "Crooked Lane Street" was apparently graded out of existance, perhaps in an effort to keep erosion from the hillside from flowing into and blocking the U.S. Musket Factory canal.

The cleared and graded hillside(Block AA and BB) can be seen in the 1857 lithograph (HF- 51), which was probably drawn in 1856.

Most of the houses demolished 1849-51,were probably old and dated back to the 1810-21 period. (Also see HF- 628, an oil painting ca. 1826).

MAP NO. 6

"Map No. 2 - Sketch showing two practicable locations for the Balto. & Ohio R. Road through the village of Harper's Ferry-(1838). Scale 100 feet to inch."

No date, but drawn in 1837-38 for the Baltimore and Ohio Railroad Company.

Map marked "Ordnance Office, Drawer 5, Portfolio 1- No. 5." but this map is missing from the National Archives Record Group No. 77, Records of the Office of the Chief of Engineers, Fortifications Map File, Washington, D.C., where it may have been once located.

Park copy of this map, a photostat, received from Vicksburg NHP in 1958. Location of the original map is unknown.

Harpers Ferry NHP Map No. 35, in Map, Case, Drawer No. 12.

Hypothetical arrangement of the 1841-59 rent roll house identification numbers by Charles W. Snell is as follows:

Buildings No. 27, 28, 29, 30, 31, 32, and 33 are Armory Dwelling Houses located on Block AA, Camp Hill, and fronting on what later became North Cliff and then Potomac Street.

House No. 27 is probably Armory Dwelling House No. 66, a one-story frame residence occupied by the master mason Peter Little during the years 1840-1849.

House No. 28 may be Armory Dwelling House No. 67, a two-story brick house located on Lot No.2, Block AA, Camp Hill.

House No. 29 could be Dwelling No. 68, one-story wood.

House No. 30 could be Dwelling No.69,one-story wood.


House No. 31 may be Dwelling No. 70, one-story frame.

House No. 32 may be Dwelling House No. 71, 1 story, frame.


House No.33 could be double house No.72-73, one-story wood.

All of these residences, with the exception of House No. 28(Dwelling No. 67 on Lot 2, Block AA, were demolished in 1849-51.

86 A


Potomac
River
14
Hill Hammes
13
12
11
10
9
8
7
6
5
4
3
15
16
17
18
19
33
32
31
30
29
28
27
U
T
S

86B


Government
Work
Street
Private
Summer Residence
Arsenal
Back Rd
Canal Rd
River
17
18
19
20
21
22
23
24
25
26
27
1
2
3
4
5
6
7
9
A
B
C
D
E
F
G
H
I
J
K
L
M
N
O
P
R
S
T
U

MAP NO. 7

MAP OF HARPER'S FERRY(1848-51)
Prepared in Compliance with Letter to Major(John) Symington, April 22, 1848,' Drawn by S. Howell Brown in 1848. The section of the map relating to Virginius Island was revised and updated by Superintendent Symington(in red inck) in January 1851. Scale 165 feet to inch.

Original lien map, only existing copy is Harpers Ferry NHP Map No. 77, in Park Map Case, Drawer No.4.

While Brown fails to include the numbered Armory Dwelling Houses on this detailed map, he does indicate the house lot system and streets as they existed in 1848.

The arrangement of the House Numbers 66 to 89, fronting on North Cliff or Potomac Street and both sides of "Crooked Lane Street" is conjectional, except for House No. 67, which is known to have been Located on Lot 2, Block AA, and fronting on North Cliff Street.


p. 87A
Public
Grave Yard.
Jefferson Rock
N
PREPARED

MAP NO. 8

" Map of HarperS Ferry - Plat of the Harpers Ferry Armory Property laid off into lots for sale in pursuance of the Act of December 15th, 1868. Approved November 16th 1869 by Wm. W. Belknap, Secretary of War. Map completed by S. Howell Brown, Nov. 1,1869. Scale 165 feet per inch."


Copied by Architect Archie W. Franzen from an original linen drawing in color, which in turn had been copied from the original by Pusey & Jone Company, Nov.26, 1901.

Harpers Ferry NHP Map No. 83, Map Case, Drawer No. 10.

On his 1852 map, Surveyor S. Howell Brown had subdivided part of the U.S. Armory lands in to 312 building lot. In 1869 he subdivided the remaining undivided U.S. owned land into 188 additional building lots, thus bringing the grand total of lots to 500. Two hundred and twenty-four of these lots had been sold in 1852; 31 additional lots were donated in 1869, and the balance were to be offered at public auction in December 1869.

Conjectural arrangement of the U.S. Armory Dwelling Houses No. 66 to 89, as standing in 1841.

88 A


CANAL
MUSKET FACTORY
N
SEMINARY LOT
ST.
MAGAZINE HILL
BB
CROOK Road Lane
HIGH ST.
M.E. CH.
CHURCH St.
M.P. CH.
ALLEY
CLAY ST.
YOUNG ST.
PUBLIC SQUARE
HARPER
STORER COLLEGE
GRAVE YARD
4 ACRES
EE
CATHOLIC SCHOOL LOT
PRESBYTERIAN CHURCH
JEFFERSON'S LOT
H.E.
P.P.
C.P.
BRID
TON

Armory Reserve along base Hill

Proposed Street

Washington

Street

S.

Sheet.

5. for District.

B. by the Government

MAP NO. 11

MAP OF HARPER'S FERRY(1848-51)

Prepared in Compliance with Letter to Major(John) Symington, April 22, 1848,' Drawn by S. Howell Brown in 1848. The section of the map relating to Virginius Island was revised and updated by Superintendent Symington(in red inck) in January 1851. Scale 165 feet to inch.

Original Linen map, only existing copy is Harpers Ferry NHP Map No. 77, in Park Map Case, Drawer No.4.

While Brown fails to include the numbered Armory Dwelling Houses on this detailed map, he does indicate the house lot system and streets as they existed in 1848.

1841-52 House identification numbers have been added to the map by Charles W. Snell.

Camp Hill Section of Map.

Legend:

A. Presbyterian Church
B. Catholic Church
C. Methodist Episcopal Church
D. Methodist Protestant Church
E. Engine House
H. Methodist Episcopal Parsonage lot
P Pumps
S Springs.

Large S - Harpers Ferry Female Seminary Lot.
F. Lutheran Church Lot.

C.O.'s Quarters, the Commanding Officer's or Superintendent's Residence.


N
U.S. Magazine
151 (?)
152
C.S.
D.S.
U.S.C.
U.S.C.
U.S.C.
F
156?
149
158
114
113
112
111
110
109
116
117
118
C.S. Stable
C.S. Quarters
154

148
147?
F
150?
149?
145
114
113
112
111
110
109
108
107
106
105
104
103
102
101
100
99
98
97
S
96
96A
94
93
92
POND
116
117
118
119
120
121
122
123
124
127
128
131
133
135
138
146
134
136
137
139
140
142
G
144
141
143
125
126
129
130
Pay Masters Quarters
185
Public
Grave
20' Stable
C.O. Quarters
N

MAP NO. 12

"Map of Harpers Ferry, 1852,
by S. Howell Brown," Approved by Col. Benjamin Huger,
Superintendent, Harper's Ferry Armory, April, 1852.
Scale 165 feet to the inch. The working copy made by
A. M. Kitzmiller, Superintendent's Clerk. This MS linen
map is the only known extant copy of Brown's 1852 map.

Harpers Ferry NHP Map No. 89, Park Map Case, Drawer No. 3.

On June 10, 1852, Secretary of War C. M. Conrad approved this map or plat on which surveyor S. Howell Brown laid out 312 house lots from the U.S. Armory land at Harpers Ferry. These were offered for sale on August 31 and September 1-2, 1852.

The map shows the new street systems that were established and all the public lands and boundaries thereof that were reserved from the 1852 sale for continued U.S. use. Two hundred and twenty-four building lots were sold in 1852.

Camp Hill Section of Map.

FERRY
ROAD

MAP NO. 13

" Map of HarperS Ferry - Plat of the Harpers Ferry Armory Property laid off into lots for sale in pursuance of the Act of December 15th, 1868. Approved November 16th 1869 by Wm. W. Belknap, Secretary of War. Map completed by S. Howell Brown, Nov. 1,1869. Scale 165 feet per inch."

Copied by Architect Archie W. Franzen from an original linen drawing in color, which in turn had been copied from the original by Pusey & Jone Company, Nov.26, 1901.


Harpers Ferry NHP Map No. 83, Map Case, Drawer No. 10.

On his 1852 map, Surveyor S. Howell Brown had subdivided part of the U.S. Armory lands in to 312 building lot. In 1869 he subdivided the remaining undivided U.S. owned land into 188 additional building lots, thus bringing the grand total of lots to 500. Two hundred and twenty-four of these lots had been sold in 1852; 31 additional lots were donated in 1869, and the balance were to be offered at public auction in December 1869.

Camp Hill Section of Map.

Numbered Armory Dwelling Houses of the 1841-52 period have been added to the 1869 by Charles W. Snell.


S T.
S T.
S T.
S T.
P O
W
X
Y
Q
R
O
P
K
L
M A R I O N
F R A N K L I N
R I D G E
U N I O N S Q U A R E
L U T H E R A N C H.
S. CH.
LOT
W A S H I N G T O N
J A C K S O N
F I L L M O R E
B O U N D A R
STORER COLLEGE
1502
1517
1627
1407
1467


SEMINARY LOT
S T.
MAGAZINE HILL
BB
M.E. PAR.
PUBLIC SQUARE
M.P. CH. PAR.
ODD FELLOWS
STORER COLLEGE
JACKSON
YOUNG
CLAY
HARPER
GRAVE ACRES
S. CLIFF
YORK

ARMORY DWELLING HOUSE NO. 90 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block BB Lot No. 4 & 5 Washington Street, Camp Hill.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Wm. Ferrill	8.00	8.00	
Dec. 31, 1844	Brick					Thomas Earnshaw	9.20	14.45	George W. Ferrill deliquent 17.68
Dec. 31, 1846	Brick					William Simpson	10.00	10.00	G.W. Ferrills owe 17.68.
June 30, 1849	Brick	1		11	300	John Shewbridge	8.75		
Dec.31,1 1850	Brick	1		12	250	Austin McCorn	8.75	8.75	Geo. W. Ferrall owed 17.68
June 30, 1851	Brick	1				House demolished and materials sold May 31, 1851			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: One story brick house erected 1798-1833 and demolished May 31, 1851.

House apparently one of four one-story brick row houses (Nos. 90 - 93) that were all demolished in May 1851.

ARMORY DWELLING HOUSE NO. 91 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block BB Lot No. 4 & 5 Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Wm. Bilson(or Belson)	6.25	6.25	
Dec. 31, 1844	Brick					William A. Roderick	7.15	8.70	
Dec. 31, 1846	(sic) Wood					Lewis E. Gore	7.15	7.15	
June 30, 1849	Brick	1		10	400	Lewis E. Gore	7.50		
Dec.31,1 1850	Brick	1		12	250	House demolished and materials sold May 31,1851			Lewis E. Gore Est owed 15.00;Mrs.Go owed 7.50.
June 30, 1851						House demolished and materials sold May 31,1851			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: One-story brick house erected 1798-1833 and demolished May 31, 1851.

House apparently one of four one-story brick row houses (Nos. 90 to 93) that were demolished in May 1851.

ARMORY DWELLING HOUSE NO. 92 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block BB Lot No. 4 & 5 Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Samuel Compton	6.25	6.25	
Dec. 31, 1844	Brick					Samuel Compton	7.15	7.15	
Dec. 31, 1846	Brick					Samuel Compton	7.15	7.15	
June 30, 1849	Brick	1		11	300	Samuel Compton	7.50		
Dec.31,1 1850	Brick	1		12	250	Samuel Compton	7.50	45.00	Sold May 31, 1851
June 30, 1851	Brick	1				House demolished and sold for materials May 31, 1851			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	none	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: One-story brick house built 1810-1833 and demolished May 31, 1851.

House apparently one of four one-story brick row houses(No. 90-93) all demolished in May 1851.

ARMORY DWELLING HOUSE NO. 93 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block BB Lot No. 4 & 5 Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For location see Park Map No. 80 - 1850

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Thomas Russell Jr.	6.25	6.25	
Dec. 31, 1844	Brick					Harrison L. Clowe	7.15	7.15	
Dec. 31, 1846	Brick					Harrison L. Clowe	7.15	7.15	
June 30, 1849	Brick	1		11	300	H. L. Clowe	7.50		
Dec.31,1 1850	Brick	1		12	250	Lewis Johnson (?)	7.50	7.50	Sold 31 May 1851
June 30, 1851						House demolished and materials sold 31 May 1851.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	None	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: One-story brick house erected 1811-33 and demolished May 31, 1851.

House apparently one of four one-story brick row houses (Nos. 90 - 93) all demolished in May 1851.

ARMORY DWELLING HOUSE NO. 94 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block BB Lot No. 6, Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For location see Park Map No. 80 - 1850

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Wm. Stipes	3.50	3.50	
Dec. 31, 1844	Wood					John D. Stipes	4.00	4.00	
Dec. 31, 1846	Wood					Ezekial Stipes	4.00	4.00	
June 30, 1849	Wood	1		15	100	Ezekiel Stipes	5.00		
Dec.31,1 1850	(sic) Stone	1		11	300	Ezekiel Stipes	7.00	14.00	
June 30, 1851	Stone					Mrs Stipes			
June 30, 1852						Mrs. Stipes			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: One and one-half story frame house built ca. 1811-29 and reserved from the 1852 sale for U.S. use. House renumbered as Armory Dwelling House No. 22, Camp Hill, about 1859. Described in July 1865 as "one and one-half store frame(house), in good condition and occupied by Mrs. M. Stipes, by order of Col. H(enry) K. Craig." This house and lot were sold to Valinda Stipes for $ 5.00 in December 1869. The U.S. issued the dded to Mrs. Stipes on January 13, 1870.

ARMORY DWELLING HOUSE NO. 95 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block BB Lot No. 9, Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80 - 1850

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Claspy *	8.00	8.00	
Dec. 31, 1844	Wood					John Claspy	9.20	9.20	
Dec. 31, 1846	Wood					John Claspy	9.20	9.20	
June 30, 1849	Wood	2		8	500	John Claspy	10.00		
Dec.31,1 1850	Wood	1		9	450	John Claspy	10.00	10.00	
June 30, 1851	Wood	1				John Claspy			
June 30, 1852	Wood	1				John Claspy			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: One story frame house built 1811-33 and reserved from 1852 sale for U.S. use. House demolished in period 1855-1859. Not standing in 1861.

*John Claspy had an October 1831 claim of $ 40.00 for building a shed.

ARMORY DWELLING HOUSE NO. 96 (1841-1858) HARPER"S FERRY, ARMORY, VA.

SCHOOL HOUSE

Location: Block BB Lot No 10, Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Abraham Berlin *	4.00	4.00	
Dec. 31, 1844	Wood					Vacant			
Dec. 31, 1846	Wood					William Earle	3.00	3.00	
June 30, 1849	Wood	1				School Room	Free		
Dec.31,1 1850	Wood	1		16	50	Used as School room	Free	Free	
June 30, 1851	Wood	1				School Room			
June 30, 1852	Wood	1				Demolished and materials sold in 1852.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: One-story frame house built 1811-33 and demolished in 1852. Used as a school room, 1849-52.

House stood immediately east (or south) the town pump at junction of Clay and Washington Street.

* Abraham Berlin paid $ 57.84 on December 31,1823 for building a small frame house. R.G. 217, 1st Series, File 7624, Voucher 116A.

ARMORY DWELLING HOUSE NO. 97 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 1, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					David Gilbert	15.00	15.00	
Dec. 31, 1844	Brick					Meshac Kirby	17.25	34.50	
Dec. 31, 1846	Brick					Meshac Kirby	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Meshac Kirby	17.50		
Dec.31,1 1850	Brick	2		6	800	Meshac Kirby	17.50	17.50	
June 30, 851	Brick	2				Meshac Kirby			
June 30, 852	Brick	2			900.00	Meshac Kirby			

852 ale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	8/31/52	900.00	Meshac Kirby	July 26, 1866	

emarks: House No. 97, a two- story brick house perhaps erected 1831-32.

The houses built in 1831-32 were 37 by 20 feet, tha cellar s held a kitchen, pantry, and cellar. The first floor, nine feet high, had a central hall and two rooms. The second or half story was divided into three room s. The basements were 8 feet deep with stone wall 22 inches thick. The front and rear brick walls were 14 inches thick and the gable end walls 9 inches thick. The gable roofs were covered with wood shingles. John Markell, who constructed 5 brick houses of this type under contract in 1831-32, received for $ 4,700.00 for his services.

ARMORY DWELLING HOUSE NO. 99 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 3, Camp Hill - Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For Location see Park Map No. 80.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Joseph McKee	15.00	15.00	
Dec. 31, 1844	Brick					Joseph McKee	17.25	17.25	
Dec. 31, 1846	Brick					Joseph McKee	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Joseph McKee	17.50		
Dec. 31, 1850	Brick	2		6	800	Joseph McKee	17.50	17.50	
June 30, 1851	Brick	2				Joseph McKee			
June 30, 1852					900.00	Joseph McKee			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 900.00	Joseph MCKee	October 13, 1859

Remarks: House No. 99, a two- story brick house perhaps erected in 1831-32. Photo HF-63(1865).

The houses built in 1831-32 were 37 by 20 feet, the cellar s held a kitchen, pantry, and cellar. The first floor, nine feet high, had a central hall and two rooms. The second or half story was divided into three room s. The basements were 8 feet deep with stone wall 22 inches thick. The front and rear brick walls were 14 inches thick and the gable end walls 9 inches thick. The gable roofs were covered with wood shingles. John Markell, who constructed 5 brick houses of this type under contract in 1831-32, received for $ 4,700.00 for his services.

(100 and 101)

ARMORY DWELLING HOUSE NO. 100 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 5, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For Location see Park Map No. 80 - 1850

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone & wood					Benjamin Stipes *	10.00	10.00	
Dec. 31, 1844	Stone & wood					Francis Wentzle	11.50	23.00	
Dec. 31, 1846	Wood & Stone					Francis Wentzle	11.50	11.50	
June 30, 1849	Wood	2		8	500	J.W. Cruchley	12.50		
Dec.31,1 1850	Wood	1		10	400	J. W. Cruchley	12.50	12.50	
June 30, 1851	Wood	1				J. W. Crutchley			
June 30, 1852					400.00 and with House No. 101, total appraised value was $				800.00

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 800.00	Asa Marsteller	December 12,1856

Remarks: House No. 100, a one story- frame and stone house, forming a duplex house with House No. 101. both erected 1811- 33 and sold in 1852, including Houses 100-101 and lot, for $ 800.00.

House No. 101, a one-story frame house, erected 1811-33.
Benjamin Stipes had an October 1831 claim of $ 30.00 for building a stable, privy and fence. He was paid $ 21.30 in settlement of this claim on November 9, 1837. R.G. 217, 2nd Series, File 2094, Voucher 115B.

(100-101)

ARMORY DWELLING HOUSE NO.101 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 5, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For Location see Park Map No. 80 - 1850

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone & wood 101					John Marstellar	10.00	10.00	
Dec. 31, 1844	Wood					John Marstellar	11.50	11.50	
Dec. 31, 1846	Wood					John Marstellar	11.50	11.50	
June 30, 1849	Wood	2		8	500	John Marstellar	12.50		
Dec.31,1 1850	Wood	1		10	400	Asa Marsteller	12.50	12.50	
June 30, 1851	Wood	1				Asa Marsteller			
June 30, 1852					400.00	appraised value of House 101, which House 100 included, total value of 2 houses and lot was $ 800.00			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 800.00	Asa Marstellar	December 12, 1856

Remarks: House No. 101, a one-story frame house erected 1811-33, with House No. 100-wood and stone, also one-story, forming a duplex house on same lot.

SCHOOL ROOM

ARMORY DWELLING HOUSE NO. 102 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block E Lot No. 6, Camp Hill, Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For Location see Park Map No. 80 - 1850

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Valemtine McKann	4.00	8.00	Delinquent 4th qr. of 1840
Dec. 31, 1844	Wood					Not listed(probably a school room)			
Dec. 31, 1846	Wood					school room			
June 30, 1849	Wood	1		School room		Mrs. Bates-School Room	Free		
Dec.31,1 1850	Wood	1		14	150	School Room	Free	Free	
June 30, 1851	Wood	1				House apparently demolished in 1852			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	8/1/52	$ 500.00	Rezin Cross	December 12, 1856	Vacant lot sold at public auction, 185

Remarks: One-story frame house located apparently on Lot 6 and erected 1811-33. House must have been removed or demolished in early 1852, For Lot 6 was sold as a vacant lot on September 1-2, 1852 at the public auction to Rezin Cross. No house on lot.

ARMORY DWELLING HOUSE NO. 103 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block F Lot No. 1, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					William Apsey, Machinist	Free	Free	
Dec. 31, 1844	Brick					Louisa Apsey	17.25	49.50	
Dec. 31, 1846	Brick					Zadoc Butt, Inspector	Free	Free	
June 30, 1849	Brick	2		5	1,000	Solomon Cohen , Clerk	Free		
Dec. 31, 1850	Brick	2		5	900	Henry W. Clowe(Machinist)	Free	Free	Clowe was to become Superintendent in 1855.
June 30, 1851	Brick	2				H.W. Clowe, Machinist	"	"	
June 30, 1852					900.00	H. W. Clowe, Machinist	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 900.00	Henry W. Clowe	September 5, 1856.

Remarks: House No. 103 was a two- story brick house that was probably erected in 1837-38.

In 1837-38 dwellings, the main house was brick, 2- stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 12 by 16 feet in size.

ARMORY DWELLING HOUSE NO. 104 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block F Lot No. 2, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For Location see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Joseph Britton	10.00	10.00	
Dec. 31, 1844	Brick					Joseph Brittain	11.50	11.50	
Dec. 31, 1846	Brick					Joseph Brittain	11.50	11.50	
June 30, 1849	Brick	2		9	450	Joseph Brittain	11.50		
Dec. 31, 1850	Brick	1		10	400	Eml. Spangler	11.50	11.50	Joseph Brittain owed 23.00
June 30, 1851	Brick	1				Emanuel Spangler			
June 30, 1852					475.00	ED Emanual Spangler			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 475.00	Emanuel Spangler	October 18, 1852.

Remarks: House No. 104 was a one-story brick house erected ca. 1830-34.

This one-story brick house may have been the replacement house constructed for the dwelling at the northeast corner of Arsenal Square, Lot 1, Block A, Shenandoah Street, that was taken over for use as the Superintendent's Office. The arsenal house, a one-story brick dwelling 28 by 21 feet, with hip roof, was remodelled into a office in 1832-33(see House No. "190"). In December 1833 the masons Mullen and Spencer were paid $ 382.52 for building one brick house and Daniel Lasham, who did the carpenter work on this residence, received $ 203.68 for his services, also in December 1833. The replacement house may be either House 104 or No. 140, the only one-story brick houses on Camp Hill prior to 1852.

ARMORY DWELLING HOUSE NO.105 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block F Lot No. 4, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry For location see Park Map
S. Howell Brown's 1869 Map of Harpers Ferry No. 80- 1850

Date of Rent Roll	Material built of	No.of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Henry Clowe	8.00	8.00	
Dec. 31, 1844	Stone					Henry W. Clowe	9.20	9.20	Clowe was to becom Armory Supt. in 1855.
Dec. 31, 1846	Stone					Henry W. Clowe	9.20	9.20	
June 30, 1849	Wood	2		8	500	Henry W. Clowe	9.25		
Dec.31,1 1850	Stone	1		9	450	H. L. Clowe	9.25	9.25	
June 30, 1851	Stone	1				H. L. Clowe			
June 30, 1852					600.00				

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 600.00	Philip Schaarsman	December 12, 1856

Remarks: House No. 105 was a one-story stone dwelling erected 1822-33

ARMORY DWELLING HOUSE NO.106 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block F Lot No. 3, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80- 1850

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Abrose(Ambrose) Cross	5.00	20.00	
Dec. 31, 1844	Wood					Ambrose Cross	5.75	5.75	
Dec. 31, 1846	Wood					Ambrose Cross	5.75	5.75	
June 30, 1849	Wood	2		8	500	Ambrose Cross	7.50		
Dec.31,1 1850	Wood	1		10	400	Ambrose Cross	7.50	7.50	
June 30, 1851	Wood	1				Ambrose Cross			
June 30, 1852					175.00	Ambrose Cross			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 175.00	Ambrose Cross	December 12, 1856.

Remarks: House No. 106 was a one-story frame house erected ca. 1811-33.

ARMORY DWELLING HOUSE NO. 107 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block G Lot No. 1, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Benjamin Moor,Jr.,Clerk	Free	Free	the son of master armorer,Benjamin Moor.
Dec. 31, 1844	Brick					Benjamin Moor,Jr., Clerk	Free	Free	
Dec. 31, 1846	Brick					Benjamin Moor, Clerk	Free	Free	
June 30, 1849	Brick	2		5	1,000	Benjamin Moore, Jr. Clerk	Free		
Dec.31,1 1850	Brick	2		5	900	James B. Young (Foreman)	Free	Free	Benj. Moor, Jr. owed 31.25 in ren
June 30, 1851	Brick	2				J. B. Young, Foreman	Free	Free	
June 30, 1852					1,000.00	J. B. Young, Foreman	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 1,000.00	Jerome B. Young	June 9, 1854.

Remarks: House No. 107, a 2- story brick house that was probably erected in 1837-38.

In 1837-38 dwellings, the main house was brick, 2- stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 12 by 16 feet in size.

ARMORY DWELLING HOUSE NO. 108 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block G Lot No. 2, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Isaac Yantis	10.00	10.00	
Dec. 31, 1844	Wood					Isaac Yantis	11.50	11.50	
Dec. 31, 1846	Wood					Isaac Yantis	12.00	12.00	
June 30, 1849	Wood	1		8	500	Isaac Yantis	12.50		
Dec.31,1 1850	Wood	1		8	500	Solomon Yantis	12.50	12.50	
June 30, 1851	Wood	1				Solomon Yantis			
June 30, 1852					500.00	Solomon Yantis			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 500.00	Philip Burkart	December 12, 1856

Remarks: House No. 108 was a one-story frame dwelling built 1811-1833.

ARMORY DWELLING HOUSE NO. 109 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block G Lot No. 3, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Duke*	9.00	72.00	Delinquent from 4th qr. of 1840.
Dec. 31, 1844	Wood					James F. Duke	10.35	10.35	John Duke owes 62.13.
Dec. 31, 1846	Wood					James F. Duke	10.35	22.18	John Duke owes 62.13.
June 30, 1849	Wood	2		8	500	Talcott Duke	10.50		
Dec. 31, 1850	Wood	1		9	450	Talcott S. Duke	10.50	10.50	John Duke owes 62.13; James F. Duke owes 29.79.
June 30, 1851	Wood	1				T. S. Duke			
June 30, 1852					600.00	John Duke			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 600.00	John Duke	October 13, 1859.

Remarks: House No. 109 was a one-story frame dwelling erected ca. 1811-33.

John Duke had an October 1831 claim of $ 390.00 for building a log house 19 by 24 feet complete, also privy, stable, fence, stone wall. He was paid $ 279.49 in settlement of this claim on April 26, 1837. R.G. 217, 2nd Series, File 1423. This house was apparently erected in 1825.

ARMORY DWELLING HOUSE NO. 110 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block G Lot No. 4, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Jerome & J. Wright	15.00	15.00	
Dec. 31, 1844	Brick					Jerome B. Wright	17.25	17.25	
Dec. 31, 1846	Brick					Jerome B. Wright	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Jerome B. Wright	18.00		
Dec. 31, 1850	Brick	2		6	800	John Russell of TH(?)	18.00	18.00	Jerome B. Wright owed 18.00
June 30, 1851	Brick	2				John Russell of TH(?)			
June 30, 1852					1,000.00	John Russell			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 1,000.00	John Russell	To John E.P. Daingerfield Sept. 5, 1856.

Remarks: House No. 110, 2- story brick, probably erected 1837-38. John Russell purchased the house on August 31, 1852 for $ 1,000.00 and sold it for the same price to John E. P. Daingerfield, the Armory Paymaster's Clerk, on the same date. The U.S. issued the date for the property to Daingerfield in 1856, when he completed his payments.

In 1837-38 dwellings, the main house was brick, 2-½ stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 12 by 16 feet in size.

ARMORY DWELLING HOUSE NO. 111 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block II Lot No.1 , Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For Location See Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John Lewellyn	15.00	15.00	
Dec. 31, 1844	Brick					John Lewellyn	17.25	17.25	
Dec. 31, 1846	Brick					John Lewelyn	17.25	17.25	
June 30, 1849	Brick	2		6	800	John Cavallier	17.50		
Dec.31,1 1850	Brick	2		7	600	Benjamin Ott	17.50	17.50	John Lewellyn owed 35.72
June 30, 1851	Brick	2				Daniel J. Young			
June 30, 1852					825.00				

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 825.00	Daniel J. Young	September 5, 1856.

Remarks: House No. 111. a two- story brick house probably erected in 1831-32.

The houses built in 1831-32 were 37 by 20 feet, the cellar s held a kitchen, pantry, and cellar. The first floor, nine feet high, had a central hall and two rooms. The second or half story was divided into three room s. The basements were 8 feet deep with stone wall 22 inches thick. The front and rear brick walls were 14 inches thick and the gable end walls 9 inches thick. The gable roofs were covered with wood shingles. John Markell, who constructed 5 brick houses of this type under contract in 1831-32, received for $ 4,700.00 for his services.

ARMORY DWELLING HOUSE NO. 112 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block H Lot No. 2, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Located, see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Adam Rhulman, Inspector	Free	Free	
Dec. 31, 1844	Brick					Adam Rhulman, Inspector	Free	Free	
Dec. 31, 1846	Brick					Adam Rhulman, Inspector	Free	Free	
June 30, 1849	Brick	2		5	1,000	Adam Rhilman, Inspector	Free		
Dec. 31, 1850	Brick	2		5	900	Adam Rhulman , Foreman	Free	Free	
June 30, 1851	Brick	2				Adam Rhulman, Foreman	Free	Free	
June 30, 1852					1,110.00	Adam Rhulman, Foreman	Free		

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 1,100.00	Adam Rhulman	May 11, 1860

Remarks: House No. 112 was a two- story brick house probably built in 1837-38.

In 1837-38 dwellings, the main house was brick, 2- stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 12 by 16 feet in size.

ARMORY DWELLING HOUSE NO. 113 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block II Lot No. 3, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Cruchley *	5.00	5.00	
Dec. 31, 1844	Wood					John W. Crutchley	5.75	5.75	
Dec. 31, 1846	Wood					John W. Crutchley	5.75	5.75	
June 30, 1849	Wood	1		12	250	John Russell	5.75		
Dec. 31, 1850	Wood	1		15	100	John Russell(Father)	5.75	5.75	
June 30, 1851	Wood	1				John Russell (Father)			
June 30, 1852						House broken up in 1852.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Leased	none	none	none. Vacant lot in 1852

Remarks: House No. 113, a one-story frame dwelling was erected 1811-33 and demolished in 1852. The vacant lot was then leased by the U.S. to Methodist Episcopal Church for use as a parsonage lot. On January 13, 1870, the U.S. donated this lot to the Methodist Episcopal Church.

* John Crutchly had an 1829 claim of $ 150.00 for a wooden dwelling he had erected in 1825.

ARMORY DWELLING HOUSE NO. 114 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block H Lot No. 4, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For locations see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Thomas Lewellyn (sic)	5.00	5.00	
Dec. 31, 1844	Wood					Thomas Llewelyn	5.75	5.75	
Dec. 31, 1846	Wood					Thomas Llewelyn	5.75	5.75	
June 30, 1849	Wood	1		12	250	Thomas Llewelyn	5.75		
Dec. 31, 1850	Wood	1		10	400	Thomas Llewellyn	8.50	8.50	
June 30, 1851	Wood	1				Thomas Llewellyn			
June 30, 1852					400.00	Thomas Llewellyn			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	8/31/52	$ 400.00	Thomas Llewellyn	Final deed never issued as Llewellyn did not complete his pa	

Remarks: House No. 114, a one-story frame house erected 1811-33. Thomas Llewellyn purchased the dwelling at the private sale held August 31,1852 at the appraised price, $ 400.00. Up to December 31,1860, however, he had paid in only $ 156.25 of the total of $ 400.00 due on the house and lot. Llewellyn , the only armorer not to complete payment on the 1852 house, thus never received a deed for the property. The wooden house may have been destroyed by fire in the period 1854-1860. The house was not standing in December 1869, when Lot 4, Block H, described as a vacant lot, was donated to the Methodis Epsicopal Church, together with Lot No. 3, as a parsonage lot on January 13, 1870.

ARMORY DWELLING HOUSE NO. 115 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block I Lot No. 1, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For location see Park Map No. 80- 1850.

Date of Rent Roll	Material built of	No.of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					William B. Yeaman *	5.00	25.00	Delinquent from 4th qr of 1840
Dec. 31, 1844	Wood					William Yeaman	5.00	55.00	
Dec. 31, 1846	Wood					Mrs. Yeaman	1.00	87.00	
June 30, 1849	Wood	1		16	50	Mrs, Yeaman		88.00	
Dec.31,1 1850	Wood	1		16	50	Vacant			Mrs. Yeaman owed $ 88.00
June 30, 1851	Wood	1				Broken up in 1852			
June 30, 1852									

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	9/1/52	$ 325.00	William Richards	December 12,1856	Vacant lot sold at public auction,1852.

Remarks: House No. 115, a one-story frame dwelling, was erected 1811-33 and demolished in 1852.

*In 1828 Nathan Yeaman was paid $ 296.03 for building a wooden house.

ARMORY DWELLING HOUSE NO.116 (1841-1858) HARPER"S FERRY, ARMORY, VA.
Storer College Lot on 1869 Map.

Location: Block II Lot No Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry at Jackson Street.
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Henry Miller, Inspector	Free	Free	In 1837-38 houses the main house was ~~brick, 2-stories~~
Dec. 31, 1844	Brick					Thomas Chapman	17.25	17.25	28 by 22 feet, wi a stone foundatic 20 inches thick.
Dec. 31, 1846	Brick					Thomas Chapman	17.25	17.25	The front and back brick walls were 14 inches thick
June 30, 1849	Brick	2		4	1,200	J.H. King, Director, Rifle Factory	Free		and the gable end walls 9 inche thick. The rear
Dec.31,1 1850	Brick	2		5	900	N. W. Dearing	20.00	20.00	kitchen wing,bric was one-story, wit a cellar undernea
June 30, 1851	Brick	2				N.W. Dearing			The stone cellar foundations were 20 inches thick.
June 30, 1852						N. W. Dearing			The kitchen wing w 12 by 16 feet in size.

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from U.S 1852 sale for U.S. use.

Photo HF- 60(1865).

Remarks: House No. 116, a 2- story brick dwelling erected 1837-38. and reserved from the 1852 sale for U.S use. Used as an armory dwelling house 1853-1861 and renumbered as Armory Dwelling No. 23. The residen ce was described in July 1865 as"Armory Dwelling No. 23, Camp Hill, two-story brick, in bad condition and being used for army purposes." Lot No. 2, Blocck II, and House No. 23, were donated by the U.S. to the Independent Order of Odd Fellows, Virginia Lodge No. 1, on January 1,1870, as replacement and compensation for their lodge structure which had been badly damaged by Union soldiers in 1862-63. Their lodge room had formed the upper story of the Methodist Protestant E Church, a stone structure about 30 by 50 feet. The lodge had filed as claim asking for $ 1,500 to repair the damage.

ARMORY DWELLING HOUSE NO. 117 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block II Lot No. 2, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					William Cruzen*	8.00	8.00	
Dec. 31, 1844	Wood					George Cruzen	9.20	9.20	William Cruzen Estate owed 16.00
Dec. 31, 1846	Wood					George Cruzen	9.20	9.20	
June 30, 1849	Wood	1		7	600	George W. Cruzen	11.25		
Dec.31,1 1850	Wood	1		9	450	George W. Cruzen	11.25	11.25	Wm.Cruzen estate owed 16.00
June 30, 1851	Wood	1				George W. Cruzen			
June 30, 1852						George W. Cruzen			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot and house reserved from 1852 sale for U.S. use.

Remarks: House No. 117, a one-story dwelling was erected 1811-33 and reserved from the 1852 sale for armory use. The house was demolished in the period 1855 to 1859.

* William Crusen was paid $ 173.00 in 1831 for improvements he had made to a dwelling house.

ARMORY DWELLING HOUSE NO. 118 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block II Lot No. 1, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Asaph Wilson, Inspector	Free	Free	
Dec. 31, 1844	Brick					Asaph Wilson, Inspector	Free	Free	
Dec. 31, 1846	Brick					Asaph Wilson, Inspector	Free	Free	
June 30, 1849	Brick	2		5	1,000	Asaph Wilson, Inspector	Free		
Dec. 31, 1850	Brick	2		5	900	John L. Rowe	18.25	18.25	Asaph Wilson owed 18.75
June 30, 1851	Brick	2				J. L. Rowe			
June 30, 1852						J. L. Rowe			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	None	House and lot reserved from 1852 sale for U.S. use.

Photo HF-60(1865).

Remarks: House No. 118, a two-story brick dwelling erected 1837-38. House reserved from 1852 sale and renumbered about 1859 as Armory Dwelling House No. 24. This house was described in July 1865 as "Two-story, brick, in good condition, occupied by Ordnance Agent Daniel J. Young as private quarters." Young was still living there as ordnance storekeeper in December 1869. Mary D. Young purchased the house and lot from the United States for $ 1,200.00 on December 6, 1869. The U.S. issued the deed to Mrs. Young on December 5, 1871.

In 1837-38 dwellings, the main house was brick, 2- stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 13 by 16 feet in

ARMORY DWELLING HOUSE NO. 119 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 4, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location of house see Park Map No. 73- 1848.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Joshua Cox *	15.00	15.00	
Dec. 31, 1844	Brick					Thomas Sturdy	17.25	33.32	
Dec. 31, 1846	Brick					Thomas Sturdy	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Thomas Sturdy	17.50		
Dec.31,1 1850	Brick	2		5	900	Thmas K. Laley, (Foreman)	Free	Free	Thomas Sturdy estate owed 71.88
June 30, 1851	Brick	2				T. K. Laley, Foreman	Free	Free	
June 30, 1852					1,000.00	T. K. Laley ,Foreman	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 1,000.00	Adam Brown	September 5, 1856

Remarks: Photo HF-60(1865) may show rear of house.
House No. 119 was a two--story brick dwelling probably built in 1837-38.
* Joshua Cox had been paid $ 65.00 in 1822 for erecting a wooden dwelling.

In 1837-38 dwellings, the main house was brick, 2- stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 12 by 16 feet in size.

ARMORY DWELLING HOUSE NO. 120 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block D Lot No. 3, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry For location see Park Map
S. Howell Brown's 1869 Map of Harpers Ferry No. 73 - 1848.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Jesse Bateman	15.00	15.00	
Dec. 31, 1844	Brick					John Avis	17.25	49.34	
Dec. 31, 1846	Brick					John Avis	17.25	187.34	
June 30, 1849	Brick	2		5	1,000	W. D. Riley	17.50		
Dec. 31, 1850	Brick	2		6	800	Wm. D. Riley	17.50	17.50	Mrs. Avis owed 28.75; John Avis estate owed 210.
June 30, 1851	Brick	2				W. D. Riley			
June 30, 1852					1,000.00	W. D. Riley			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 1,000.00	William D. Riley	December 12, 1856.

Photo HF-60(1865) may show rear of house.

Remarks: House No. 120, a two- story brick house perhaps erected in 1837-38.

147

In 1837-38 dwellings, the main house was brick, 2- stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The

ARMORY DWELLING HOUSE NO. 121 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 1, Camp Hill Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 73 - 1848.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Meshac Kirby *	8.25	8.25	
Dec. 31, 1844	Wood					Francis C. Melhorn	9.45	9.45	
Dec. 31, 1846	Wood					Francis C. Melhorn	12.00	12.00	
June 30, 1849	Wood	1		7	600	F. C. Melhorn	12.50		
Dec. 31, 1850	Wood	1		8	500	F. C. Melhorn	12.50	12.50	
June 30, 1851	Wood	1				F. C. Melhorn			
June 30, 1852					600.00	F. C. Melhorn			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 600.00	Francis C. Melhorn	October 13, 1859

Remarks: House No. 121, a one-story frame house erected 1811-33.

Photos: HF-60(1865) may show rear of house; HF-63 (1865).
* Meshac Kirby was paid $ 286.66 on December 31, 1823 for building a frame house 24 by 16 feet, 2 stories. R.G. 217, 1st Series, File 7624, Voucher 167A.

ARMORY DWELLING HOUSE NO. 122 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block C Lot No. 3 and 4, Lot No. 3, Camp Hill Town Square, Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Joshua Riley*	6.25	6.25	
Dec. 31, 1844	Wood					Singleton Chambers	14.35	14.35	
Dec. 31, 1846	Wood					Singleton Chambers	14.35	14.35	
June 30, 1849	Wood	1				Singleton Chambers	15.00		
Dec. 31, 1850	Wood	1		10	400	Singleton Chambers	11.50	11.50	
June 30, 1851	Wood	1				Singlton Chambers			
June 30, 1852					475.00	Singleton Chambers			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	475.00	Singleton Chambers	June 9, 1857 included Lot 4.

Remarks: House No. 122, a one-story frame house erected 1811-1833. House No. 122 straddled Lots No. 3 and 4 in Block C.

Photos HF-60(1865), may show rear of house; HF-63 (1865).
* Joshua Riley was paid $ 225.75 on December 23, 1823 for building a wooden house 30 by 16 feet.
R.G. 217, 1st Series, File 7624- Voucher 113A.

ARMORY DWELLING HOUSE NO. 123 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block II Lot No. 1, Camp Hill Fillmore Street at McDowell Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry


Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone Room	(store?)				William S. Elgin	18.75	18.75	
Dec. 31, 1844						not listed (vacant?)			
Dec. 31, 1846									
June 30, 1849						"Broken up in 1845."			
Dec. 31, 1850	Wood	1		-	-	"Broken up in 1845"			
June 30, 1851	Wood	1				Broken up in 1845			
June 30, 1852						vacant lot			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	9/1/52	$ 348.00	William F. Wilson	June 9, 1857	Vacant lot in 1852

Remarks: One-story frame house, apparently a store, built 1811-33 and demolished in 1845. This may have been "a small temporary frame storehouse" that had been erected by Michael K. Wartman under permission given by Superintendent James Stubblefield." Its value in 1829 was estimated to $ 175.00. Stubblefield, in 1829, described it as "situated on the hill between the two rivers. The house upon it is a very small temporary frame house, that may at any time be easily removed."
The store house had been built in 1826


Front view of a Brick Building 23 by 22 feet
One and a half Stories High.
(Traced from Superintendent George Rust, Jr.' plan
submitted April 23, 1833-) Scale 2/10 In. to the Foot.

Eight houses of this type were erected under contract along Fillmore Street in 1833-34 by carpenters James Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy. Cost of construction was $ 8,897.70 for a total of nine brick dwelling house.




MAP NO. 15

First Story of a Brick Building [illegible] 22 feet
One and a half stories high.
(Traced from Superintendent George Platt, Jr.'s plan submitted April 23, 1833) Scale 2/10 In. to the Foot.



Kitchen one story with cellar bel



Tracing Made ... Superintendent ... Dust Jr.'s Map of April 23,1833 to show the loca... of 12 new Govern... ment Dwelling Houses.

ARMORY DWELLING HOUSE NO. 124 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 6, Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					David Claspy	15.00	15.00	
Dec. 31, 1844	Brick					William Copeland	17.25	17.25	
Dec. 31, 1846	Brick					Joseph Lenox	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Joseph Lennox	17.50		
Dec.31,1 1850	Brick	2		6	800	William F. Wilson	17.50	17.50	Benjm McBee Estate owed 43.33. from House 117
June 30, 1851	Brick	2				William F. Wilson			
June 30, 1852					650.00	William F. Wilson			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 650.00	William F. Wilson	June 9, 1857.

Photo HF- 60 (1865).

Remarks: a two-story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2-story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace. In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace.

ARMORY DWELLING HOUSE NO. 125 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block GG Lot No. 3 & 4, Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map or Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Benjamin McBee	15.00	15.00	
Dec. 31, 1844	Brick					Cyrus Sutterland	17.25	17.25	House 117 Benjamin McBee est owed 43.33
Dec. 31, 1846	Brick					Cyrus Southerland	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Cyrus Sutherland	17.50		
Dec. 31, 1850	Brick	2		6	800	F. C. Smith	17.50	17.50	
June 30, 1851	Brick	2				Fred. C. Smith			
June 30, 1852						Fred. C. Smith			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	none	none	House and lot reserved from U.S sale of 1852 for armory use.	

Remarks: a two- story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2- story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace. House withheld from 1852 sale and renumbered as House 26 about 1859. Torn down by Union soldiers, under orders from Brig. Genl. J.D. Stevenson in 1864, who used the bricks to built their winter quarters.

ARMORY DWELLING HOUSE NO. 126 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block GG Lot No. 2 Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Wm. T. A. Pollock	15.00	15.00	Pollock had 1829 claim of $ 352.72 for a wooden house he erected in 1825
Dec. 31, 1844	Brick					Samuel J. Lindsay	17.25	17.25	
Dec. 31, 1846	Brick					Samuel J. Lindsay	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Joseph Martin	17.50		
Dec.31,1 1850	Brick	2		6	800	J. R. Martin	17.50	17.50	
June 30, 1851	Brick	2				J. R. Martin			
June 30, 1852						J. R. Martin			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: a two- story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2- story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace. House withheld from 1852 sale and renumbered Armory Dwelling No. 27 about 1859. Torn down by Union soldiers in 1864, under orders from Brig. Gen. J. D. Stevenson. Bricks used to built troops' winter quarters.

ARMORY DWELLING HOUSE NO. 127 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block D Lot No. 8, Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					William Turk	15.00	15.00	
Dec. 31, 1844	Brick					John Chapman	17.25	17.25	
Dec. 31, 1846	Brick					John Chapman	17.25	34.50	
June 30, 1849	Brick	2		5	1,000	John Chapman	17.50		
Dec.31,1 1850	Brick	2		6	800	W. D. Copeland	17.50	17.50	John Chapman owed 35.00.
June 30, 1851	Brick	2				W. D. Copeland			
June 30, 1852					650.00	Wm. D. Copeland			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	8/31/52	$ 650.00	William D. Copeland	October 13, 1859.

Photo HF-60(1865).

Remarks: a two- story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2- story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace.

ARMORY DWELLING HOUSE NO. 128 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 5, Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Erasmus Bell	15.00	15.00	
Dec. 31, 1844	Brick					James P. Engle	17.25	17.25	
Dec. 31, 1846	Brick					James P. Engle	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	James P. Engle	17.50		
Dec. 31, 1850	Brick	2		6	800	J. P. Engle	17.50	17.50	
June 30, 1851	Brick	2				J. P. Engle			
June 30, 1852					675.00	J. P. Engle			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/ 52	$ 675.00	John McClellan, Jr.	September 5, 1856.

Photos HF-60(1865) and HF-63(1865).

Remarks: a two-story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2- story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace.

ARMORY DWELLING HOUSE NO. 129 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block FF Lot No. 4, Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John Ervin(Arvin)	15.00	15.00	
Dec. 31, 1844	Brick					John Arvin	17.25	17.25	
Dec. 31, 1846	Brick					John Arvin	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	John Arvin	17.50		
Dec.31,1 1850	Brick	2		6	800	Thomas Llewellyn, Jr.	17.50	17.50	
June 30, 1851	Brick	2				Thomas Llewellyn, Jr.			
June 30, 1852						John E. P. Daingerfield,Clerk	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	None	House and lot reserved from 1852 sale for U.S. use.

Remarks: a two-story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2-story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace. House withheld from 1852 sale and renumbered as Armory Dwelling No. 28 about 1859. House torn down by Union soldiers in 1864, under orders from Brig. Gen. J.D. Stevenson. Bricks used to built troops' winter quarters.

ARMORY DWELLING HOUSE NO. 130 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block FF Lot No. 2 and 3, Camp Hill - Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Joseph Ott	15.00	15.00	
Dec. 31, 1844	Brick					Joseph Ott	17.25	17.25	
Dec. 31, 1846	Brick					Joseph Ott	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	Joseph Ott , Inspector	Free		
Dec.31,1 1850	Brick	2		6	800	John Shewbridge	17.50	17.50	
June 30, 1851	Brick	2				John Shewbridge			
June 30, 1852						John Shewbridge			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	not sold	none	none	House and lot reserved from 1852 sale for U.S. use.	

Remarks: a two- story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2- story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace. House withheld from 1852 sale and renumbered as Armory Dwelling No. 29 about 1859. House torn down by Union soldiers in 1864, under orders from Brig. Gen. J. D. Stevenson. Bricks used to build troops's winter quarters.

ARMORY DWELLING HOUSE NO. 131 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 7, Camp Hill Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Charles C. Cameron	15.00	15.00	Cameron had been paid $ 125.00 in 1830 for building a wooden house.
Dec. 31, 1844	Brick					Charles C. Cameron	17.25	17.25	
Dec. 31, 1846	Brick					Charles C. Cameron	17.25	17.25	
June 30, 1849	Brick	2		5	1,000	J, W. Miller	17.50		
Dec. 31, 1850	Brick	2		1	800	J. W. Miller	17.50	17.50	
June 30, 1851	Brick	2				Joseph W. Miller			
June 30, 1852					675.00	Joseph W. Miller			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
1852 Sale	8/31/52	$ 675.00	Joseph W. Miller	December 12, 1856	

Photo HF- 63(1865)- probable view of front elevation.

Remarks: a two- story brick house with slate roof, erected 1833-34. This is one of eight houses erected under contract in 1833-34 by carpentersJames Foley and Daniel T. Mathias, mason Joseph Hillard, slater William Bayley, plasterer Leo W. Brown, and painter John P. Kennedy at a cost, including a 9th house, of $ 8,897.70. Each of 8 houses was a 2- story brick structure with a slate covered gable roof. The main house was 28 by 22 feet size. Each story had three rooms and each floor had one fireplace In the rear there was a one-story brick kitchen wing, 12 by 18 feet, with a cellar below. The kitchen contained one fireplace.

ARMORY DWELLING HOUSE NO. 132 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block C Lot No. 2, Camp Hill - Town Square, Washington Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For location see Park Map
No. 80- 1850- house not numbered but shown.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Charles Holt	5.00	5.10	Delinquent since 4th qr. of 1840.
Dec. 31, 1844	Wood					Charles Holt	7.45	7.45	
Dec. 31, 1846	Wood					Charles Holt	7.45	7.45	
June 30, 1849	Wood	2		10	400	Charles Holt	7.50		
Dec. 31, 1850	Wood	2		11	300	George W. Woods	9.00	9.00	
June 30, 1851	Wood	2				G. W. Woods			
June 30, 1852					425.00	G. W. Woods			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 425.00	Michael E. Price	July 26, 1866

Remarks: House No. 132 a two-story frame house erected 1811-33.

For Location see Park Map No. 73 - 1848. Has number on the house.

Photo: HF-63(1865). Probable view of house.

ARMORY DWELLING HOUSE NO. 133 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block C Lot No. , on Public Square, Washington Street, Camp Hill
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 73 - 1848.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Riley *	4.00	4.00	
Dec. 31, 1844	Wood					, John Riley	4.60	53.20	
Dec. 31, 1846	Wood					John Riley	4.60	4.60	
June 30, 1849	Wood	1		16	50	Mrs. John Riley			
Dec. 31, 1850	Wood	1		16	50	Mrs. Riley	5.00	55.00	John Riley estate owed 15.00
June 30, 1851	Wood	1				Mrs. Riley			
June 30, 1852						Mrs. Riley House demolished and materials sold in 1852.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House site made part of town public square on Camp Hill

Remarks: House No. 133 was a one-story frame house built 1811-33 and demolished in 1852.

* John Riley had been paid $ 27.53 on December 31, 1823 for making repairs to a wooden house. R.G. 217, 1st Series, File 7624, Voucher 154A.

ARMORY DWELLING HOUSE NO. 134 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 7, Camp Hill - Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry at Columbia Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Joab Holt *	7.50	7.50	
Dec. 31, 1844	Wood					Joab Holt	8.60	8.60	
Dec. 31, 1846	Wood					Isaac Busey	8.60	8.60	
June 30, 1849	Wood	1		11	300	Joab Holt (?)	8.75		
Dec. 31, 1850	Wood	1		13	200	Joab Holt	8.75	8.75	
June 30, 1851	Wood	1				Jacob Crowl	Free	Free	
June 30, 1852					350.00	Jacob Crowl			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 350.00	Singleton Chambers, Jr	December 12, 1856.

Remarks: House No. 134 a one-story frame house erected 1811-33.

*On October 1831, John Holt had a claim of $ 62.00 for a mantlepiece, partitions, doors, kitchen cellar, smoke house, stable, privy, and fence he had built on his lot. He was paid $ 62.00 in settlement of this claim on June 13, 1837. R.G. 217, 2nd Series, File 1423. John Holt was also paid $ 58.53 on December 31,1823 for repairs he had made to a wooden house.(R.G. 217, 1st Series, File 7624, Voucher 149A.

ARMORY DWELLING HOUSE NO.135 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No.6, Camp Hill, Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80 - 1850. at Columbia Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Thomas Earnshaw	15.00	15.00	
Dec. 31, 1844	Wood(Sic)					Benjamin Wentzle	17.25	18.83	
Dec. 31, 1846	Brick					Benjamin Wentzle	17.25	17.25	
June 30, 1849	Brick			5	1,000	Benjamin Wentzle	17.50		
Dec.31,1 1850	Brick	2		5	900	Benjamin Wentzle	17.50	17.50	
June 30, 1851	Brick	2				Benjamin Wentzle			
June 30, 1852					950.00	Benjamin Wentzle			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 950.00	Benjamin Wentzle	September 5, 1856.

Remarks: House No. 135 was a one and one-half story brick dwelling probably built in 1837-38.

For location,with number on house, see Park Map No. 73 - 1848.

In 1837-38 dwellings, the main house was brick, 1½ stories high, 28 by 22 feet, with a stone foundation 20 inches thick; the front and back brick walls were 14 in. thick and the gable end walls 9 inches thick. The rear kitchen wing, brick, was one story high, with a cellar underneath. The cellar foundations were 20 inches thick and the brick walls of the wing 9 inches thick. The wing was 12 by 16 feet in size.

ARMORY DWELLING HOUSE NO. 136 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block B Lot No. 8, Camp Hill - Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Sleppy	7.00	7.00	
Dec. 31, 1844	Wood					John Sleppy	8.05	8.05	
Dec. 31, 1846	Wood					John Sleppy	8.05	8.05	
June 30, 1849	Wood	1		10	400	John Sleppy	8.75		
Dec. 31, 1850	(Brick written above wood-sic) Wood	1		14	150	William F. Lennox	8.75	8.75	
June 30, 1851	Brick(sic)	1				William T. Lennox			
June 30, 1852					300.00	W. T. Lennox			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 300.00	Mrs. Elizabeth Lennox mother of William T. Lennox	December 12, 1856.

Remarks: House No. 136 was a one-story, apparently brick(or frame) house erected ca. 1811-33.

ARMORY DWELLING HOUSE NO. 137 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 9, Camp Hill - Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Emanuel Spangler	7.50	7.50	
Dec. 31, 1844	Wood					Emanuel Spangler	8.60	8.60	
Dec. 31, 1846	Wood					Emanuel Spangler	8.60	8.60	
June 30, 1849	Wood	1		11	300	Emanuel Spangler	8.75		
Dec.31,1 1850	Wood	1		13	200	William C. Kirby	8.75	8.75	
June 30, 1851	Wood	1				W. C. Kirby			
June 30, 1852					275.00	W. C. Kirby			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 275.00	William C. Kirby	October 31, 1856

Remarks: House No. 137 was a one-story frame dwelling erected 1811-33.

ARMORY DWELLING HOUSE NO. 138 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 4, Camp Hill- Washington Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					James Wilsom	7.50	7.50	
Dec. 31, 1844	Wood					Bazil Avis	8.60	8.60	
Dec. 31, 1846	Wood					Bazil Avis	8.60	8.60	
June 30, 1849	Wood	1		11	300	Bazil Avis	11.50		
Dec. 31, 1850	Wood	1		11	300	Bazil Avis	9.50	9.50	
June 30, 1851	Wood	1				Bazil Avis			
June 30, 1852					400.00	Bazil Avis			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 400.00	Isaac Fleming	July 7, 1855

Remarks: House No. 138 was a one story frame house erected ca. 1811-33.

For location, with number on the house, see Park Map No. 73 - 1848.

ARMORY DWELLING HOUSE NO. 139 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No.10, Camp Hill - Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Henry Best	5.00	5.00	
Dec. 31, 1844	Wood					John Holt	5.75	5.75	Henry Best owed 17.23
Dec. 31, 1846	Wood					Martin Leece	5.75	5.75	Henry Best owed 17.23.
June 30, 1849	Wood	1		14	150	Martin Lesse	5.75		
Dec.31,1 1850	Wood	1		15	100	Martin Leece (Leese)	5.75	5.75	Henry Best owed 17.23.Mrs.Claspy Est. owed 10.83.
June 30, 1851	Wood	1				Martin Leece			
June 30, 1852					275.00	Martin Leece.			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 275.00	Martin Leese	October 31,1856

Remarks: House No. 139 was a one-story frame dwelling erected 1811-33.

ARMORY DWELLING HOUSE NO. 140 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 12, Camp Hill - Fillmore Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry at Lancaster Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					Richard Johnson *	9.00	9.00	
Dec. 31, 1844	Brick					Jeremiah Fuss (carpenter)	10.35	10.35	Richard Johnson owed 7.50.
Dec. 31, 1846	Brick					Jeremiah Fuss	10.35	11.06	
June 30, 1849	Brick	1		7	600	Jeremiah Fuss	12.50		
Dec. 31, 1850	Brick	1		8	500	Jeremiah Fuss	Free	Free	
June 30, 1851	Brick	1				Jeremiah Fuss			Fuss elected 1st mayor of Harpers Ferry, May 1851.
June 30, 1852					400.00	Jeremiah Fuss			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/ 52	$ 400.00	Jeremiah Fuss	October 13, 1859

Remarks: House No. 140 was a one-story brick dwelling erected ca. 1830-34.

This house was one of the two one-story brick house standing on Camp Hill prior to 1852. For its possible construtions in 1833 as a replacement for the dwelling on Arsenal Square, Lot 1, Block A, Shenandoah Street(House 190) that was remodelled into the Superintendent's Office in 1832, see remarks on House No. 104, the other one-story brick dwelling on Camp Hill. Richard Johnson was paid $ 17.80 on April 16,1845 for furnishing material and putting up 45 panels of fence,furnishing material and erecting kitchen 15 by 12 feet and building 5 perhhes of stone wall, total value. $ 61.25. $ 30.62 deducted for decay and $ 12.83 deducted as cost of gaining possession of lot.R.G.217-3rd Series, File 2474, Voucher 7.

ARMORY DWELLING HOUSE NO. 141 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Storer College Lot with Armory Dwelling No. 30 on it.

Location: Block Lot No. , Camp Hill- Fillmore Street

S. Howell Brown's 1852 Map of Harpers Ferry Probable location on south side of Fillmore, SW corner at Lancaster Street

S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					F. W. Stephenson *	8.00	8.00	
Dec. 31, 1844	Wood					F. W. Stephenson	9.20	9.20	
Dec. 31, 1846	Wood					Robert D Porter	9.20	9.20	
June 30, 1849	Wood	1		7	600	Robert D. Porter	11.25		
Dec. 31, 1850	Wood	1		8	500	Alex Grillett	11.25	11.25	
June 30, 1851	Wood	1				Alex Grillett			
June 30, 1852						Reserved from 1852 sale			House demolished in 1854.

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House 141, a one-story frame dwelling erected 1811-33 and demolished in 1854.

* Frederick W. Stephenson was paid $ 53.00 in 1836 for making repairs to his house.

ARMORY DWELLING HOUSE NO. 142 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block A Lot No. 6, Camp Hill "Back of Washington Street"-
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Fillmore Street (probable location)

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					John Butler*	4.00	4.00	
Dec. 31, 1844	Wood					John Butler	4.60	4.60	
Dec. 31, 1846	Wood					Vacant			John Butler owed 9.20.
June 30, 1849						House broken up in 1847.			
Dec. 31, 1850	Wood	1		16	50	"Broken up in 1847"			John Butler owed 9.20.
June 30, 1851	Wood	1				broken up in 1847.			
June 30, 1852						vacant lot			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: House No. 142, a one-story frame dwelling built 1811-33 and demolished in 1847.

* John Butler had a claim in 1829 for a wooden dwelling he had built in 1820 in the amount of $ 150.00.

ARMORY DWELLING HOUSE NO. 143 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Storer College Lot, opposite to Block A, Lots 5 and 6, Camp Hill
Block Lot No. ,

S. Howell Brown's 1852 Map of Harpers Ferry Probable location on south side of Fillmore, SE corner at Lancaster Street.
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Solomon Fleming *	7.50	7.50	
Dec. 31, 1844	Wood					Solomon Fleming	11.50	11.50	
Dec. 31, 1846	Wood					Solomon Fleming 2 month-11.50 1 " 13.50		12.16	
June 30, 1849	Wood	2		6	800	Solomon Fleming	13.50		
Dec. 31, 1850	Wood	2		8	500	Isaiah E. Miller	13.50	11.50	
June 30, 1851	Wood	2				I. E. Miller			
June 30, 1852						Reserved from 1852 sale			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: House No. 143, a two-story frame dwelling built 1811-33. House and lot reserved from 1852 sale for U.S. use. House demolished in period 1855-59.

*Thomas Duke, in October 1831, had a claim of $ 71.00 for plastering a house, finishing rooms, steps, window frames, painting house, digging cellar, building stable and kitchen. This claim was transferred to Solomon Fleming who received $ 20.00 in settlement of this $ 71.00 claim on April 28,1837. R.G. 217, 2nd Series, File 1423.

ARMORY DWELLING HOUSE NO. 144 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block A Lot No. 2, Camp Hill- Clay Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Methodist Parsonage	Free	Free	
Dec. 31, 1844	Wood					Methodist Parsonage	3.00	5.00	
Dec. 31, 1846	Wood					Methodist Parsonage	3.00	3.00	
June 30, 1849	Wood	2		8	500	Methodist Parsonage	3.00		
Dec.31,1 1850	Wood	1		12	250	Methodist Parsonage	Free	Free	
June 30, 1851	Wood	1			250.00	John Russell			
June 30, 1852					250.00	John Russell			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 250.00	John Russell	March 22, 1854 .

Remarks: Houe No. 144 was a one-story frame house erected 1811-33.

The Methodist Episcopal Church erected a church edifice on leased Armory land in 1827-28. The one and one-half story building over elevated basement was constructed of stone, measured 40 by 60 feet and was built by Lewis Wernwag. On January 19,1838, the Secretary of War granted permission to the Harper's Ferry Methodist Episcopal Church to use Armory Dwelling House No. 144 as a parsonage. In 1851 the Secretary of War granted the Methodist Episcopal Church a lease to vacant Lots No. 3 and 4, Block H, Camp Hill , as a site on which to built their parsonage.

ARMORY DWELLING HOUSE NO. 145 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block A Lot No. 4, Camp Hill - Clay Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry For location see Park Map No. 73 - 1848.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone & Wood					James Merrick *	13.75	13.75	
Dec. 31, 1844	Stone					John A. Cocke	15.80	31.60	
Dec. 31, 1846	Stone					John H. Cocke	10.00	10.00	
June 30, 1849	Stone	2		7	600	J. H. Cocke	11.00		
Dec. 31, 1850	Stone	2		9	450	John McClellan, Jr.	11.00	11.00	John H. Cocke owed 7.33.
June 30, 1851	Stone	2				John McClellan, Jr.			
June 30, 1852					500.00	John McClellan, Jr.			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 500.00	Marine F. Krepps (or Kreps).	February 2, 1857

Remarks: House No. 145 was a two-story stone house erected ca. 1822-33.

James Merrick had a claim in 1829 of $ 75.00 for building a wooden house. He was paid $ 33.00 in 1831 for making repairs to his dwelling.

ARMORY DWELLING HOUSE NO. 146 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 1, Camp Hill - Clay Street & Lancaster Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
For location see Park Map No. 80 - 1850.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Philip McBride	7.50	7.50	
Dec. 31, 1844	Wood					Asa Marstellar	17.25	25.90	undercharge in 3rd qr of 8.65.
Dec. 31, 1846	Wood					Asa Marsteller	17.25	17.25	
June 30, 1849	Wood	2		6	800	Asa Marsteller	17.50		
Dec. 31, 1850	Wood	2		7	600	Isaac Fleming	17.50	17.50	
June 30, 1851	Wood	2				Isaac Fleming			
June 30, 1852					700.00	Isaac Fleming			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	8/31/52	$ 700.00	Bazil Avis	October 31, 1856

Remarks: House No. 146 was a two-story frame dwelling erected ca. 1811-33.

For location of house, with house numbered, see Park Map No. 73 - 1848.

ARMORY DWELLING HOUSE NO. 147 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , "Up the Bank of the Potomac River."
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Daniel Johnson *	7.50	7.50	Johnson was paid $ 158.37 on 12/31/ 1823 for building
Dec. 31, 1844	Wood					Daniel Johnson	9.20	15.98	in part a brick hou In Oct.1831 he had a $25.00 claim for
Dec. 31, 1846	Wood					Daniel Johnson	9.20	9.20	a kitchen and room, flooring out bldg, smoke house, roof
June 30, 1849	Wood	2		8	500	John Price(?)	17.25		to spring house, stable & fence. Johnson paid $ 17.7
Dec.31,1 1850	Wood	1		11	300	Patrick Macquire	9.25	9.25	on Nov.7,1845 . R.G.217-3rd Series File 1934-V. 29.
June 30, 1851	Wood	1				Patrick Macquire			
June 30, 1852						Patrick Macquire			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 147 was a one-story frame house erected 1811-33; reserved from the 1852 sale for Armory use, and demolished in the period 1855-1859.

This house, or House No. 148, was probably built by John Lowstetter, the contractor who worked on the U.S. Potomac dam in 1820-21. On June 12,1822, he was paid $ 395.00 "for a horse he built for the accommodation of himself and his hands while engaged in building the dam across the Potomac last year."(National Archives Record Group 217, Records of the 2nd Auditor of the Treasury, First series, File No.6274- Voucher No. C59.)

ARMORY DWELLING HOUSE NO. 148 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , "Up the bank of the Potomac" River
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John McCartney	15.00	75.00	Delinquet from 4th qr 1840- 60.00.
Dec. 31, 1844	Stone					Horatio Jarboe	8.60	8.60	
Dec. 31, 1846	Stone					Henry Buckler	8.60	8.60	
June 30, 1849	Stone	1		8	500	Henry Buckler	8.75		
Dec.31,1 1850	Stone	2		11	300	Richard Russell	8.75	8.75	
June 30, 1851	Stone					Richard Russell			
June 30, 1852						Richard Russell			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	House and lot reserved from U.S. sale for armory use.

Remarks: House No.148 was a two-story stone house erected 1821-33. The house and lot were reserved from the 1852 sale for armory use and was demolished in the period 1855-59. House probably built in period 1820-33. See house No. 147 for possible construction of House 147 or 1148 by dam builder John Lowstetter in 1821. House No. 148 was located on the south bank of the Armory Canal or raceway, at the base of the cliff, due north of Armory Dwelling House No. 104 on Lot 2, Block F, Camp Hill and Houses 105-106 on Lots 3 and 4, Block F, Camp Hill. See Harpers Ferry NHP Map No.80 - Map Case, Drawer 4, 1850 map prepared by Major John Symington, "Locality of the Site for the Harper's Ferry Female Institute, Camp Hill," which shows the exact location of House No. 148.

ARMORY DWELLING HOUSE NO. 149 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block KK Lot No.4, Camp Hill,"In a line between the Commanding
S. Howell Brown's 1852 Map of Harpers Ferry Officer's House and the Magazine.
S. Howell Brown's 1869 Map of Harpers Ferry South side of Washington Street

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Jonathan Anderson *	7.50	7.50	
Dec. 31, 1844	Wood					William Turk	8.60	8.60	Jonathan Anderson owed 22.50
Dec. 31, 1846	Wood					Benjamin Ott	8.60	8.60	
June 30, 1849	Wood	1		11	300	Benjamin Ott	8.75		
Dec.31,1 1850	Wood	1		11	300	Peter Jones	8.75	8.75	
June 30, 1851	Wood	1				Peter Jones			
June 30, 1852						Peter Jones			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 149 was a one-story frame dwelling erected 1811-33. House reserved from U.S. sale in 1852 for armory use. House demolished between 1855 and 1859.

This is the probable location of the house Block KK, Lots 4 or 3. House No. 151 is an alternative dwelling that could have been located on Block KK, Lots 2 and 3.

* John. Anderson had an October 1831 claim of $ 130.00 for a house and kitchen he built, also a smoke house, privy, bake oven, fence, digging cellar, and wall.

ARMORY DWELLING HOUSE NO. 150 (1841-1858) HARPER"S FERRY, ARMORY, VA.
Lutheran Church LOt

Location: Block J Lot No. , Camp Hill." In a line between the Commanding
~~Officer's (1848) House and~~ the Magazine.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Probable site on Washington Street

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					William Marlatt	5.00	5.00	
Dec. 31, 1844	Wood					Vacant			
Dec. 31, 1846						House broken up in 1845.			
June 30, 1849						"Broken up in 1845."			
Dec. 31, 1850	Wood	1		-	-	"Broken up in 1845."			
June 30, 1851	Wood	1				"Broken up in 1845."			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	

Remarks: House No. 150 was a one-story frame dwelling erected 1811-33 and demolished in 1845.
House No. 150 may have been located on Block F, on the Lutheran Church Lot(Lot F on the 1848 map). The dwelling was demolished in 1845 and the lease to Lot F, which fronted 66 feet on the north side of High Street and ran back 165 feet, containing one-quarter acre, was granted to the church on February 21, 1850.

ARMORY DWELLING HOUSE NO. 151 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block W Lot No. Camp Hill, in a line between the Commanding Officer's
S. Howell Brown's 1852 Map of Harpers Ferry (1848) Quarters and the magazine
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Corbin Baker	1.50	3.00	Delinquent from 4th qr. 1840.
Dec. 31, 1844	Wood					Henry Sagle	1.75	1.75	Corbin Baker owed 9.00.
Dec. 31, 1846	Wood					Michael Carbaugh	1.75	1.75	Corbin Baker owed 5.68
June 30, 1849	Wood	1		15	100	Mrs. Carbaugh	3.00		
Dec. 31, 1850	Wood	1		16	50	Mrs. Carbaugh	3.00	3.00	
June 30, 1851	Wood					Mrs. Carbaugh			
June 30, 1852						Mrs. Carbaugh			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	none	none	House and lot reserved from U.S sale	for armory use.

Remarks: House No. 151 was a one-story frame house built ca. 1811-33 and reserved from the 1852 sale for armory use. The dwelling was demolished between 1855 and 1859.

House may have been located on Block W ,Camp Hill, but if so, the dwelling should have been demolished in 1852, because Block W was vacant when offered for sale in September 1852. Another possible location for House No. 151 is Block KK, Lots 2 and 3, Camp Hill, on the south side of Washington Street (See House 149). Block KK was reserved from sale in 1852.

ARMORY DWELLING HOUSE NO. 152 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block O or L Lot No. , Camp Hill, located in a line between the Commanding Officer's(1848) quarters and the magazine.

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Jacob Engles (sic) *	1.50	1.50	
Dec. 31, 1844	Wood					Jacob Engels	1.75	1.75	
Dec. 31, 1846	Wood					Jacob Engels	1.75	1.75	
June 30, 1849	Wood	1		12	250	Jacob Engles	3.00		
Dec.31,1 1850	Wood	1		12	250	Mrs. Mahoney,	3.00	3.00	Calvin Engle owed 7.00;Austin Mahone owed 3.00
June 30, 1851	Wood	1				Mrs. Mahoney			
June 30, 1852						" Broken up 1852".			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: House No. 152 was a one-story frame house built 1811-33 and demolished in 1852.

Probable location of the House was on Block O or L prior to 1852. Another possible location was Block W prior to 1852. * Jacob Engles had an October 1831 claim of $ 40.00 for building a kitchen, stable, fence, privy, chimney, and weatherboarding.

SECTION F

ARMORY DWELLING HOUSES NOS. 153 - 155:

Located on South Bank of the Shenandoah River and the U.S. Shenandoah Ferry, 1818-1844:

ARMORY DWELLING HOUSE NO. 153 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On South Bank of Shenandoah River, opposite the Ferry Lot, Shenandoah Street, Harper's Ferry.

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
House No. 153 located east of House No. 154.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John Starrett	9.00	9.00	
Dec. 31, 1844	Stone					Michael Derry 3 months for Ferry 2 1/3 month	15.00 81.25	230.64	Derry delinquent 152.45
Dec. 31, 1846	Stone					William Medlar 3 months Wm. Kemp & Sol. Traille 3 m.	3.00 15.00	3.00 15.00	Derry delinquent 155.04.
June 30, 1849	Stone	2		5	1,000	Solomon Trail William Medlar(?)	7.50 7.50		two-family house
Dec.31,1 1850	Stone	2			600	Casper Shumaker John Fair	7.50 7.50	7.50 7.50	Derry owed 155.04
June 30, 1851	Stone	2				Robert Nicholson Casper Overwater			
June 30, 1852						Hillsborough and Harpers Ferry Turnpike Company. Toll House	25.00 per year		Toll House

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S use.

Remarks: House No. 153 was a two-story stone dwelling erected by George Harding in 1826 for use as a ferry house. The estimated value of the structure in 1829 was $ 650.00. This located on the 68 acre ferry tract on the south side of the river. The U.S. appears to have purchased title to this house on November 9, 1837 when it paid Edward Harding, the administrator of the estate of the mason John Lackey $ 650.00 "for building a stone house 18 by 40 feet and a wall in front."(NA Record Group 217, records of 2nd Auditor, Second series, File 2094, Voucher 156B. The house was reserved from the 1852 sale and used as a armory dwelling, in 1859 the edifice was renumbered as Armory Dwelling No, 9 and was described in July 1865 as "a two-story stone house, in fair condition." House No. 153 was leased by the Hillsborough and Harpers Ferry Turnpike Company from 1851 to 1861 at an annual rent of $ 25.00. The house can be seen in HF NHP Photos. HF-44(1876) and HF - (1885).

ARMORY DWELLING HOUSE NO. 154 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the south bank of the Shenandoah River, on the 68 acre Ferry Lot tract.

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
House No. 154 located west of House No. 153.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					Reuben Stipes	6.25	6.25	On November 24, 1823, Stipes had been paid $ 24.36
Dec. 31, 1844	Stone					Reuben Stipes	7.15	7.99	for making repairs to a wooden house.
Dec. 31, 1846	Stone					Reuben Stipes	7.15	7.15	
June 30, 1849	Stone	2		9	450	Reuben Stipes	7.50		
Dec. 31, 1850	Stone	1		11	300	Reuben Stipes	7.15	7.15	
June 30, 1851	Stone	1				Reuben Stipes			
June 30, 1852						Reuben Stipes			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	None	None	House and lot feserved from 1852 sale for U.S. use.

Remarks: House No. 154, a one-story stone dwelling built by Job C. Harding in 1811 as his ferry house and dwelling. Ferry rights, 68 ferry lot tract on south side of river, including building purchased from Ferdinando Fairfax for $ 5,000.00 on October 27, 1818. Job Harding and his wife operated the ferry from 1811 to their death in 1826. From March 1827 to March 1830, the ferry was leased to Edward Harding, from 1830-31 by Philip Coons, and 1831- 1832 by William Graham. House No. 154 was reserved from the 1852 sale and retained for armory use. The house was renumbered as Armory Dwelling No. 10 in 1859. In July 1865 it was described as "One story, stone, in good condition, occupied free of rent by Mrs. Stipes by order of Col. Henry K. Craig."

ARMORY DWELLING HOUSE NO. 155 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block Lot No. , South Bank of the Shenandoah River, about opposite to U.S. Ferry Lot. (Probable location)

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry
Probably located west of House No. 154.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					David Potts	7.50	7.50	
Dec. 31, 1844	Stone					David Potts	8.60	8.60	
Dec. 31, 1846						Vacant			
June 30, 1849						"Broken up in 1847"			
Dec. 31, 1850	Wood	1		13	200	Broken up in 1847			
June 30, 1851	Wood	1				This house may have been located on the south bank of the Shenandoah River, near House No. 154, the location as given in 1850 is not very clear.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: A one-story wood(or stone) house built ca. 1811-33. Demolished in 1847.

SHENANDOAH FERRY , 1818- 1844

HARPER"S FERRY, ARMORY, VA.

NPS Land

Location: Block Lot No. ; Shenandoah Street FERRY LOT
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Ferry					David Coons	90.00	507.00	William Graham estate owed $ 231.00 for F
Dec. 31, 1844	Ferry					Michael Derry 2 1/3 months-- also owed (also House 153)	81.25 152.45	230.64	Wm.Graham-231.(Thomas Griggs- owed 316.23
Dec. 31, 1846						Shenandoah toll bridge open- ferry no longer operating.			Michael Derry- 155.04; W.Graha 231.00;
June 30, 1849	The U.S. purchased the ferry rights over the Shenandoah River from Ferdinando Fairfax on October 27, 1818 for $ 5,000.00. This included 68 acres in the ferry tract on the south bank of the river. Job Harding and his wife, who had been operating the Shenandoah Ferry under a lease with Fairfax since 1811, continued to run the ferry for the U.S. Armory from 1818 until 1826 . From March 1827 to March 1830, the ferry was next leased to Edward Hardy. Under the lease arrangements from 1818 to 1830, the ferry operators paid no rent to the United States, but did furnish their own boats and crossed all U.S. teams and wagons and armory employess free of charge. In March 1830, the U.S. advertised the lease to the ferry. Philip Coons accepted the lease, agreeing to pay an annual rent of $ 251.00. He operated the ferry from March 1830 to March 1831. Rates of ferriage, under law, were 45 cents for a wagon and four horses; 10 cents for a horse and man; and five cents for a footman. Rates actually charged prior to 1831, were 12½ cents for wagon and four horses, 5 cents for a horse and man, and 3 cents for a footman. In 1831-32 the actual ferriage rates were increased by 100 percent.								
Dec.31, 1850									
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Right reserved to U.S.

Remarks: In 1831-32 the ferry was leased by William Graham who agreed to pay $ 362.00 a year in rent. In 1836 it was reported that the ferry was rented for $ 360 annually. On May 14,1842, Supt, Henry K. Craig reported that"The Ferry has been rented for $ 450 per an. and is now leased for $ 365, the Ferryman furnishing his own boats,ropes, &c., and crossing free of toll all Armory Officers, and Armorers living on the south side of the River, and all waggons with fuel or other property for the Armory.. all our firewood and charcoal come over, so that the advantages (to the U.S. amounted to about..) $ 1,000 per an." The ferry ceased operations in late 1844, when the Shenandoah River toll bridge was completed and opened for traiff.

SECTION G

ARMORY DWELLING HOUSES NOS. 156 to 169,

Located on the Upper Hall Island, Shenandoah River.

House No.164, Captain John H. Hall's Residence, 1819-1840, located on Camp Hill.

House No.167 located on the Lower Hall Island, at the U.S. Rifle Factory.

Brief History of Construction of Dwellings on the Upper and Lower Hall Island, 1819-1837:

In the summer of 1819 three dwelling houses were erected at an approximate total cost of $ 1,350 for the accommodation of three of Captain John H. Hall's employees at his new U.S. Rifle Factory plant, which was also being built in 1819. These dwellings were probably located on the Upper Hall Island.

A fourth dwelling, a log house, was built for one of Hall's employees in April 1825 at a cost of $ 102.75.

In 1827-28 House No. 164, a two-story brick residence was erected on Camp Hill as Captain Hall's fine new house. Also built in 1827-28 were two more dwellings for Hall's employees, so that by 1828 Hall and his men occupied a total of seven armory dwelling houses. In 1831 Hall spent $ 433.71½ building kitchens to two of his men's dwellings and $ 76.45 making repairs to three other employees' houses.

In 1837, working under contract with the armory, mason Joseph Hilliard(or Hillard) and carpenter James Foley, constructed a one and one-half story brick dwelling house on the Upper Hall Island at an approximate cost of $ 900.00.

The main house was 28 by 22 feet, 1½ stories high, foundation of Stone, 20 inches thick; front and back Brick wall 14 inches thick; end wall 9 inches.

Kitchen or Wing - 1 story high, cellar underneath. Stone foundations 20 inches; Brick wall 9 inches. Dimensions 12 by 16 feet.

The 1837 brick house is probably Armory Dwelling House No. 158.

Armorer Francis Attlespeiger constructed a stone house, 17 by 20 feet, kitchen, stable, bake oven, and wood house on the Hall Island which was appraised at $ 315.00 October 1831. He assigned his claim to Jeremiah Seaman for $ 294.00 on April 20,1835. U.S. paid Seaman $ 223.65 on December 12,1837 after deducting $ 91.35 for depreciation.

MAP NO. 17

MAP of HARPER'S FERRY Shewing the Location of the Winchester and Potomac Rail-road, No. 1- 1835 Drawn by Lieuts. White, Allen, and R.S. Smith, U.S. Army Under the Direction of James Kearney, Lt. Col. and T.E. Scale of 100 feet to one inch. Approved by President Andrew Jackson, 27th January 1835."

From National Archives Record Group No. 77, Records of the Chief Engineer, Fortifications File, Drawer 150, Sheet 82 - 1, Washington, D.C.

Harpers Ferry NHP Map Case, Map No. 31, Drawer No.12.

Section from the map showing the Armory-owned dwelling houses located on the Upper Hall Island in 1834.

Armory dwelling have been marked by Charles W. Snell with their probable 1841-1859 rent roll identification numbers. These houses were definitely located on the Upper Hall Island but the arrangement of the numbers is hypothetical.

Remarks: House No. 158 is not shown on this map as it was not constructed until 1837-38.

House No. 164, the residence of Captain John H. Hall, was located on top of Camp Hill near Harpers Grave Yard.

House No. 167 was located on the Lower Hall Island(to the east or right) at the Hall or U.S. Rifle Factory.

MAP NO 18

MAP C.

"A Plot Exhibiting the Limits pf the grounds requisite for the Passage of the Winchester & Potomac Rail Road through the Islands, adjacent to Harper's Ferry. Scale 100 feet to the inch."

No date, but completed by the engineers of the railroad company by August 12, 1834.

National Archives Record Group No. 77, Records of the Chief of Engineers, Fortifications File, Drawer 150, Sheet 78- part 4. Cartographic Division, National Archives, Washington, D.C.

Harpers Ferry NHP Maps No. 25 and 26m Map Case, Drawer No. 12

A section of the map showing the Armory-owned dwelling houses located on the Upper Hall Island.


Armory dwelling houses have been marked by Charles W. Snell with their probable 1841-1859 identification rent roll numbers. These houses were definitely located on the Upper Hall Island but the arrangement of the numbers is hypothetical.

Remarks: House No. 158 is not shown on this map as it was not erected until 1837-38.

House No. 164, the residence of Captain John H. Hall, was located on top of Camp Hill, near Harpers Grave Yard.

House. No. 167 was located on the Lower Hall Island, at the Hall or U.S. Rifle Factory.

201 A


works
Canal
Thorp's Island
Overton
161
160
159
162
163
165
157
166
156
169
168
Hall's
Isd's.
UPPER HALL ISLAND
(U.S.)
CAPTAIN JOHN H. HALL"S
RESIDENCE, HOUSE No. 164,
was located on Camp Hill.

MAP NO. 19

MAP OF HARPER'S FERRY(1848-51)
Prepared in Compliance with Letter to Major(John) Symington, April 22, 1848,' Drawn by S. Howell Brown in 1848. The section of the map relating to Virginius Island was revised and updated by Superintendent Symington(in red inck) in January 1851. Scale 165 feet to inch.

Original linen map, only existing copy is Harpers Ferry NHP Map No. 77, in Park Map Case, Drawer No.4.

While Brown fails to include the numbered Armory Dwelling Houses on this detailed map, he does indicate the house lot system and streets as they existed in 1848.

Armory dwelling house identification numbers have been marked on Brown's house lots by Charles W.Snell. These houses were definite located on the Hall Islands but arrangement of the numbers by lot is hypothetical.


Remarks: House No. 162 is not shown on this 1848 map because it was demolished in 1845.

House No. 164, the residence of Captain John H. Hall from 1827 to 1840, was located on Camp Hill near Harpers Graveyard. (1)


House No.167 was located on the Lower Hall Island at Hall's or the U.S. Rifle Factory.

(1) House No. 164 was demolished in 1848 and the Paymaster's New House erected on its site in 1847-48.(See House No."185" for details).

202 A


156
157
159
160
164
166
169
161
163
162
168
U.S.
UPPER HALL ISLAND
THROP'S ISLAND
Throp's Id
3
5
Note by
Company's
Note - This
10 ft. too
of the centre

LEGEND FROM S. HOWELL BROWN"S 1848 MAP OF HARPER"S FERRY, identifying 23 buildings at THE U.S. RIFLE FACTORY ON THE LOWER HALL ISLAND



1 Finishing Shop New
2 Forging and tempering Shop
3 Stockers Shop
4 Filers Shop New
5 Filers Shop Old
6 Barrel Welding Shop
7 Felt Hammer Shop
8 Vitriol House
9 Rod Tilting Shop
10 Inspectors Office
11 Assembling and Finishing Shop
12 Barrel Turning and Boring Shop
13 Bell Shop Stockers and Machinery
14 Store House and Office
15 House for Steaming Stocks
16 Engine House
17 Privy
18 Drill Shop
19 Forging Shop
20 Annealing Shops
21 Annealing Furnace
22 Forging Stamps
23 Proof House

Lower Lock
Island
Lower Hall Island
SHENANDOAH STREET AND CANAL
156
157
158
159
160
161
163
169
168
Toll House
Upper Hall Island
Upper Lock

ARMORY DWELLING HOUSE NO.156 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John Avis	15.00	15.00	
Dec. 31, 1844	Brick					Philip McBride, Inspector	Free	Free	
Dec. 31, 1846	Brick					Philip McBride, Inspector	Free	Free	
June 30, 1849	Brick	2		5	1,000	William Richards	18.00		
Dec. 31, 1850	Brick	2		6	800	William Richards	18.00	18.00	
June 30, 1851	Brick	2				William Richards			
June 30, 1852						William Richards			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	None	None	House and Lot reserved from 1852 sale for U.S. use.

Remarks: House No.156 was a two-story brick house erected ca. 1822-33. House withheld from 1852 sale for armory use. In 1859 the dwelling was renumbered as Armory Dwelling House No. 6. In July 1865 it was described as "a two-story brick house," which had been torn down by Union troops in 1864 to "make room for the military railroad" that was built to supply Sheridan's army in the Shenandoah valley.

Photos: HF- 794(ca. 1853); HF- 37 (May 22, 1865).

ARMORY DWELLING HOUSE NO. 157 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					William Baden	5.00	5.00	
Dec. 31, 1844	Wood					William Baden	8.60	8.60	
Dec. 31, 1846	Wood					William Baden	8.60	8.60	
June 30, 1849	Wood	2		10	400	William Baden	8.75		
Dec. 31, 1850	Wood	2		9	450	William Baden	8.75	8.75	
June 30, 1851	Wood	2				J. G. W. Hyatt			
June 30, 1852						J. G. W. Hyatt			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 157 was a two-story frame house, perhaps one of the three dwelling houses erected in 1819 for Captain John H. Hall's workmen at the new rifle factory, at a cost of $ 1,350.00. House reserved from the U.S. sale of lots for Armory use in 1852. House No. 157 was demolished in 1854.

Photos 794(1853); HF- 37 (May 22, 1865).

ARMORY DWELLING HOUSE NO. 158 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory, Shenandoah River.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick					John H. King, Inspector	Frwe	Free	King became director of the U.S. Rifle Fac
Dec. 31, 1844	Brick					John H. King, Director, R.F.	Free	Free	On Oct.10,1840, King was paid $ 10.00 for erect-
Dec. 31, 1846	Brick					John H. King, Director, R.F.	Free	Free	ing a wooden smoke house,fenc- ing and wood hous
June 30, 1849	Brick	2		5	1,000	James H. Burton	18.75		at his dwelling on Hall's Island R.G. 217,2nd Ser.
Dec.31,1 1850	Brick	2		5	900	A. J. Amiss	18.75	14.58	File 5624,V.2.
June 30, 1851	Brick	2				John Earnest			
June 30, 1852						John Earnest			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Photo HF-794 (ca. 1853); HF-37(May 22,1865-of area only).

Remarks: House No. 158 was one of 10, 2-story brick houses erected in 1837-38. It was erected in 1837, under contract, by mason Joseph Hillard(or Hilliard) and carpenter James Foley at an approximate cost of $ 900.00. The main house was 28 by 22 feet, 2-stories high, with a stone foundation 20 inches thick; front and back brick walls 14 inches thick; end walls 9 inches. The Kitchen wing was 1 story high, with a cellar underneath. The stone foundations were 20 inches thick and the brick wall 9 inches. Dimensions of the wing were 12 by 16 feet. House reserved from 1852 sale for U.S. use and renumbered as Armory Dwelling No. 8 about 1859. House described in 1865 as "two-story, brick," had been demolished by Union soldiers in 1864 to make room for the construction of the military railroad that was then being built to support Sheridan's army in the Shenandoah Valley in1864-65.

ARMORY DWELLING HOUSE NO. 159 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					James Caton	2.50	2.50	
Dec. 31, 1844	Wood					Henry Nunnamaker	4.30	4.30	
Dec. 31, 1846	Wood					Henry Nunnamaker	4.30	4.30	
June 30, 1849	Stone	2		6	800	Jacob Crowl, Jr.	4.50		
Dec. 31, 1850	Stone	2		13	200	J. G.W. Hyatt	4.50	4.50	
June 30, 1851	Stone	2				Austin McCorn			
June 30, 1852						Austin McCorn			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: A two-story stone house built ca. 1822-1833. House demolished by armory in 1854.

ARMORY DWELLING HOUSE NO. 160 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					William Wilson *	6.25	6.25	
Dec. 31, 1844	Stone					William Orme	7.15	7.15	
Dec. 31, 1846	Stone					William Orme	7.15	7.15	
June 30, 1849	Stone	1		15	100	William F. Fitzsimmons	7.50		
Dec. 31, 1850	Stone	1		12	250	W. F. Fitzsimmons	7,50	7.50	
June 30, 1851	Stone	1				W.F. Fitzsimmons			
June 30, 1852						Wm. F. Fitzsimmons			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	None	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: One-story stone house erected ca. 1822-33. House demolished by armory in 1854.

* William Wilson was paid $ 5.00 on November 21, 1840 for furnishing the materials and building a smoke house. R.G. 217, 2nd Series, File 5624, Voucher 22.

ARMORY DWELLING HOUSE NO. 161 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block , Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John Stahl	7.50	7.50	
Dec. 31, 1844	Stone					John Stahl	8.60	8.60	
Dec. 31, 1846	Stone					John Stahl	8.60	8.60	
June 30, 1849	Stone	1		11	500	William Orme	8.75		
Dec. 31, 1850	Stone	1		13	200	William Orme	8.75	8.75	
June 30, 1851	Stone	1				William Orme			
June 30, 1852	Stone	1				William Orme			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: One-story stone house erected ca. 1822-33 House demolished by armory in 1854.

ARMORY DWELLING HOUSE NO. 162 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood					Lawson & Grear *	25.00	125.00	Delinquent from 4th qr. of 1840.
Dec. 31, 1844						Vacant			Lawson & Greer ow 119.50. William Clarke owed 24.3
Dec. 31, 1846						Vacant or demolished			Wm. Clarke owed 24.37; Lawson & Gr owed 119.50
June 30, 1849				-	-	"Broken up in 1845			
Dec. 31, 1850	Wood	1		8	500	Removed 1850			Wm. Clarke owed 24.37; Greer & Lawson owed 119.5
June 30, 1851	Wood	1				Removed 1850.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	

Remarks: 1-story frame house erected ca. 1819-1833 and demolished in 1845.

* A William Greer was renting an armory dwelling House No. 83 from 1841 to 1848.

ARMORY DWELLING HOUSE NO."163" (1841-1858) HARPER"S FERRY, ARMORY, VA.

error in numbering-
1841

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone					John Kennedy (omitted above) +	7.50	7.50	(1)
Dec. 31, 1844									
Dec. 31, 1846									
June 30, 1849									
Dec.31,1 1850									
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: Kennedy's name was added to the completed rent roll after most of the list had been completed. This apparently enduced an error in numbering houses after No. 163. House No. 163 was actually wood, not stone, as stated in the 1841 rent roll.

+ Kennedy may have been the armory painter.

ARMORY DWELLING HOUSE NO. 163 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood				listed as in 164.	William Graham (probably and not John Kennedy (painter?) (2)	7.50	(1) 7.50	William Graham probably in 1841
Dec. 31, 1844	Wood					William Graham	9.50	9.50	
Dec. 31, 1846	Wood					William Graham	9.50	9.50	
June 30, 1849	Wood	1		9	450	William Graham	9.50		
Dec. 31, 1850	Wood	1		11	300	William Graham	9.50	7.91	
June 30, 1851	Wood	1				George Cockwell			
June 30, 1852						George Cockwell			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	

Remarks: One-story frame house perhaps built about 1819; House demolished by armory in 1854.

(1) Rent roll for March 31,1841 lists House No. 164 as "wood" occupied by William Graham, who was paying a rent of $ 8.25. There is thus an error in numbering houses in the rent rolls in 1841; Graham was probably living in House 163 in 1841.
(2) John Kennedy was probably in House No. 165 in 1841.

ARMORY DWELLING HOUSE NO. 164 (1841-1858) HARPER"S FERRY, ARMORY, VA.

CAPTAIN JOHN H. HALL'S RESIDENCE, 1827 - 1840.

Location: Block , Lot No. , Camp Hill, Fillmore Street, near Harper's Graveyard
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry on later site of Paymaster's Quarters (Park Bldg No.56).

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick & Wood				listed as in 165	A.M. Kitzmiller, Chief Clerk	Free	Free	house misnumbered as Dwelling 165
Dec. 31, 1844	Brick & Wood					A.M, Kitzmiller, Clerk	Free	Free	No. 164
Dec. 31, 1846	Brick & Wood					A. M. Kitzmiller, Clerk	Free	Free	
June 30, 1849	Brick	2		2	2,500	"Broken up in 1848."			Paymaster's new House(Park Bldg. No. 56, erected
Dec.31,1 1850	Brick	2				Broken up in 1848.			on site of 164 in 1847-48.
June 30, 1851	Brick	2				Broken up in 1848.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	

Remarks: This two-story brick house was erected as Captain John H. Hall's residence in 1827, or his 1819 quarters were greatly enlarged in 1827-28. Hall received the pay and held the title of master armorer for the Rifle Factory. On December 10.1840 Captain Hall received $ 380.00 from the Armory for improvements that he had made to his house, yard, and garden during the period 1827-40. The armory demolished house No. 164 in 1848 in order to clear the grounds for the construction of the Paymaster's new house(Park Bldg. No. 56),which was later numbered as Armory Dwelling House No. 321, in 1859.

ARMORY DWELLING HOUSE NO. 165 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block , Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory, Shenandoah River.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone				listed as in 166	Thomas Laley	7.50	7.50	Probable occupant (1)
Dec. 31, 1844	Stone					John L. Rowe	8.60	8.60	
Dec. 31, 1846	Stone					John L. Rowe	8.60	8.60	
June 30, 1849	Stone	1		9	450	John L. Rowe	8.75		
Dec. 31, 1850	Stone	1		11	300	Peter Woodhall	8.75	8.75	
June 30, 1851	Stone	1				Peter Woodhall			
June 30, 1852						Peter Woodhall			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 165 was a one-story stone house erected ca. 1822-33. The armoru demolished the dwelling in 1854.

(1) due to numbering error in 1841 Kennedy was listed as being in House No. 163, but he was probably in House No. 165(see remarks on Houses 163 and 164- 1841).

ARMORY DWELLING HOUSE NO. 166 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone				listed as in 167	Zachariah Potts	7.50	7.50	probable resident
Dec. 31, 1844	Stone					Zachariah Potts	8.60	8.60	
Dec. 31, 1846	Stone					Zachariah Potts	8.60	8.60	
June 30, 1849	Stone	1		9	450	John Earnest	8.75		
Dec.31,1 1850	Stone'	1		11	300	John Earnest	8.75	8.75	
June 30, 1851	Stone	1				Henry Fossett			
June 30, 1852						Henry Fossett			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 166, a one-story stone dwelling erected ca. 1822-33; House demolished by Armory in 1854.

ARMORY DWELLING HOUSE NO. 167 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , at the U.S. Rifle Factory, on the Lower Hall Island, Shenandoah River.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick & wood				Listed as in 168	Hiram Carney *	8.25	8.25	probable resident
Dec. 31, 1844	Wood					Joshua T. Lewis	9.50	9.50	
Dec. 31, 1846	Wood					David Potts	9.50	9.50	
June 30, 1849	Stone	1		9	450	David Potts	9.50		"Located at Rifle Factory"
Dec.31,1 1850	Stone	1		9	450	"removed 1850"			
June 30, 1851	Stone	1				Removed in 1850.			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none.	

Remarks: House No. 167, apparently a one-story stone house built 1822-33 and demolished by the armory in 1850.

* Hiram Carney was paid $ 8.81 on August 11,1841 for improving a house and kitchen. R.G. 217, 2nd Series, File 6454, Voucher 4.

ARMORY DWELLING HOUSE NO. 168 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Shenandoah River.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone				listed as house 169	William Richards	8.75	8.75	
Dec. 31, 1844	Stone				168	Philip Burkhart	10.05	10.05	
Dec. 31, 1846	Stone					Philip Burkhart	15.00	15.00	
June 30, 1849	Stone	1		5	1,000	Philip Burkhart	15.00		
Dec. 31, 1850	Stone	2		6	800	Philip Burkhart	15.00	15.00	
June 30, 1851	Stone	2				Philip Burkhart			
June 30, 1852						Philip Burkhart			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	none	none	House and lot reserved from 1852 sale	for U.S. use.

Remarks: House No. 168, a two-story stone house erected ca. 1822-1833. House reserved from the 1852 sale for armory use. Dwelling renumbered as Armory Dwelling House No. 7 about 1859. In July 1865, Armory Dwelling No. 7 , a two-story stone house, was reported to have been demolished by Union soldiers in 1864 "to make room for the military railroad that was built to supply Sheridan's army in the Shenandoah Valley.

ARMORY DWELLING HOUSE NO. 169 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. , On the Upper Hall Island, above the U.S. Rifle Factory, Shenandoah River.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Wood				listed as House 170	Thomas Kirgin *	8.75	8.75	
Dec. 31, 1844	Wood					Thomas Kirgin	10.05	10.05	
Dec. 31, 1846	Wood					Thomas Kirgin	10.05	10.05	
June 30, 1849	Wood	1		7	600	Thomas Kirgin	12.00		
Dec. 31, 1850	Wood	1		9	450	Charles Holt	12.00	12.00	
June 30, 1851	Wood	1				Charles Holt			
June 30, 1852						Charles Holt			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	none	none	House and lot reserved from the 1852 sale for U.S. use.	

Remarks: House No. 169 was a one-story stone dwelling erected ca. 1822-33 and demolished by the armory in 1854.

* Thomas "Kugin", "Keigin", "Kergin" or Kirgin had a 1831 claim for $ 35.00 for building a staircase, digging a cellar, for 1 lock, painting house, kitche, smoke house, fence, stable, and privy, He was paid $ 24.85 in settlement of this claim on July 20, 1838. R.G. 217, 2nd Series, File 2729, Voucher 95B.

SECTION H

STABLE AND SLAUGHTER HOUSE SITES LEADED BY U.S.

ARMORY DWELLING NOS. 170 - 173.

Located on North Bank of Shenandoah River, Block G,

Shenandoah Street.

In addition to the stables described in this section, the Armory, on April 20, 1843, paid Eli H. Carrell $ 191.00 "for his stable on the margin of the Shenandoah River on foundations and embankment built by the U.S." John Littlejohn had erected this frame stable on the U.S.-built foundations and sold his rights to the stable to Carrell. for $ 240.00. The U.S. deducted $ 49.00 as unpaid ground rent for the stable site for two years from the money paid Carrell. This indicates that Carrell acquire title to the stable in 1841. (R.G. 217, 3rd Series, File 187, Voucher No. 99.

Eli H. Carrell was the proprietor of the U.S. and Virginia House Hotels, located on Wager Ferry Lots No. 6,7,8,and 9, from June 1842 to March 1845.

For site location maps, see:

Map No. 1, (1835), p. 13.

Map No. 2, (1834), p. 14.

Map No. 3, (1848), p. 15.

1841 No. ARMORY DWELLING HOUSE NO."170" (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block , Lot No. ,
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Stone				Listed as house 171	Office - Richard Parker (Paymaster)	10.00	50.00	Omitted 40.00 for the year 1840.
Dec. 31, 1844						not mentioned			
Dec. 31, 1846						not mentioned			
June 30, 1849									
Dec.31,1 1850									
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks: This stone building may have been located Lot 6, Block D, Shenandoah Street. Major John Symington's Legend for S. Howell Brown's 1848 map of Harper's Ferry has "X" for "Old Office" located on Lot 6, Block D.

GROUND RENT, 1844

SLAUGHTER HOUSE SITE.

ARMORY DWELLING HOUSE NO. 170 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block A. , Lot No. , Shenandoah Street, on north bank of river.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry or at Block G, Shenandoah Street.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						not listed			
Dec. 31, 1844	ground rent					Ground rent for slaughter house William Megraw ++	2.62	13.11	
Dec. 31, 1846	Ground rent					Ground rent for a slaughter house William Megraw (McGraw)	2.62	2.62	
June 30, 1849	"On the Shenandoah near the Arsenal.					Ground rent of slaughter house William Magraw	2.62		
Dec.31,1 1850	Site for a slaughter house					Willam McGraw	2.62	2.62	
June 30, 1851	Site for a slaughter house					William McGraw			
June 30, 1852						Building removed and site cleaned up in 1852.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: Slaughter house house was probably located on the southern end of Block A, Shenandoah, between the southern side of the Winchester and Potomac Railroad track and embankment and the north bank of the Shenandoah River. Another possible location for the slaughter house would have been at Block G, Shenandoah Street. See "Z"-"Old Stables, Wood Yard, &c.," on S. Howell Brown's 1848 map of Harper's Ferry.

++ On March 13, 1839, William McGraw leased vacant Wager Lot No. 22 for 10 years, effective April 1,1839, from Gerard B. Wager. McGraw, a butcher, erected a two-story stone dwelling on Lot 22.(See Armory Dwelling House No. 180, p. 233.) McGraw died in November 1847.

Ground rent for a Stable

ARMORY DWELLING HOUSE NO. 171 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block G ; Lot No. , Shenandoah Street, on the bank of the Shenandoah River.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						Not mentioned			
Dec. 31, 1844	Ground rent of a Stable					Philip Coons (merchant)	3.00	6.00	
Dec. 31, 1846	Ground rent of a stable					Philip Coons	3.00	3.00	
June 30, 1849	Ground rent of a stable					Philip Coons	3.00		
Dec.31,1 1850	Site for a slaugher house(sic) -probably stable					Philip Coons	3.00	3.00	
June 30, 1851	Site for a slaughter house(sic)					Philip Coons			
June 30, 1852						stable apparently removed and site cleaned up in 1852.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: Stable site apparently located on Block G, Shenandoah Street, see site "Z"="Old Stables, Wood Yard, &c.," on S. Howell Brown's 1848 Map of Harper's Ferry.

For more data on Philip Coons, see House No. 179, p. 232. Coons also owned Park Bldg. No. 10.

ARMORY DWELLING HOUSE NO. 172 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Ground Rent
for Stable Site

Location: Block G , Lot No. , Shenandoah Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						Not mentioned			
Dec. 31, 1844	Ground rent for a		stable			John C. Unseld *	3.00	3.00	
Dec. 31, 1846	Ground rent for a		stable			John C. Unseld	3.00	3.00	
June 30, 1849	Ground rent for a		stable			John C, Unseld	3.00	3.00	
Dec.31,1 1850	Site for a stable					John C. Unseld	3.00	3.00	
June 30, 1851	Site for a stable					John C. Unseld			
June 30, 1852						Building removed and the lot cleaned up in 1852.			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot reserved from U.S 1852 sale for armory use.

Remarks: Stable apparently located on Block G. Shenandoah Street, see "Z" -"Old Stables, Wood Yard,&C, on S. Howell Brown's 1848 Map of Harper's Ferry.

* Also see House No. 182,-p.235 under 1850 for mentioned of Unseld.

Garden

ARMORY DWELLING HOUSE NO. (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block , Lot No. ,

S. Howell Brown's 1852 Map of Harpers Ferry

S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						Not mentioned			
Dec. 31, 1844	rent for	garden				James Duncanson	0	10.00	Delinquent $ 10.00
Dec. 31, 1846	rent for	garden				James Duncanson		10.00	" "
June 30, 1849									
Dec. 31, 1850									
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:

Remarks:

SECTION I

ARMORY DWELLING HOUSES NOS. 174 - 182

Located on Wager Six Acre Reservation Lots

Between High and North Cliff or Potomac Streets.

In 1847-49 the U.S. Armory purchased a total of 19 lots, or portions thereof, including the buildings standing on this land, in the Wager Six Acre Reservation for a total of $ 38,937.35. This figure included $ 15,357.69 paid for the land and $ 23,579.69 to acquire title to the buildings.

Full title was acquired to all of Wager Lots 12, 18, 19, 20, 21, 22, 23, 26, 27, 29, 33, and 34. Full title was also purchased to the northern ends, to a depth of 25 feet, of the following Wager Lots: No. 15-subdivision 4, 16, 17, 24, 25, and 28.

The stables, houses, and out-buildings fronting on the south side of the 15-foot wide alley that separated the the Wager Six Acre Reservation from the U.S. Musket Factory yard were demolished in 1848-49 to widen the alley into a 40-foot wide fire lane that was to protect the Musket Factory workshops and storehouses from fire that might originate in structures located on Six Acre Reservation land.

The new street was named North Cliff Street and later was known as Potomac Street.

The brick and stone dwelling houses located on the southern ends of these newly acquired Wager Lots, fronting on High or Washington Street, were retained by the Armory for use as dwelling houses for Armory clerks, inspectors, and foremen. These seven retained houses, No. 176 to 182, had all been constructed by private individuals on privately owned land in the period 1839-1843. Their combined estimated value in 1848 was $ 14,500.

MAP NO. 20

"MAP of the Relative Position of the Reserved Land(of the Wager Six Acre Reservation) & Public Works(The U.S. Musket Factory) at HARPERS FERRY, VA. - 1844"

Major John Symington, Superintendent of the Harper's Ferry Armory, submitted this copy of the 1844 map to the Ordnance Department on March 22, 1847.

National Archives Record Group No. 121, Public Buildings Service, Harpers Ferry Laminated Material(Drawer 5, Portfolio No. 1).


After 1847-48, Armory Dwelling Houses No. 178 to 182 were located on the following U.S. owned Wager Lots:

House No.	Wager Lot No.	Description of House:
176	18	2-story, brick.
177	19	2-story, brick.
178	21	2-story, stone.
179	20	2-story, brick .
180	22	2-story , stone.
181	26	2- story, stone.
182	27	2-story, stone.
" 183"	H (Block AA, Lot 1)	2-story, stone

Buildings fronting on the 15-foot wide alley marked "S"(for stables" and "H" for (Houses) were demolished in 1848-9 in order to widen the narrow alley into a 40-foot wide street and fire lane that was named North Cliff Street

The location of House No. 174 on Lot 26 and House No. 175 on Lot No. 20 is purely hypothetical. Both dwellings were listed as stone.

1844 MAP


Potomac River.
Shenandoah
Winchester & Potomac Rail Road.
Shenandoah Street.
N
High Street, leading to Charlestown.
Armory Canal.
Alley - 16 feet.
Alley - 10 feet.
Arsenal.
Arsenal.
Office.
Hotel.
Hotel.
Paymaster's Quarters.
Bell Shop.
Boring Mill.
Stocking Shop.
Warehouse.
Forging Shop.
Forging Shop.
Forging Shop.
Shop.
Baltimore and Ohio Rail Road to Cumberland.
Potomac River.
Dr. Nicholas Marmion's 1829-1847 stone house and lot(U.S.
S = Wood or Stone stables demolished in 1848.
H = Stone houses demolished or moved in 1848.
Shop = Alexander Kelly's black smith shop.
A.B.C.D.
E.F.G.
11 & 12.
a.b.
++
H. i.

ARMORY DWELLING HOUSE NO. 174 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 27, Washington Street (on Alley).
S. Howell Brown's 1852 Map of Harpers Ferry Six Acre Reservation.
S. Howell Brown's 1869 Map of Harpers Ferry Probable location.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						Probable location: on the north end of Wager Lot No. 26, so that			
Dec. 31, 1844						House No. 174 fronted on the 15-foot wide alley that was widened into North Cliff Street in 1848-49.			
Dec. 31, 1846						Purchased by U.S. June 9, 1847.			
June 30, 1849	Stone					Charles W. Button	18.75	18.75	
Dec. 31, 1850				5	900	"Broken up in 1848"			
June 30, 1851						"Broken up in 1848."			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot reserved from 1852 sale for U.S. use.

Remarks: See Armory Dwelling House No. 182 for history of Lot 27 and 1844 description of house on alley, which may be House No. 174.

ARMORY DWELLING HOUSE NO. 175 (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 20, Washington Street

S. Howell Brown's 1852 Map of Harpers Ferry Six Acre Reservation.

S. Howell Brown's 1869 Map of Harpers Ferry Probable location

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						Probable location: on the northern end of Wager Lot No. 20, with house No. 175 fronting on the 15-foot wide alley that was widened into North Cliff Street (40 feet wide) in 1848-49.			
Dec. 31, 1844						Lot 20 purchased by U.S. June 3 and September 4, 1847.			
Dec. 31, 1846									
June 30, 1849	Stone					James O. Gannon	28.00	0	
Dec. 31, 1850				5	900	"Broken up in 1848."			
June 30, 1851						"Broken up in 1848.:"			
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot reserved from 1852 sale for U.S use.

Remarks: See Armory Dwelling House 179 for a history of Wager Lot No. 20 and a 1844 description of what may be Dwelling House No. 175- the stone house fronting on the alley.

ARMORY DWELLING HOUSE NO. 176 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 18, Six Acre Reservation High Street
S. Howell Brown's 1852 Map of Harpers Ferry Also Armory Dwelling House No.14(1859)
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						U.S. purchased House No.176 and Lot No. 18 from Gerard B. Wager for $ 1,806.00 on July 1, 1847 and Samuel Lover's lease to the			
Dec. 31, 1844						house and lot on July 2, 1847 for $ 800.00. Total cost, 1847: $ 2,606.00.			
Dec. 31, 1846									
June 30, 1849	Brick	2		3	2,000	?	27.50		
Dec.31,1 1850	Brick	2	wood shingle	3	2,000	William McSherry	37.50	75.00	
June 30, 1851	Brick					William McSherry			He was U.S.ranger in charge of forest land on Loudoun Heights.
June 30, 1852						William McSherry			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 176 described in 1844 as "On High Street a 2-story brick house, 30 by 22 feet, covered with shingles, and cellar underneath. House constructed by Gerard B. Wager, 1836-41. Lover leased house and lot for 99 year, effective October 1, 1841 at annual rent of $ 175, plus paying all taxes. On alley in 1844,"a stable for wood, with loft for hay." Frame stable leased by Wager to William Correll in 1841, who operated the "Virginia House Hotel", which was located on Wager Lot No. 5. The armory demolished the stable in 1847-48. House 176 and lot reserved from 1852 sale for U.S. use. House renumbered as Armory Dwelling House No. 14 about 1859. In July 1865, described as "two and a half story, brick. In good condition and vacant." House sold October 22,1884 to John and George Dittmeyer for $1,055.00. U.S. issued the deed on June 22,1886.

ARMORY DWELLING HOUSE NO. 177 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 19, Six Acre Reservation, High Street.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Also Armory Dwelling No. 15(1859)
Armory Dwelling House B (1852)

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						U.S. purchased Lot No. 19 from Gerard B. Wager for $ 750.00 on June 30, 1847. The U.S. purchased title to House No. 177 and the			
Dec. 31, 1844						lease to the lot from the Ann Reed estate on September 9, 1847 for $ 1,845. Total cost: $ 2,595.00.			
Dec. 31, 1846									
June 30, 1849	Brick	2		3	2,000	Horatio Jarboe		25.00	
Dec.31,1 1850	Brick	2	wood shingle	3	2,000	A. M. Kitzmiller, Clerk	Free	Free	Wm. H. Moor owed 87.08
June 30, 1851	Brick	2				A. M. Kitzmiller,Clerk			
June 30, 1852						A. M. Kitzmiller, Clerk			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 for U.S. use.

Remarks: House No. 177 described in 1844 as "On High Street a 2-story brick house,30 by 22 feet, covered with shingles, and cellar underneath, a porch in front and rear." Wager leased the lot to Charles Button, administrator of the Ann Reed Estate for 10 years, Jan. 1,1841, at an annual rent of $ 160.00. Button constructed House No. 177 in 1841, which he used as his saddle and harness making shop and dwelling; On Alley in 1844"a wooden stable,with hay loft 20 by 18 feet. This erected 1839-41 by Samuel Gibson, under lease from Wager. Gibson operated a "National Hotel"(1834-39) and dry goods store located on Wager Lot No. 5. Armory demolished the stable in 1848. House No. 177 renumbered as House No. 15 about 1859. Described in 1865 as 2½ story,brick, in good condition and vacant. House sold December 1869 to Patrick Daley for $ 453.00. U.S. issued deed on January 31, 1880.

ARMORY DWELLING HOUSE NO. 178 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No.21, Six Acre Reservation, High Street.

S. Howell Brown's 1852 Map of Harpers Ferry

S. Howell Brown's 1869 Map of Harpers Ferry Also Armory Dwelling No. 17(1859)

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						The U.S. purchased House No. 178 and Lot 21 from Gerard B. Wager for a total of $ 3,000.00 on July 1,1847. This sum included			
Dec. 31, 1844						$ 1,000.00 for the land and $ 2,000.00 for the buildings.			
Dec. 31, 1846									
June 30, 1849	Stone	2		5	1,000	Albert Beale	12.50	-	
Dec.31,1 1850	Stone	2	wood shingle	7	600	Albert Beale William Mahony	12.50 7.50	25.00 7.50	
June 30, 1851	Stone	2				Albert Beale William Mahony			
June 30, 1852						Albert Beale William Mahony			

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 178 was built by Gerard B. Wager, probably in 1836, as his residence, and certainly prior to 1841. House described in 1844:"On High stree a 2-story stone house,with basement,30 by 26 feet, covered with slate, with back buildings,all well finished; on alley a stone stable 26 by 20 feet,with hay loft;also, a stone smoke house 10 by 9 feet. The armory demolished the stone stable in 1848. House No. 178 renumbered as House No. 17 about 1859. Described in July 1865 as "three story, stone, in good condition and occupied as Ordnance Office." U.S. sold house in December 1869 to Edith O" Donnell for $ 2,275.00. The U.S. issued the deed on January 10,1872.

ARMORY DWELLING HOUSE NO. 179 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No.20, Six Acre Reservation, High Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Also Armory Dwelling No. 16(1859). and Armory Dwelling C(1852).

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						The U.S. purchasedthe land from Noah H. Swayne(the husband of Sarah Ann Wager) for $ 833.33	on June 8, 1847 and House No. 179		
Dec. 31, 1844						and lease to the lot from Philip Coons for $3,500.00 on September 4, 1847. Total Cost: $ 4,333.	33.		
Dec. 31, 1846									
June 30, 1849	Brick	2		2	2,500	J. E. P. Daingerfield, Clerk	Free	Free	
Dec.31,1 1850	Brick	2	slate	3	2,000	J. E. P. Daingerfield,Clerk	Free	Free	
June 30, 1851	Brick	2				J. E. P. Daingerfield, Clerk	Free		
June 30, 1852						J. E. P. Daingerfield,Clerk	Free		

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1852 Sale	Not sold	none	none	House and lot reserved from 1852 for U.S. use.

Remarks: House 179 was built by Philip Coons, probably about 1841. The house was described in 1844 as "On High Street a 2-story brick house, with basement, and cellar under basement 34 by 23 1/3 feet covered with slate, well finished. On the alley a 2-story stone house,26 by 22 feet, covered with shingles. The alley house was erected by Isreal Russell, a merchant, in 1839. The armory demolished the alley house in 1848.
House No. 179 was renumbered as Armory Dwelling 16 about 1859. House described in July 1865 as three story brick, in fair condition and occupied as Provost Marshal's Office. U.S. sold house to Mary D. Cochrane on December 1869 for $ 755.00. U.S. issued the deed on January 28, 1885.

ARMORY DWELLING HOUSE NO. 180 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 22, Six Acre Reservation, High Street.

S. Howell Brown's 1852 Map of Harpers Ferry

S. Howell Brown's 1869 Map of Harpers Ferry Also Armory Dwelling No. 18(1859) and Armory Dwelling D (1852).

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						The U.S. purchased lot no. 22 from Gerard B. Wager for $ 1,000.00 on July 1, 1847 and title to House No. 180 and the lease to the lot			
Dec. 31, 1844						from the William McGraw estate for $ 2,500.00 on June 8, 1848. Total cost: $ 3,500.00.			
Dec. 31, 1846									
June 30, 1849	Stone	2		2	2,500	George H. Ward, Clerk	Free	Free	
Dec. 31, 1850	Stone	2	slate	3	2,000	George H. Ward	Free	Free	
June 30, 1851	Stone	2				George H, Ward, Clerk	Free	Free	
June 30, 1852						George H. Ward, Clerk	Free	Free	

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 180 was erected by William McGraw in 1839-40. The house was described in 1844 as" On High street a 2-story stone house, with basement, 30 by 26 feet, covered with slate, well finished, and a stone corn-house 14 by 9 feet; on the alley a wooden stable 27 by 20 feet, with hay loft." The armory demolished the stable in 1848. House No. 180 was renumbered as Armory Dwelling 18 about 1859. In 1865 the house was described as "three-story stone, in fair condition, occupied as Quartermasters Office." U.S. sold House No. 180 to Alexander Murphy for $ 604.00 in December 1869. The U.S. issued the deed for the property on October 31, 1879.

ARMORY DWELLING HOUSE NO. 181 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 26, Six Acre Reservation, High Street.

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Also Armory Dwelling No. 19 (1859) and

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						The U.S. purchased Lot No. 26 from Noah H. Swayne (the husband of Sarah Ann Wager) for $ 833.33 on June 8, 1847 and title to House			
Dec. 31, 1844						181 and the lease to the lot from Hugh McAleer for $ 2,250.00 on September 14,1847. Total cost: $ 3,083.33.			
Dec. 31, 1846									
June 30, 1849	Stone	2		2	2.500	James O. Connor	32.00		
Dec.31,1 1850	Stone	2	wood shingle	3,	2,000	Nathan Sagle	32.50	32.50	
June 30, 1851	Stone	2				Nathan Sagle			
June 30, 1852						Nathan Sagle			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 181 probably built by Patrick Hagan in 1843-44 and described in 1844 as "On High street a 2-story stone house, with basement, 24 by 20 feet, covered with shingles." In 1839-40 Robert Wallace built(probably) a house located on alley. This described in 1844 as"on alley a 2-story stone house, 30 by 26 feet, covered with slate, and a 1-story stone kitchen, 14 by 12 feet." The armory demolished the alley house and kitchen in 1848. House No. 181 was renumbered as Armory Dwelling No. 19 about 1859. House described in 1865 as "three-story stone, in good condition. Vacant." U.S. sold the house in December 1869 to James McGraw for $ 1,000.00. U.S. issued the deed on January 10,1872.

ARMORY DWELLING HOUSE NO. 182 (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Wager Lot No. 27, Six Acre Reservation, High Street

S. Howell Brown's 1852 Map of Harpers Ferry

S. Howell Brown's 1869 Map of Harpers Ferry Also Armory Dwelling House No. 20(185[illegible] and Armory Dwelling No. E (1852).

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						U.S. purchased lot No. 27 and House No. 182 from Michael Foley, a carpenter, for $ 2,000.00 on June 9, 1847. Of this total,			
Dec. 31, 1844						$ 1,000.00 was for the land and $ 1,000.00 for the buildings.			
Dec. 31, 1846						Michael Foley had purchased vacant lot No 27 from James B. Wager on June 18, 1836 for $ 775.00.			
June 30, 1849						Nicholas Marmion (Dr.)	45.00		
Dec. 31, 1850	Stone	2	slate	3	2,000	vacant			John C. Unseld owed 34.50
June 30, 1851	Stone	2				J. M. Bodman, Clerk	Free	Free	
June 30, 1852						J. M. Bodman, Clerk	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: House No. 182 was built by Michael Foley ca. 1836-37; In 1844 his residence was described as" Vacant on High street on the alley, a two-story stone house, 30 by 20 feet covered with slatem & a 2-story stone kitchen, 28 by 16 feet, shingle roof." The armory did not demolish these structures in 1848, thus indicating that House No.182 must have been set back at least 25 feet from the southern boundary of lot 27 in order to escape destruction when the 15-foot wide alley was widened to 40 feet in 1847-49. House renumbered as Armory Dwelling No. 20 about 1859 and described in 1865 "as three story stone, in bad condition, occupied as quarters for Ordnance Detachment." U.S. sold the house on May 25, 1880 to James McGraw for $ 325.00. The U.S. issued the deed on June 1,1880.

Not a historic house no. used in the 1850s.

This house should have been No. 174 or 175 on the 1848-51 rent rolls.

ARMORY DWELLING HOUSE NO."183" (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block AA Lot No. 1, Camp Hill, fronting on High Street
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry Block H on 1844 Map
This might be House No. 174 or 175.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841			35 foot wide lot on High Street		fronting	Dr Nicholas Marmion in a house he had built on leased U.S. land	Ground rent		He refused to pay his ground r
Dec. 31, 1844	Stone	2			2,260	Dr. Nicholas Marmion	Ground rent	271.25	refused to pay
Dec. 31, 1846					2,000	Dr. Nicholas Marmion	Ground rent	"	refused to pay from June 3,1829
June 30, 1849			buildings on		Dr. Marmion's	U.S. purchased title to the leased lot on November 30,1847 for		$ 2,000.00	cash. Ground re
Dec.31,1850									debt cancelled.
June 30, 1851									
June 30, 1852									

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	Lot and house reserved from 1852 sale for U.S. use.

Remarks: Dr. Nicholas Marmion constructed a 2-story stone dwelling on Lot H under a lease from the Secretary of War dated June 3, 1829. The house was completed in 1829. In 1844 his dwelling was described as "A stone house, two stories, with basement and gallery. 35 by 22 feet; also a wooden 1-story house, 16 by 14 feet." Marmion resided in this house from 1829 to 1847. On November 30, 1847 the U.S. purchased his title to the 2 buildings and lot H and cancelled all the ground rent that he had failed to pay from 1829 to 1847. The Government renumbered this House as No. 13 ca.1859. In 1865 described as two-story stone, in good condition, occupied free of rent by Mr. Henry Russell, by order of Col. H.K. Craig. House sold by U.S. to Storer College for $ 362.40 in Dec. 1869. U.S, issued the deed on December 18, 1879.

FIVE QUARTERS FOR ARMORY OFFICERS,

Built 1846 - 1859

Armory Dwelling Nos. "184" to "188".

MAP NO. 21


MAP OF HARPER'S FERRY(1848-51)
Prepared in Compliance with Letter to Major(John) Symington, April 22, 1848,' Drawn by S. Howell Brown in 1848. The section of the map relating to Virginius Island was revised and updated by Superintendent Symington(in red inck) in January 1851. Scale 165 feet to inch.

Original linen map, only existing copy is Harpers Ferry NHP Map No. 77, in Park Map Case, Drawer No.4.

While Brown fails to include the numbered Armory Dwelling Houses on this detailed map, he does indicate the house lot system and streets as they existed in 1848.

"C.O."s Quarters and Stables" are the Commanding Officer's or Superintendent of the Armory's Residence, erected in 1846-47, and now the south wing of Park Bldg. No. 59.

"Paymaster's Quarters" was erected in 1847-48 and enlarged in 1858-59. This is present Park Bldg. No. 56.


148
147?
S
F
150?
149
?
165
114
113
112
111
110
109
108
107
106
105
104
103
102
101
100
99
98
97
96
94
93
92
POND
132
133
135
138
146
146
G
144
134
136
137
139
140
142
141
143
106
117
118
119
120
121
122
123
124
127
128
131
125
126
129
130
Pay Masters Quarters
185
Publi
Grave
20' Stables
B.O. Quarters
N

MAP NO 22


"Map of Harpers Ferry, 1852,
by S. Howell Brown," Approved by Col. Benjamin Huger,
Superintendent, Harper's Ferry Armory, April, 1852.
Scale 165 feet to the inch. The working copy made by
A. M. Kitzmiller, Superintendent's Clerk. This MS linen
map is the only known extant copy of Brown's 1852 map.

Harpers Ferry NHP Map No. 89, Park Map Case, Drawer No. 3.

On June 10, 1852, Secretary of War C. M. Conrad approved this map or plat on which surveyor S. Howell Brown laid out 312 house lots from the U.S. Armory land at Harpers Ferry. These were offered for sale on August 31 and September 1-2, 1852.

The map shows the new street systems that were established and all the public lands and boundaries thereof that were reserved from the 1852 sale for continued U.S. use. Two hundred and twenty-four building lots were sold in 1852.

Map shows the grounds around the Commanding Officer's Quarters and Paymaster's Quarters that were reserved for U.S. use in 1852.


M
A
H
A
O
A
P
FERRY
COMMD. OFFICER'S QUARTER
GRAVE YARD
ROAD

MAP NO. 23

" Map of HarperS Ferry - Plat of the Harpers Ferry Armory Property laid off into lots for sale in pursuance of the Act of December 15th, 1868. Approved November 16th 1869 by Wm. W. Belknap, Secretary of War. Map completed by S. Howell Brown, Nov. 1,1869. Scale 165 feet per inch."

Copied by Architect Archie W. Franzen from an original linen drawing in color, which in turn had been copied from the original by Pusey & Jone Company, Nov.26, 1901.

Harpers Ferry NHP Map No. 83, Map Case, Drawer No. 10.

On his 1852 map, Surveyor S. Howell Brown had subdivided part of the U.S. Armory lands in to 312 building lot. In 1869 he subdivided the remaining undivided U.S. owned land into 188 additional building lots, thus bringing the grand total of lots to 500. Two hundred and twenty-four of these lots had been sold in 1852; 31 additional lots were donated in 1869, and the balance were to be offered at public auction in December 1869.

Armory Dwelling No. 25, Storer College Lot, is "House No. 184", the Commanding Officer's or Superintendent's Quarters, erected in 1846-47. This house now forms the south wing of Park Bldg. No. 59.

Armory Dwelling No. 30,Storer College Lot, Fillmore Street. House No."186", the Paymaster's Clerk's Quarters, erected in 1857-58. This is now Park Bldg. No. 58.

Armory Dwelling House No. 31, Storer College Lot, Fillmore Street. House No."187", the Superintendent's Clerk's Quarters, erected in 1857-58. This is now Park Bldg. No. 57.

Armory Dwelling No. 32, Storer College Lot, Fillmore Street. "House No."185", the Paymaster's Quarters, erected in 1847-48 and enlarged in 1858-59. This is now Park Bldg. No. 56.

S T.

SEMINARY LOT

N

MAGAZINE HILL

BB

PUBLIC SQUARE

C L A Y

S T.

Y O U N G

S T.

S T O R E R

C O L L E G E

H A R P E R

S. C L I F F

G R A V E

4 ACRES

J A C K S O N

C O L L E G E

I O D F E L L O W S

M. E. PAR.

M. P. CH. PAR.

P. E. PAR.

H H

G G

F F

Y O R K

Not a historic house no. used in the 1850's

House no carried on 148-51 rent rolls.

ARMORY DWELLING HOUSE NO. "184" (1841-1858) HARPER'S FERRY, ARMORY, VA.

Location: Block Lot No. Commanding Officer's Quarters, Camp Hill. Fillmore Stree

S. Howell Brown's 1852 Map of Harpers Ferry Armory Dwelling House No. 25(1859).

S. Howell Brown's 1869 Map of Harpers Ferry Park Bldg. No. 59, South Wing of.

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841									
Dec. 31, 1844									
Dec. 31, 1846						House constructed 1846-47 by Armory			
June 30, 1849	Brick	2	tin and slate		14,405	Superintendent: Major John Symington	Free	Free	
Dec. 31, 1850						Major John Symington	Free		
June 30, 1851						Major John Symington	Free		
June 30, 1852						Superintendent: Brevet Colonel Benjamin Huger	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Remarks: The large and impressive brick house, two stories over an elevated stone basement, was designed and erected by Major John Symington in 1846-47 at an approximate cost of $ 14,405.00. The main house measured about 41 by 43 feet and a lower two-story wing on the north side was joined to the main edifice by means of a lower brick passageway. The hipped roofs were covered with tin and slate. The main house had four chimneys and 10 fireplaces with marble mantels. The wing had one fireplace. The house had cut stone water table, sills, cornice and coping. The gutters and downspouts were of copper. House used as quarters for the Armory superintendents from 1847 to 1861. The badly damaged house survived the Civil War. On December 15, 1869, the United States donated the house, numbered as Armory Dwelling No. 25 about 1859, to Storer College. Photos: HF -20 (1862), HF-31 (1862) and HF-338(November 1862).

Not a historic number used in 1850's as the house was not carried on the 1848-51 rent rolls.

ARMORY DWELLING HOUSE NO."185" (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block Lot No. PAYMASTER'S QUARTERS, CAMP HILL, Fillmore Street.
S. Howell Brown's 1852 Map of Harpers Ferry Armory Dwelling No. 32(1859)
S. Howell Brown's 1869 Map of Harpers Ferry Park Bldg. No. 56.

Date of Rent Roll	Material built of	No.of stor-ies	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841									
Dec. 31, 1844									
Dec. 31, 1846						House constructed by armory 1847-48 and enlarged 1858-59.			
June 30, 1849	Brick	1	tin		7,303	Paymaster Edward Lucas,Jr.	Free as armory supt.		Lucas had served from 1837 to 1841.
Dec.31,1 1850						Edward Lucas,Jr. P.M.	Free		
June 30, 1851						Edward Lucas, Jr., P.M.	Free		
June 30, 1852						Edward Lucas, Jr., Pay Master	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale from U.S. use.

Photos: HF-47 (1861), HF-352(1862); HF-40 (1863); HF-341(1864);HF- 78(1866).

Remarks: The Paymaster's quarters was erected in 2 stages. As designed and built by Major John Symington in 1847-48 at and approximate cost of $ 7,303.00, the house was a 1-story brick house over a full 1-story high stone basement, measuring 56 feet 4 inches by 39 feet 9 inches in size. Theedifice had cut-stone water table, door and window sills , cornice and coping. The gutters and downspouts were of copper and the hipped roof was covered with tin. In 1858-59, Superintendent Henry W. Clowe designed and added a brick second story to the original house at a cost of about $ 4,000.00. The new hipped roof was covered with slate, wooden porches were added to the east and west elevations and the basement was fully excavated around all four exterior sides. House used as quarters of paymasters from 1848 to 1861, by General Sheridan as his headquarters in 1864. The dwelling survived the Civil War and on December 15,1869 the U.S. donated the house and lot to Storer College.

Not a historic house No. used in 1850's

ARMORY DWELLING HOUSE NO. "186" (30-1859 No.) HARPER"S FERRY, ARMORY, VA.

Location: Block . Lot No. , PAYMASTER'S CLERK'S QUARTERS, FILLMORE STREET, CAMP HILL.

S. Howell Brown's 1852 Map of Harpers Ferry

S. Howell Brown's 1869 Map of Harpers Ferry (Park Bldg. No 58).

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
Nov. 1858	Brick	2	slate		6,820	Benjamin Mills, Master Armorer	Free	Free	Nov. 1858 to Nov. 1858
1859						Thomas Leiper Patterson, Civil Engineer supervising construct of new Potomac Dam			Nov. 1859 to August 1860
1860						John E. P. Daingerfield, Paymaster's Clerk	Free		ca. Aug. 1860 to April 19, 1861
1861						John E. P. Daingerfield, P.M.'s Clerk	Freee		

	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
1869 Sale	12/15/69	donated	Storer College	December 15, 1869

Remarks: Armory Dwelling House No. 30 was designed and erected by Superintendent Henry W. Clowe in 1857-58 at a cost of $ 6,820. The main house was a two-story brick structure with a slate- covered hipped roof and measured 39 feet 8 and 5/8 inches by 33 feet 2¼ inches in size. A two-story brick service wing, 23 1½ inches by 18 feet 8½ inches adjoined the south side of the main house. The east or front elevations of both the main house and wing each had one-story frame porches. The windows sills were of cut stone and the downspouts and gutters were of copper. There were four rooms on each of the two floors in the main house and three rooms in the service wing, the latter consisting of a kitchen and pantry on the first floor and a small bedroom on the second. There was a full basement under the rear wing and half an excavated basement under the main dwelling. In 1865 Armory Dwelling No. 30 was described as "Two story, brick, in bad condition, occupied for Army purposes." On December 15, 1869, the U.S. donated House No. 30 and lot to Storer College.

Not a historic house No.
used in 1850's

ARMORY DWELLING HOUSE NO."187"(~~31~~-1859 No.) HARPER"S FERRY, ARMORY, VA.

Location: Block SUPERINTENDENT'S CLERK'S QUARTERS, FILLMORE STREET, CAMP Hill. Lot No.,

S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry (Park Bldg. No. 57)

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
1858	Brick	2	slate		6,820	Chief Clerk Archibald M. Kitzmiller	Free		September 21, 1858 moved in
1859						A. M. Kitzmiller, C. Clerk	Free		
1860						A. M. Kitzmiller, C. Clerk	Free		
1861						A.M. Kitzmiller, C. Clerk	Free		To April 19, 1861

1869 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	12/15/69	Donated	Storer College	December 15, 1869

Remarks: Armory Dwelling House No. 31 was designed and erected by Superintendent Henry W. Clowe in 1857-58 at a cost of $ 6,820. The main house was a two-story brick structure with a slate-covered hipped roof and measured 39 feet 8 5/8 inches by 33 feet 2½ inches in size. A two-story brick service wingm 23 1½ inches by 18 feet 8½ inches adjoined the south side of the main house. The east or front elevations of both the main house and wing each had one-story frame porches, The window sills were of cut stone and the gutters and down-spouts were of copper. There were four rooms on each of the two floors in the main house and three rooms in the service wing; the latter consisted of a kitchen and pantry on the first floor and a small bedroom on the second. There was a full basement under the south wing and an half excavated basement under the main house. In 1865 Armory Dwelling House No. 31 was described as "two-story, brick, in bad condition and occupied by the U.S. Sanitary Commission." On December 15, 1869, the U.S. donated the house and its lot to Storer College.

Not a historic no. used on the 1850 rent rolls.

ARMORY DWELLING HOUSE NO. "188" (1- 1859 No.) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 3, Shenandoah Street(on 1869)Map.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

MASTER ARMORER' NEW QUARTERS.
Park Bldg. No.36.

Date of Rent Roll	Material built of	No.of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
1858						Under construction 1858-59			
1859	Brick	2	slate		7,000	Paymaster's Clerk John E. P. Daingerfield	Free		Moved in July 1859 to Aug.1860.
1860						Armistead M. Ball,Master Armorer	Free		Moved in Sept. 1860
1861						Armistead M. Ball, M.A.	Free		To April 19,1861

1884 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	Photo HF-141(1865).
	10/22/84	$ 3,600.00	J. Garland Hurst	October 22,1886	

Photos HF-18(1862); HF.-224(1865); HF-141(1865); HF-361(1865), HF- 78 (1871-1880); HF-240(1861),HF-99(1892-96).

Remarks: House No. 1 was designed by Superintendent Henry W. Clowe and erected in 1858-59 at an approximate cost of $ 7,000 The main house was a 2-story brick building on stone masonry foundations, with cut-stone window sills, and slate-covered gable roof. The gutters and downspouts were of copper. The edifice measured 42 by 38 feet and a two-story brick service wing, 25½ by 20 feet, adjoined the main house on the south or rear side. The first floor of the main dwelling had a center hall and four rooms and the second floor, a hall and five rooms. There were eight fireplaces. The two-story rear wing had a two-story covered wooden porch on its east facade. There was a kitchen and pantry on the first floor of the wing and two small bedrooms on the second floor. The cellar under the rear wing contained a second kitchen. There was no cellar under the main house. In 1865 House No. 1 was described as "Two story, brick, in fair condition and occupied as Head Quarters by Genl. Egan." The residence had also served as the headquarters of Brigadier General John D. Stevenson from August 15, 1864 to April 1865. From 1866 to 1872 the Armory rented rooms in House No. 1 to various people. Zadoc Butts, the Ordnance Agent, had his office in this building, as did the former chief clerk A. M. Kitzmiller, and John Koonce. On August 17,1872, the U.S. leased most of the building to the town government of Harper's Ferry, rent-free, for use as town office, a school house, and jail. In return the town agreed to maintain the building. In 1880 the U.S. Post Office was also located in the house. The U.S. reclaimed the house in 1884 and sold it at public auction on October 22, 1884.

SECTION K

ARSENAL SQUARE ARMORY RENTALS, 1841-1852

BLOCKS A AND B, SHENANDOAH STREET

Houses No. "189" and "190".

For Location Maps, see

Map No. 1,(1835), p. 13.

Map No. 2,(1834), p. 14

Map No. 20, (1844), p. 226.

A non-historic house no. hot used in 1850's.

OLD PAY OFFICE

ARMORY DWELLING HOUSE NO."189" (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block B Lot No. 2, Shenandoah Street(1852)-Arsenal Square, at northwest corner
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No. of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841						Paymaster's Office	Free		
Dec. 31, 1844						Paymaster's Office	Free		
Dec. 31, 1846						Paymaster's Office (1)	Free		
June 30, 1849	Brick	1	slate			J.T. W. Sullivan, merchant tailor	37.50		
Dec.31,1 1850	Brick	1	slate			Isaac Fouke (lawyer)	17.50		
June 30, 1851						Not listed			Being used as town hall, jail, mayor's office.
June 30, 1852						(town hall, jail, and mayor's office.)			

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:	
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.	

Remarks: (1) In January 1848 the Armory Paymaster removed his office from the Old(1822) Pay Office into the remodelled central office Building, Armory Dwelling House No. 1, the latter structure being ocated in the Musket Factory yard. The Old Pay Office was a one-story brick structure, 24 by 18 feet, that was erected 1822 at a cost of $ 500.00 for the use of the Paymaster. The house had a wood shingle roof. This roof was replaced by slate in 1833 and in 1840 a one-story brick "fireproof" valut, 5 by 7 feet, with walls 2½ feet thick, was added to the rear or south side of the Pay Office at a cost of $ 234. The structure served as the Office of the Paymaster from 1822 to 1848 and as the town hall, jail, and mayor's office from 1852 to 1858. In April 1858 the Old Pay Office was removed and relocated in the Musket Factory.

A non-historic house no. not used in 1850's.

OLD SUPERINTENDENT"S OFFICE
ARMORY DWELLING HOUSE NO."190" (1841-1858) HARPER"S FERRY, ARMORY, VA.

Location: Block A Lot No. 1, Shenandoah Street,-Arsenal Square- northeast corner.
S. Howell Brown's 1852 Map of Harpers Ferry
S. Howell Brown's 1869 Map of Harpers Ferry

Date of Rent Roll	Material built of	No.of stories	Roof	Class	Value	Occupants	Rent per Quarter	Rent Due	Remarks
March 31, 1841	Brick	1	slate			Office of Supt. Edward Lucas, Jr. After April,1841,of Major	Henry K.	Craig. to	Nov.1844.
Dec. 31, 1844						Office of Supt. Major John Symington	Free		
Dec. 31, 1846						Office of Major John Symington	Free		
June 30, 1849		August	28,1848 leased to	Miss Mari	a Fellow s of Harper's Ferry Fe	male Semin ary for use as school room for girls.	Free		
Dec.31,1 1850	Brick	1	slate			Harper's Ferry Female Seminary School Room	Free		
June 30, 1851						Harper's Ferry Female Seminary School Room	Free		
June 30, 1852						Harpers Ferry Female Seminary school Room	Free		

1852 Sale	Date Sold	Price Paid	Purchaser:	Date U.S. issued deed to Purchaser:
	Not sold	none	none	House and lot reserved from 1852 sale for U.S. use.

Photos HF-628(1826 ca.); HF-18(1865);HF-492(ca.1883),HF-355(ca.1886)

Remarks: Superintendent's Office, a one-story brick building 28 by 21 feet, with wood shingled hip roof, was erected as a dwelling house, apparently in 1826, at a cost of about $ 450.00. It served as the residence of armorer James Clark from October 1826 to August 1832. The armory took possession of the residence in 1832 and remodelled the structure for use as the Superintendent's Office. The roof was slated in 1833. The edifice served as the office of the superintendent from 1832 to 1848, when the commanding officer of the armory moved his office into the newly remodelled central office building in the Musket Factory yard(See Armory Dwelling House No.1). From 1848 to 1854 the Old Office served as the school room of the Harper's Ferry Female Seminary. From 1854 to ca. 1858 it served as the free school house for the town of Harpers Ferry and from 1858 to 1861 as the town offices of the mayor and council. U.S. [illegible] the office

PART II

RENTAL POLICIES AT HARPER'S FERRY ARMORY, VIRGINIA, 1812 to 1852, AND RENTS COLLECTED, 1822 to 1851.

Section A

Armory Policy on Renting U.S. Owned Dwelling Houses:
1812 - 1821:

The first evidence bearing on the question of rents charged for Government Dwelling Houses appears in the Secretary of War's letter of January 24, 1812 to Pay Master Samuel Annin.

In that letter the Secretary ordered Mr. Annin:

"You will require and collect such rents as you may think reasonable for the houses occupied by the Armorers at Harpers-Ferry, charging rents from the 1 January 1812, and appropriate the proceeds of such rents to necessary repairs of the public buildings- rendering an account of the Same."[1]

As of October 1, 1811, there were 20 Armory-owned dwelling houses, occupied by 41 families, at Harper's Ferry. As the Armory superintendent, paymaster, and master armorer, each occupied a house free of rent, this meant that 38 families living in 17 quarters could have been charged rent. Because of the great shortage of housing and the war effort, the single men were rooming on the second floors of the Armory workshops and storehouses in 1812.

The records of the Armory Paymaster for the years 1812 to 1816 are no longer extant. An examination of the Paymaster's records for the period from 1817 to 1821 failed to uncover any rent rolls for the U.S. Armory at Harper's Ferry. It therefore seems probable that Armory superintendent James Stubblefield made no effort to collect rents from his employees from 1812 to 1821. The number of Armory dwelling standing in in 1821 was 87. These houses were occupied by 115 families.

1. Secretary of War Henry Dearborn to Paymaster Samuel Annin, January 24, 1812. Harpers Ferry NHP Microfilm Reel 18, Vol. 2, p. 149. Data from National Archives, Washington, D.C.

Section B

Ordnance Department Policy on Collecting Rents at the Harper's Ferry Armory, 1822 - 1829:

On February 22, 1822, Colonel George Bomford, Chief of Ordnance, notified both Superintendent Lee of the Springfield Armory,Mass., and Superintendent James Stubblefield of the Harper's Ferry Armory of the regulations that would govern the collection of rents on armory-owned dwelling houses, writing:

"The subject respecting the application of the funds derived from the rents of the public buildings at the National Armories, has been duly considered. And the Secretary of War is of opinion that the War Department is not authorized to apply the rents to any other, than public purposes, and that it will require the authority of an Act of Congress to apply them to the support of Schools, or of the Ministers of the Gospel. He therefore directs that rents shall be regularly charged to the persons who occupy the buildings, and the amount deducted from the sum due them on the Rolls, at the expiration of each quarter.

"The principal Officers at the Armory, Viz - the Superintendent, Paymaster, and Master Armorer, are not includedin the above rule, they will each be entitled to dwelling as heretofore - rent free.

"The Superintendents will fix the rate at which each dwelling shall be rented, having due regard to the value and convienance of each. The rents should be moderate. As the dwelling houses were erected for the benefit of the public, and theconvienance of the persons engaged in it, no other persons than those actually employed in the public service at the Armory, should be permitted to occupy them.

"It will be the duty of the Superintendent to keep allthe public buildings in a proper state of preservation; but the amount expended in repairing a dwelling house should in no instance exceed the proceeds of its rent. No other repairs should be permitted, but than expressly directed by the Superintendent.

"The Superintendent is authorized to set a part a suitable apartment for divine worship; and another or two, if necessary, for the use of schools."[2]

2. Harpers Ferry NHP Microfilm Reel 22, Vol. 3, pp. 218-220.

The method of collecting rent is revealed by the following instructions of Lt. Col. Bomford, issued to Paymaster McGuire, of the Harpers Ferry Armory, on December 17, 1822:

"...The mode of collecting the rents at Springfield is to charge each man, on the rolls, with the amount due from him for rent, and to deduct the same amount credited to him for work done. This mode is considered preferrable, to that which you have pursued in the last quarters accounts, and you will please to conform to it hereafter. It will, notwithstanding, be necessary to forward the rent roll..."[3]

The records of the Second Auditor of the Treasury Department, 1st Series, in National Archives Record Group 217, reveal that Stubblefield began collecting rent on the armory dwelling houses on July 1, 1822. A total of $ 596.50 was collected during the year, $ 305.25 from 94 renters in the 3rd quarter and $ 291.25 for the 4th quarter.[4]

The rent rolls , for the period 1823 to 1828 will be found in the "Statement of rents collected on dwelling houses belonging to the United States armory, Harper's Ferry, Virginia, and occupied by workmen employed in the said armory, from the year 1823 until the close of 1828, and the names of persons from whom collected," prepared by Superintendent James Stubblefield, and dated February 1, 1829.[5] (See Appendix No. 1).

Quarterly amounts collected, taken from the Paymaster's actual rent rolls in the Second Auditor's Records (the annual totals sometimes differ from those given by Stubblefield) will be found in Appendix No. 2.

3. HF NHP Reel 14, Vol.4, pp. 340-341.
4. National Archives Record Group 217, Records of 2nd Auditor, 1st Series, Files 6606 and 6410 for 1822.
5. American State Papers- Military Affairs, Vol. IV, pp.146-148; Also HF NHP Reel 17, Vol. 3, pp.238-240. List is in Appendix No. 1.

According to Superintendent James Stubblefield's report, which was published by Congress in 1829, the following amounts were collected in rents on armory dwelling houses from 1823 to 1828:

Year	Stubblefield Report Amount Collected	No. of renters	By Armory Rent Rolls Amount Collected	Remarks
1823	$ 568.50	98	$ 1,015.25	1st, 2nd, & 3rd quarters
1824	1,331.50	135	1,472.50	all 4qrs. complete.
1825	1,316. 75	132	1,017.25	4th qr. missing.
1826	1,409.75	134	412.25	Rolls for 2nd, 3rd & 4th quar, missing.
1827	1,395.83	141	1,067.87	1st qr. roll missing.
1828	1,322.00	130	502.50	2nd & 4th qrs. missing
TOTAL	$ 7,344.33	-	$ 5,487.62	

During 1829, Stubblefield's last year in office, at least $ 552.37 was collected in rents(The rolls for the 1st and 2nd quarter of 1829 are missing.)[6] Including 1822 and 1829 figures, it is clear that at least $ 8,373.16 (using Stubblefield's 1823-28 totals) and probably about $ 9,900,* was collected in rent on the armory dwelling houses from 1822 to 1829.

Individual rents ranged from $ 3.00 to $ 24.00 a year.

* This figure is calculated at about $ 1,300 a year in rent from 1823 through 1829, plus the $ 596.50 collected in 1822.

SECTION C

Armory Rent Policy, 1830 - 1841:

In 1830 Mr. George Rust, Jr. toed command of the Harpers Ferry Armory and Col. Bomford issued the following instructions for Superintendent Rust's guidance:

"...It is proper that all such of the old dwelling houses belonging to the United States, as are fit for use and worthy of being preserved, should be put in good repair. Andyou are authorized to proceed to repair them provided the expense of such repairs shall not exceed the amount of rents received. Upon this subject I must refer you to the regulations on file at the Armory dated February 22, 1822...."[6]

On July 22, 1830 Col. Bomford further advised Mr. Rust:

"....It is believed that the amount hitherto charged as rent has been too low. By a report of the number and value of the buildings at the Armory, made in April 1827, it appears that the value of the dwelling houses belonging to the U. States, and occupied by workmen was estimated at about fifty thousand dollars. - The rent collected during the last five years, averages something less than $1400. per annum; being less than 3 per cent on the value. It is not desired that the rents of these houses should be sources of profits on the capital invested in them. But such rents should be exacted, as will be sufficient to keep the buildings in a good state of repair, and to renew them, when decayed; so that the capital invested inthem may remain unimpaired.

"I suppose that 5 per cent on the value of any house, should be the least amount to be required as rent. Probably a higher rate would be more correct. Upon this point however, you will be governed by your own judgement; fixing the rate at what may be considered liberal, and somewhat less than could be afforded by an individual. - The rule for fixing rents should be established before concluding the new agreements above mentioned (for renting a government dwelling house); in order that the amount, in each case, may be inserted in the agreement..."[7]

6. HF NHP Reel 14, Vol. 8. pp. 745-746.

7. HF NHP Reel 14, Vol. 8, p. 753.

In the same letter Col. Bomford also included a copy of the "Form for an agreement granting permission to workmen to occupy public Houses," which Rust was to review and then have every workman living in a Government House sign. The form read:

"This agreement made this__day of___ one thousand eight hundred & thirty____between A. B. Superintendent of the Harpers Ferr armory, in the service of the U. States of the one part, and C. D. of Harpers Ferry, of the other part Witnesseth:

"First: That the said Superintendent has, by this agreement, granted permission to said C. D. to occupy the (brick, stone or frame) dwelling house belonging to the U. States, situated in _____Street and designated on the list of public buildings at said Armory, as number __ it being understood, the said house is to be occupied by said C. D. and his family for the ordinary purposes of a dwelling house; and for no other. And that it shall be taken care of, and be usedinthe manner enjoined, by the established regulations of the Armory.

"Second: It is further agreed that the said Superintendent, or his successors in office, may at any time discontinue or annul this agreement; and upon due notice being given thereof, the said C. D. agrees to relinquish possession of said house & premises, and to remove therefrom with his family & effects,within ten days thereafter; in default of which, he binds himself to pay to the Armory Paymaster for the use of the United States (two) dollars per day, for each and every day that the said house may remain in the occupancy of himself. his family, or his effects, after the expiration of the aforesaid period of ten days, And it is to be understood, that at the expiration of the said period of ten days, the Supt. orany person by him appointed, shall have full authority to re-enter, and take entire possession of said house and premises; and to remove all persons and effects therefrom, without hinderance or molestation, and without any liability therefor, for damages or for suit of any kind, either in law or equity.

"Third: It is further agreed: that during the continuance of this agreement, the said C. D. shall pay for the use of said house, to the Armory paymaster a rent at the rate of ___dollars per annum, payable in due proportion, quarter yearly at the expiration of each quarter. And it is also agreed that he shall pay such further sum, as may at any time be necessary to repair or make good any injuries or damages which said house or premises may have sustained while in his occupancy from causes not beyond human control.

In testimony whereof the parties have hereunto affixed their respective signatures.

A. B. Supt.
Harpers Ferry Armory
C. D."[8]

Witness
E. F.

Col. Bomford also proposed to make the following amendment in the February 1827 Regulations for the Harpers Ferry Armory:

"21st. A reasonable rent will be charged, the amount of which will be specified in the permit.

"No addition will be made to any dwelling by its occupant; nor will any alteration or repairs be made, without permission of the Superintendent; any if any be made with his sanction, they shall give no claim to recompense from the U. States, nor from any individual. The occupants of all houses belonging to the U. States, are required to keep them clean and in good order and carefully to preserve them from injury or damage, as they will be held answerable for any such as may happen during their occupancy." 9

On September 25, 1830 Col. Bomford informed Superintendent Rust, in regards to rents:

"...It has been stated that public dwelling houses have been rented out, by those who are entitled to occupy them free of rent.-This has no doubt been done, under a belief in its entire propriety - Such practices, however are considred inexpedient; and should not be permitted. Dwellings are furnished by the U. States because of their necessity or convenience, to persons employed in the public service, and they are not to be regarded as perquisited. - Dwellings should be assigned to such persons as are authorized by regulations to occupy them; at the discretion of the Supt. - And if they donot choose to occupy them as dwellings for their own & their families residence; the dwellings should be appropriated to others in the public service, by the Supt.

Fuel also, is to be regarded in the same light. It should be issued in Kind, and in no other form; to those who are entitled to receive it; and to such an extent as may be required for actual use, not exceeding the limits prescribed in the regulations-. No connutation in money or otherwise, can be made for either quarters or fuel." 10

In November 1832 the Inspector of National Armories and Arsenals, Lt. Col. Talcott, inspected Harpers Ferry Armory and recommended:

8. HF NHP Reel 14, Vol. 8, pp. 761-762.
9. HF NHP Reel 14, Vol. 8, pp. 762-763.
10. HF NHP Reel 14, Vol. 8, p. 785.

"A moderate rent should be charged to the occupants (of Government Dwelling Houses) and the proceeds faithfully applied to keep the tenements in good repair. Many additions and repairs to the public dwelling houses have been made by the workmen who occupy them. All such expenses, so far as authorized by the Superintendent, should have been repaid out of the annual rents, but these are extremely low, the Gov't receiving only $2230 per annum for 127 tenements, averaging less than 20 dollars each, it appears probable that most of these expenditures were made without any expectation of repayment..." 11

Some idea of how the rent money was spent by the Harper's Ferry Armory during the 1830's can be formed from Master Armorer Benjamin Moor's letter of September 23, 1835 to Col. George Bomford, Chief of Ordnance. Moor wrote:

"Your letter of the 19th instant in relation to the amount of rents collected, &c. has been this day received. In reply thereto, I have to state, that the amount of rents received by the Paymaster in the 1st quarter of this year was $833.17; in the 2nd quarter of this year, the amount was $804.13, and the amount of the Rent Roll, for the 3rd quarter will be about the same amount. The amount of rents received by the Paymaster, has been passed into his account according to the instructions contained in the 27 par. of the Ord. Regulations.

"The rents have not been heretofore regarded as a specific fund for the purposes of repairing the public dwelling houses, but have been, when received by the Paymaster (the Collector), amalgated with the General Armory fund.

"No part of the rents, as a specific fund have been expended in the repair of the public dwelling houses.

"At the close of the present quarter, the Paymaster will probably receive rents to the amount of about eight hundred dollars.

"In conclusion I will remark, that the amount expended in the repairs of the public dwelling houses has been very inconsiderable and the sum expended in repairs, has been applied to a multitude of very minute objects." 12

11. Harpers Ferry NHP Photostat Collection, Vol. 1, p. 12.
12. HF NHP Reel 12, Vol. 1, pp.73-74.

Armory Rents Collected, 1830-35

During this period Captain John H. Hall's workmen rented a total of seven Armory Dwelling houses. The balance were occupied by men who worked at the U.S. Musket Factory and Arsenal.

Year	Rents According to Annual Reports to Congress	Rents Collected According to Armory Rent Rolls	Remarks
1830	$ 1,033.22 (1)	$ 535.42	120 renters. (1st and 4th quarters only) (7)
1831	2,226.58 (2)	2,113.69	118 to 121 rents (all 4 quarters) (8)
1832	2,490.87 (3)	1,922.32	124 renters (1st, 2nd and 4th quarters)(9)
1833	2,176.12 (4)	1,954.12	128 renters (1st, 3rd & 4th qrs.) (10)
1834	3,428.70 (5)	2,312.40	135 renters (2nd, 3rd, 4th qrs.) (11)
1835	3,160.56 (6)	2,359.43	136 renters. (1st, 3rd, 4th qrs.) (12)
Total:	$ 14,516.05	$ 11,197.38	

Included in these rents was the rent for the U.S. Ferry over the Shenandoah, for slaughter houses, and stables, as well as for residences. Rent from the Ferry amounted to $ 251.00 per year, rents from slaughter houses, and stables came to less than $ 100.00 per year.

The Annual Reports of the Ordnance Department to Congress indicate the rents collected from the workmen, totalling $ 14,516.05 for the years 1830 to 1835, were applied to the manufacture of arms- hence reducing the

1. National Archives R.G. 156-Entry 935, National Armory Acounts for 1830:
2. Serial No. 219, Document 170,p. 4.
3. Serial No. 235. Document 121,p.4.
4. Serial No., 257, Doc. 257,p.4.
5. Serial No. 275, Doc. 188,p.4.
6. Serial No. 292, Doc. 294, pp. 3,5. $ 146.25 of the total was paid by Hall's workmen.
7. R.G. 217- 14486, 14819. 1st series.
8. R.G. 217- 15,260, 15603, 15936, 16094.
9. R.G. 217- 16388, 16657, 17153.
10. R.G. 217- 17163, 17644(missing),17895.
11. R.G. 217- 18712, 19021, 19257.
12. R.G. 217- 19514, 200041, 20281. Lst series.

cost to the United States of producing arms by that amount! It thus appears that the rents were not being used to repair and maintain the armory dwelling houses during these years.

Armory Rents 1836- 1841:

In August 1841, as has been mentioned in Part I of this study, Armory painter John P. Kennedy painted numbers on each Armory Dwelling house that conformed to identification house number then being used in the Armory rent rolls. After 1841 it is thus possible to identify the dwelling in which each armorer was residing from 1841 to 1852.

Year	Rents According to Annual Reports to Congress	Rents collected according to Armory rent rolls	Remarks
1836	$ 3,074.66 (1)	$ 3,074.63	133 renters(7)
1837	3,435.20 (2)	3,405.95	149 renters (8)
1838	3,834.87 (3)	3,725.57	4th qr.missing. 178 renters. (9)
1839	3,667.04 (4) 1st & 2nd qrs only	3,569.76	4th qr. missing. 169 renter. (10)
1840	not reported (5)	6,716.42	includes 4th qr of 183 171 renters (11)
1841	not reported (6)	4,613.07	3rd qr,missing. 170 renters (12)
Total:	$ 14,011.77 **	$ 25,105.40	

1. Serial No. 304, Document 186,p.3.
2. Serial No. 331, Document 428. pp.3,4. $ 80.25 of total from Rifle Factory workers.
3. Serial No. 344, Document 2, pp396-399.
4. Serial No. 363, Document 2, pp. 95-101.
5. Serial No. 375 Document I pp.729-79 information not included.
6. Serial No. 395 Document No. 1, information not included.p.102-103.
7. R.G. 217- 2nd series 20761 and 20954; 3rd series 677 and761.
8. R.G. 217-3rd series, 951, 1423, 1716, 2092.
9. R. G. 217-3rd S., 2364, 2729, 3429.
10. R. G. 217-3rd S., 3695, 3971, 4246.
11. R. G. 217- 3rd S., 5252, 5624, 5784.
12. R.G. 217- 3rd S. 6195, 6465, 6718, 7045.

The $ 25,105.40 collected from 1836 to 1842 in rent from Armory workmen, as in 1830-35, was used to reduce the costs of manufacturing arms and not to repair or maintain thh Armory dwelling houses.

ARmory Rents Collected, 1842 to 1851:

The Board of Officers inspecting the Harper's Feery for the Secretary of War reported on February 22,1842 with regards to the "Dwelling Houses:"

> Most of the officers and armorers live in houses owned by the Government - the officers of the armory having their houses rent free, or, when they are not furnished with public houses, receiving a communtation of $ 60 per annum; the workmen who occupy public houses pay rents averaging from $ 60 to $__ per annum, according to size and condition of house.
>
> Many of these houses are scarcely habitable; many are out of repair, and few of them possess those conveniences of arrangement so essential to comfort and even health of the occupants.
>
> The board would therefore recommend that a portion of the rents received be applied to the erection of one or two dwelling-houses annually; the cost of these,with the repairs of the others, not to exceed the amount of rent received that year. These new buildings to be of a uniform plan, approved by the Secretary of War. (1)

No new armory dwelling houses were to be built for the use of average armory employees from 1842 to 1861, despite the recommendation of the Board of Officers. Any attempt to use rent moneys to make repairs to Armory Dwelling Houses also came to an end in 1849.

The annual estimate for the fiscal year ending June 30, 1851 stated:

> "By Act of 3d March 1849 (Pamphlet Laws, p. 105) all moneys received for rent of the public buildings have to be paid directly into the Treasury, from the 1st July 1849. Consequently for the present and next fiscal years no funds will be available..." 2

1. Congressional Serial No. 404, Document No. 207, p.45; Also Harpers Ferry NHP Photostat Collection, Vol. 2, pp.79-80.

2. HF NHP Reel 20, Vol. 7, p.685.

Henceforth money used for repair of Government Dwelling Houses was directly appropriated for that purpose by Congress.

In the floods of April 1843 and the fall of 1847, the rent money for one quarter, on each occasion, was remitted to the Armory workmen who lived in houses that suffered damages from the flood, after receiving the approval of the Secretary of War. [3]

Rents collected from Armory Dwelling Houses at Harper's Ferry, Virginia from 1842 to 1851

Year	Amount Collected	No. of Houses	No. of Renters	Remarks
1842	$ 4,897.45	169		
1843	5,497.04	169		
1844	6,188.87	168	169	renters occupied 165 houses
1845	6,068.96	162		
1846	5,229.74	162	159	159 renters occupied 155 houses
1847*	6,000.00			
1848*	6,000.00	158	161	7houses purchased and 2 built.
1849	6,217.98	148		
1850	6,032.25	141		
1851	5,402.49	124		Old houses being demolished,material sold
TOTAL:	$ 57,534.78	115 in 1852		Of 115 houses standing,53 were sold in Sept.1852.

3. Major Craig to Lt. Col. Talcott, April 20, 1843, Reel 23, v. 2 p. 131; Talcott to Sec. of War Porter, April 21, 1843, r. 19, v. 14, p. 1406; Talcott to Craig, May 5, 1843, R. 19, v. 2, p. 142; Major Symington to Talcott, December 28, 1847, R. 20, v. 1, p. 20-28; Talcott to Symington, December 31, 1847, R. 19, v. 4, p. 320-321.

SECTION E

Summary and Conclusions, Rents 1822 - 1851:

The total amount of rent collected from Armory owned dwelling houses, stores, offices, the Shenandoah ferry, and as ground rent for the sites of stables and slaughter houses from 1822 to December 31, 1851 was approximately as follows:

Years:	Amount Collected	No. of Houses
1822-1829	$ 9,900.00	87 in 1821, 113 in 1829.
1830-1835	14,516.05	About 132 in 1835.
1836 -1841	25,105.40	169 in 1841.
1842- 1851	57.534.78	148 in 1849; 124 in 1851.
TOTAL:	$ 107,056.23	

Rents on armory dwelling houses ranged from $ 3.00 to $ 24.00 a year from 1822 to 1830. There appears to have been rent increases in 1831, 1834, 1838, 1844, and 1848. In 1841 the rents on residences ranged from $ 6.00 to $ 60.00 per year; in 1844 the figures ranged from $ 7.00 to $ 69.00, and in 1848 the prices ranged from $ 12.00 to $ 70.00. By 1848 many of the old and hence cheaper dwellings had been demolished, so that most rents actually started at the $ 20.00 or more levels.

SECTION F

Rents Collected, 1852 to 1861:

During the 1940's the staff of the National Archives, Washington, D.C., destroyed the fiscal records of the Second Auditor of the Treasury Department, including the rent rolls, relating to the U.S. Armory at Harper's Ferry, Virginia, in order to save space. Information on rents collected 1852 to 1861, as well as other more important data, was thus lost forever.

The amount of rent money collected annually from 1852 to 1861, however, must have decreased rapidly and yearly after 1852 because of the sale and demolition of old armory dwelling houses. Of the 124 houses standing on January 1, 1852, 57 were sold in the fall of 1852[1] and eight other old quarters were demolished during the same year. Eleven more residences went down in 1853-54, so that the number of Armory-owned dwelling houses stood at only 48 on January 1, 1855. By 1859 and during the period 1859 to April 19,1861, the number was 33.[2] About 10 of the Government owned dwelling houses, from 1852 to 1861, were occupied by the superintendent, the paymaster, their clerks, and the inspectors and foremen free of rent, thus further reducing the amount of rent that would have been included on the destroyed rent rolls.

Of the 33 Armory-owned dwelling houses standing in 1861, only 24 survived the Civil War and were extant on July 27, 1865.

1. The 57 old dwelling houses were sold on August 31, September 1 and 2, 1852 at private and public auctions for a total of $ 38,942.00; 224 house lots also sold in 1852 brought in an additional $ 17,285.43,making a grand total of $ 56,227.43 realized from the 1852 sale of armory land and houses.

2. In 1859 the 33 old armory dwelling houses were given new identification numbers running from No. 1 to 33, inclusive.

APPENDIX NO. 1

Statement of rents collected on dwelling-houses belonging to the United States armory, Harper's Ferry, Virginia, and occupied by workmen employed in the said armory, from the year 1823 until the close of 1828; and the names of persons from whom collected.

Submitted by James Stubblefield, Superintendent of the Harper's Ferry Armory, February 1, 1829.

From: American State Papers- Military Affairs, Vol. IV, pp. 146 - 148.

Including an Index of Names of Renters, 1823 = 1828.

Statement of rents collected on dwelling-houses belonging to the United States armory, Harper's Ferry, Virginia, and occupied by workmen employed in the said armory, from the year 1823 until the close of 1828; and the names of persons from whom collected.

From whom collected.	1823.	1824.	1825.	1826.	1827.	1828.
Philip Hoffman	$8 00	$24 00	$6 00	$6 00	$24 00	$24 00
George Mallory	8 00	16 00	4 00	4 00	16 00	16 00
Edward Wager	12 00					
Charles C. Cameron	5 00	7 50	3 00			
Charles H. Mills	5 00	11 50	12 00	9 00		
William D. Moore	6 00	12 00	12 00	9 00		
John Shubridge	3 00	6 00	6 00	6 00	6 00	6 00
Hezekiah Butt	3 00	4 50	6 00	6 00	6 00	6 00
John Rodorock	4 00	4 00	2 00	10 50	6 00	6 00
James Green	6 00	9 00	9 00			
John Robinbaugh	10 00	20 00	20 00	20 00	20 00	20 00
John Mariatt	7 50	15 00	11 25	15 75	16 00	12 00
Michael Crowl	8 00	16 00	12 00	12 00	14 00	16 00
Ezekiel Stipes	3 00	8 00	8 00	8 00	8 00	8 00
Oswin Sturdy	2 00				8 00	8 00
John Donaldson	8 00	8 00	24 00	5 00		
Isaac Wood	8 00	20 00	20 00		18 75	22 50
Timothy Herrington	8 00	16 00	16 00	13 00	15 00	20 00
Jacob Ott	6 00	14 00	14 00	14 00	14 00	14 00
John Wiggington	3 00	6 00	6 00	6 00	12 50	4 00
Jacob Haines	8 00	12 00	16 00	15 00	15 00	4 00
Levi Hall	4 00	5 50	3 00	3 00	6 00	
Evan Lindsay	8 00					
Hiram Kerney	8 00	16 00	12 00			
William Ferrells	6 00	12 00	12 00	6 00		
Absolom Vanvacter	6 00	15 00	12 00	9 00	9 00	3 00
Samuel Thropp	8 00	16 00	12 00	20 00	12 00	8 00
William Green	8 00	20 00	5 00			
William Mallory	8 00	5 00	2 00	15 00	6 00	9 00
John Coons	6 00	12 00				
Joseph Barnes	1 00		14 00	20 00	18 00	15 00
William Simpson	4 00	6 00	2 00			
William Nunamaker	3 00	1 50		20 00	18 00	15 00
Peter Hoffman	4 50	12 00	3 00	6 00	9 00	18 00
Henry Stipes	3 00	12 00	4 00			
Reuben Stipes	3 00	2 00	6 00	10 00	4 00	
Daniel Little	5 00					
Alexander Wintzell	6 00					
John Holt	4 00	10 00	10 00	10 00	7 50	12 50
John Claspey	5 00	7 50	10 00	7 50		
William McClure	8 00	6 00	4 00	6 00	4 00	8 00
William Smallwood	6 00	12 00	6 00	12 00	16 00	12 00
James Reily	6 00	9 00	12 00	12 00	12 00	12 00
Charles Wintersmith	8 00	18 00	15 00	50 00	20 00	20 00
George Zoger	8 00	15 00	15 00	20 00	8 00	
John Baylis	4 00	2 00	11 00	2 00		
Thomas Hall	4 00					
William Mockbee	6 00	12 00	12 00	9 00	10 00	6 00
Daniel Hinkles	10 00	20 00	20 00	10 00		
Frederick Reily	6 00	15 00	12 00	9 00	10 00	8 00
William Chambers	3 00	6 00	8 00		9 00	9 00
Nathan Benton	4 00	8 00	8 00	8 00	8 00	8 00
Joshua Cox	4 00	8 00	8 00	8 00	6 00	8 00
Thomas Dakin	6 00	12 00	12 00	12 00	12 00	12 00
John Sickofuse	5 00	2 50				
William Adams	5 00	12 00	12 00	12 00	12 00	9 00
Richard King	4 00	18 00	13 50	18 00	13 50	9 00
John Baden	2 00	8 00	6 00	8 00		
Nathan Turk	6 00	13 00	12 00	16 00	16 00	8 00
Elisha Larkin	2 50	10 50	16 00	12 00	10 00	
Samuel Avis	10 00	14 00	12 00	9 00	12 00	12 00
William Gannon	8 00	12 00	12 00	20 00	12 00	12 00
Daniel Johnston	10 00	20 00	20 00	20 00	15 00	20 00
Ebenezer Cox	10 00	10 00	5 00			
Orson Bestor	10 00	15 00				
James Steadman	4 00					
Anthony Beisterling	6 00	16 00	12 00	12 00	12 00	12 00
James Coates	5 00	17 00	15 00	16 00	12 00	15 00
Michael Gompp	8 00	12 00	12 00	12 00	12 00	12 00
Daniel Cramer	8 00	16 00	16 00	16 00	16 00	4 00
William Sappington	8 00	13 00	15 00	18 00	13 00	15 00
Nathan Yeamans	8 00	12 00	16 00	16 00	16 00	8 00
William Phelan	4 00	10 00	8 00	3 00	6 00	6 00
George Little	6 00	12 00	16 00	8 00	12 00	
Roger Jones	3 00	4 00				
James Pryor	8 00	12 00	12 00			

From whom collected.	1823.	1824.	1825.	1826.	1827.	1828.
M. Britenbang	$8 00	16 00	$16 00	$16 00	$16 00	$16 00
Thomas Earnshaw	4 00					
William Read	8 00	16 00	16 00	12 00		
Frederick Stephenson	4 00	2 00				
David Claspey	4 00	4 00	4 00	2 00	4 00	4 00
Asahel Davis	4 00	12 50	2 50			
John Crutchly	3 00	4 50	3 00			
John Best	3 00	6 00	7 50	4 50		3 00
John H. Hall	15 00	37 50	7 50			
Nathaniel French	8 00	20 00	16 00	16 00	12 00	12 00
Pelatiah Thompson	4 00	8 00	16 00	12 00	12 00	20 00
William Burke	4 00	8 00	4 00	16 00	18 00	20 00
Jacob Coons	6 00	12 00	6 00	3 00		
Jeffrey Carlisle	2 00	5 00	4 00	4 00	4 00	4 00
Thomas Spriggs	2 00	5 00	4 00	2 00	4 00	4 00
George Compton	3 00	7 50	5 50	3 00	6 00	7 50
Ignatius McIlee	3 00					
Michael Cooke	6 00	6 00	9 00		2 00	
Joseph Hoffman		18 00	3 00	3 00	12 00	
Nahum W. Patch		12 00				
James Fisher	8 00	16 00	16 00	16 00	16 00	12 00
Michael Derry		2 00				9 00
Levi Steadman		4 50	6 00	6 00	7 50	9 00
Henry Miller		12 00	3 00	5 00	20 00	20 00
Robert Dirke		16 00	17 00	20 00	20 00	20 00
Samuel Hobbs		16 00	12 00	12 00	16 00	16 00
John Mallory		4 00				
Benjamin Wintzell		12 00	6 00	18 00	12 00	12 00
James Hughes		7 50				
Charles Staley		20 00	20 00			
David Adams		6 00	4 50	6 00	6 00	6 00
Martin Hartman		8 00	6 00	8 00	8 00	6 00
Thomas Mallory		12 00	9 00	5 00	8 00	6 00
Samuel McDowell		16 00	16 00	16 00		
Richard Martin		16 00				
Jacob Coons, 3d		1 50	3 00			
Christopher Kreps		9 00	12 00	12 00	12 00	12 00
Daniel Border		24 00	24 00	6 00		
Meshac Kirby		12 00	12 00	9 00	12 00	18 00
Joshua Reily		7 50	10 00	7 50	7 50	7 50
Edmund Barber		3 00				
Michael Milhorn		15 00	16 00	12 00	16 00	16 00
Thomas Stipes	3 00	16 00	16 00	12 00	12 00	8 00
Jacob Coons, jr				3 00		
George Rowles		5 00				
Timothy Steadman		1 50	3 00	6 00	6 00	6 00
John Tally		9 00	10 50	6 00		
Alva Keep, 2		9 00	12 00	6 00		
John G. Unseld		6 00	4 00	12 00		
M. F. A. Pollock		6 00	4 00	4 00	1 00	
Alexander Nunamaker		4 50	6 00	1 50	3 00	4 50
John Garrett		16 00				
James Thropp		9 00	12 00	12 00	12 00	12 00
Joseph Bayliss		2 00				
Jacob Engles		4 00	6 00	6 00	8 00	8 00
George Hawkin		3 00		18 00	6 00	6 00
Abraham Rodrock		1 50	6 00	4 50	6 00	6 00
William Crusin		5 00	4 50	6 00	6 00	6 00
Singleton Chambers		4 00	5 00	18 00	10 00	8 00
Charles Fouke		10 00	10 00	20 00		
James Green		3 00				
George Bryson		10 00	20 00	25 00		
Jacob Board		4 50	4 50			
Levi Hall		5 00	9 00	3 00	3 00	
Samuel Cox		10 00	10 00	20 00	20 00	15 00
Jonah M. Tompkins	4 00	8 00	6 00			
Archibald McClelland		6 00	12 00	12 00	12 00	
John Spangler		4 50		1 50	6 00	6 00
James Merrick		18 00	12 00	9 00	12 00	12 00
Thornton Warner		1 00				
Thomas Russell		4 00	16 00	12 00	12 00	20 00
Francis Leisbe		4 00	8 00	8 00	2 00	2 00
John Claspey		2 50				
Hiram Pryor		4 00				
John Reiley		3 00		6 00	2 00	
Joseph Reiley		2 50				
John Piles			12 00	12 00	5 50	23 00
Joseph Martin			4 00			
David Hoffman			6 00			

Statement of rents, &c.—Continued.

From whom collected.	1823.	1824.	1825.	1826.	1827.	1828.
Raleigh Coons			$3 00			
Shadrack Penn			9 00	$10 00	$8 00	$4 00
Amasa W. Mars			15 00	16 00	16 00	16 00
Benjamin Stipes			12 00	16 00	16 00	12 00
John Chambers			6 00	9 00	8 33	12 00
John Baylis			2 00	6 00	8 00	8 00
Jacob Shough			5 00	9 00		
Daniel Crawford			3 00	6 00	6 00	6 00
Joseph Griffith			6 00	12 00	3 00	
Zadock Butt			6 00	12 00	8 00	8 00
Robert Blanchard			8 00	12 00	12 00	12 00
Amos Sigler			8 00	12 00	12 00	12 00
John Thropp			3 00			
Jeremiah Stevens			4 00	8 00	6 00	10 00
Philip Cramer			4 00	8 00		
Ad. Rhulman				12 00	12 00	4 00
Richard A. Waters				15 00	11 25	6 00
Richard Crusia				6 00		
Edmond Chambers				7 00	12 00	12 00
Zachariah Garnes				7 00	4 00	8 00
Mathias Spangler				10 00	8 00	8 00
Charles F. Clewell				8 00	8 00	8 00
Stedson Bisbee				20 00	12 00	
John Weaning				15 00	12 00	3 00
Joseph Davis				6 00		
John Best				3 00	6 00	6 00
Daniel McFaden				15 00	18 00	18 00
William Bateman				3 00	12 00	12 00
Paul Washburn					13 50	
George Nunamaker				3 00	3 00	
James Shubridge					12 00	6 00
George Engles					8 00	8 00
Thomas Steadman					8 00	15 00
Joseph Spencer				1 50	3 00	
Horatio Hobbs					9 00	3 00
John Cable					6 00	4 50
George H. Butler					1 00	
James Clarke				5 00	20 00	20 00
John Avis					2 00	
Jacob Foreman					12 00	16 00
John Chapman					4 00	3 00
James Near					9 00	
Allen McBee				4 50	4 00	4 00
Jacob Mong					5 00	
Abraham Berlin					6 00	1 50
Isaac Jackson					2 00	4 00
Joseph Taylor					1 50	
Hiram McBride					2 00	4 00
William Spencer					4 50	4 50
Ferdinand Stephenson					12 00	21 00
Samuel Kilham					6 00	12 00
William Yeamans				3 00	4 00	14 00
Washington Busey					8 00	16 00
Eli B. Cogsill					2 00	4 00
Edwin Tucker					6 00	12 00
George Brun					3 00	
John Bowers					2 50	7 50
Berryman Brun						12 00
James Cooke						6 00
Joseph Wright						1 00
Erasmus Bell						3 00
John Hall						2 00
Frederick Houk						2 50
Thomas Melvin						4 00
Israel Parsons						5 00
	$553 50	$1,201 50	1,318 73	1,409 73	$1,225 83	$1,222 00

I hereby certify the above statement to be correct according to its purpose.

FEBRUARY 1, 1829.

JAMES STUBBLEFIELD.

INDEX OF RENTERS, 1823 - 1828

1 = one entry for year
2 = two entries for same year

Name of Renter	1823	1824	1825	1826	1827	1828
1. Adams, David		2	2	1	1	1
2. Adams, William	1	1	1	1	1	1
3. Avis, John					1	
4. Avis, Samuel	1	1	1	1	1	1
5. Baden, John	1	1	1	1		
6. Barber, Edmund		1				
7. Barnes, Joseph	1		1	1	1	1
8. Bateman, William				1	1	1
9. Baylis, John	1	1	2	2	1	1
10. Baylis, Joseph		1				
11. Bell, Erasmus						1
12. Belsterling, Anthony	1	1	1	1	1	1
13. Benton, Nathan	1	1	1	1	1	1
14. Berlin, Abraham					1	1
15. Best, John	1	1	1	2	1	2
16. Bestor, Orson	1	1				
17. Bisbee, Stedson				1	1	
18. Blanchard, Robert			1	1	1	1
19. Board, Jacob		1	1			
20. Border, Daniel		1	1	1		
21. Bowers, John					1	1
22. Britenbang, M.	1	1	1	1	1	1
23 Brua, Berry						1
24. Brua, George					1	
25. Bryson, George		1	1	1		
26. Burke, William	1	1	1	1	1	1
27. Busey, Washington					1	1
28. Butler, George H.					1	
29. Butt, Hezekial	1	1	1	1	1	1
30 Butt, Zadock			1	1	1	1
31. Cable, John					1	1
32, Cameron, Charles C.	1	1	1			
33. Carlisle, Jeffery	1	1	1	1	1	1
34. Chambers, Edmond				1	1	1
35. Chambers, John			1	1	1	1
36. Chambers, Singleton		1	1	1	1	1
37. Chambers, William					1	1
38. Chapman, John					1	1
39. Claspey, David	1	1	1	1	1	1
40. Clarke, James				1	1	1
41. Claspey, John	1	1	1	1		
42. Clewell, Charles F.,				1	1	1
43. Coates, James	1	1	1	1	1	1
44. Cogsill, Eli B.					1	1
45. Compton, George	1	1	1	1	1	1
46. Cooke, James						1

INDEX OF RENTERS, 1823 - 1828

1 = one entry for year
2 = two entries for same year

Name of Renter	1823	1824	1825	1826	1827	1828
47.Cooke, Michael	1	1	1		1	
48. Coons, Jacob,3rd		1	1			
49. Coons, Jacob,Jr.				2		
50. Coons, Jacob	1	1	1	1	1	1
51. Coons, John	1	1				
52. Coons, Raleigh			1			
53. Cox, Ebenezer	1	1	1			
54. Cox Joshua	1	1	1	1	1	1
55. Cox, Samuel		1	1	1	1	1
56. Cranner,Daniel	1	1	1	1	1	1
57. Crowl, Michael	1	1	1	1	1	1
58. Cramer, Philip			1	1		
59. Crawford,Daniel			1	1	1	1
60. Crusin, Richard				1		
61. Crusin,William		1	1	1	1	1
62. Crutchly, John	1	1	1			
63. Dakin, Thomas	1	1	1	1	1	1
64. Davis, Asahel	1	1	1			
65. Davis, Joseph				1		
66. Derry, Michael		1				1
67. Dirke, Robert		1	1	1	1	1
68.Donaldson,John	1	1	1	1		
69. Earnshaw,Thomas	1					
70. Engles, George					1	1
71. Engles, Jacob		1	1	1	1	1
72. Ferrells,Wm.	1	1	1	1		
73. Fisher, James	1	1	1	1	1	1
74. Foreman, Jacob					1	1
75. Fouke, Charles		1	1	1		
76.French,Nathaniel	1	1	1	1	1	1
77. Gannon, William	1	1	1	1	1	1
78. Garnes,Zachariah				1	1	1
79. Garrett, John		1				
80. Gompf, Michael	1	1	1	1	1	1
81. Green, James	1	1	1			
82. Green, William	1	1	1			
83. Griffith,Joseph			1	1	1	
84. Haines,Jacob	1	1	1	1	1	1
85. Hall, John						1
86. Hall, John H.	1	1	1			
87. Hall, Levi	1	1	1	1	1	
88. Hall, Thomas	1					
89. Hartman, Martin	1	1	1	1	1	1
90. Hawkins, George		1		1	1	1
91.Herrington, Timothy	1	1	1	1	1	1
92. Hinkles, Daniel	1	1	1	1		

INDEX OF RENTERS, 1823 - 1828

1 = one entry for year
2 = two entries for same year

Name of Renter	1823	1824	1825	1826	1827	1828
93.Hobbs, Horatio					1	1
94. Hobbs, Samuel		1	1	1	1	1
95. Hoffman, David			1			
96. Hoffman, Joseph		1	1	1	1	
97. Hoffman, Peter	1	1	1	1	1	1
98. Hoffman, Philip	1	1	1	1	1	1
99. Holt, John	1	1	1	1	1	1
100. Houk, Frederick						1
101. Hughes, James		1				
102. Jackson, Isaac					1	1
103. Johnson, Daniel	1	1	1	1	1	1
104. Jones, Roger	1	1				
105. Keep, Alva		1	1	1		
106. Kerney, Hiram	1	1	1			
107. Kilham,Samuel					1	1
108.Lindsay, Evan	1					
109. King, Richard	1	1	1	1	1	1
110.Kirby, Meshac		1	1	1	1	1
111. Kreps,Christopher		1	1	1	1	1
112. Larkin, Elisha	1	1	1	1	1	
113. Leisha, Francis		1	1	1	1	1
114.Little, Daniel	1					
115. Little, George	1	1				
116. McBee, Allen				1	1	1
117. McBride, Hiram					1	1
118. McClelland, Archibald		1	1	1	1	
119. McClure, Wm.	1	1	1	1	1	1
120. McDowell, Samuel		1	1	1		
121. McFaden, Daniel				1	1	1
122. McItee, Ignatius	1					
123. Mallory, George	1	1	1	1	1	1
124. Mallory, John		1				
125. Mallory, Thomas		1	1	1	1	1
126. Mallory, Wm.	1	1	1	1	1	1
127. Marlatt, John	1	1	1	1	1	1
128. Mars, Amasa W.			1	1	1	1
129. Martin, Joseph			1			
130. Martin, Richard		1				
131. Melvin, Thomas						1
132. Merrick, James		1	1	1	1	1
133. Milhorn, Michael		1	1	1	1	1
134. Miller, Henry		1	1	1	1	1
135. Mills,Charles H.	1	1	1	1		
136Mockbee, William	1	1	1	1	1	1
137. Mong, Jacob					1	
138. Moore, Wm. D.	1	1	1	1		
139. Near, James					1	

INDEX OF RENTERS, 1823 - 1828

1 = one entry for year
2 = two entries for same year

Name of Renter	1823	1824	1825	1826	1827	1828
140. Nunnamker, Alexander		1	1	1	1	1
141.Nunnamaker,George				1	1	
142. Nunnamaker, Wm.	1	1		1	1	1
143. Ott, Jacob	1	1	1	1	1	1
144. Parsons,Israel						1
145.Penn, Shadrack			1	1	1	1
146. Phelam, William	1	1	1	1	1	1
147. Piles, John			1	1	1	1
148. Pollock,M.F.A.		1	1	1	1	
149. Pryor, Hiram		1				
150. Pryor, James	1	1	1			
151. Putch, Nahum W.	1					
152. Read, William	1	1	1	1		
153. Reily,Frrederick	1	1	1	1	1	1
154. Reily, James	1	1	1	1	1	1
155. Reily, John		1		1	1	
156. Reily, Joseph		1				
157. Reily, Joshua		1	1	1	1	1
158. Rhlman, Ad.				1	1	1
159. Robinbaugh,John	1	1	1	1	1	1
160. Rodrock,Abraham		1	1	1	1	1
161. Rodorock,John	1	1	1	1	1	1
162. Rowles, George		1				
163. Russell, Thomas		1	1	1	1	1
164.Sappinton, Wm.	1	1	1	1	1	1
165 Shough, Jacob			1	1		
166. Shubridge, James					1	1
167. Shubridge, John	1	1	1	1	1	1
168.Sickofuse,John	1	1				
169. Sigler, Amos			1	1	1	1
170. Simpson, Wm.	1	1	1			
171. Smallwood, Wm.	1	1	1	1	1	1
172. Spangler, John		1		1	1	1
173. Spangler, Mathias				1	1	1
174. Spencer, Joseph				1	1	
175. Spencer, Wm.					1	1
176. Spriggs, Thomas	1	1	1	1	1	1
177. Staley,Charles		1	1			
178. Steadman, James	1					
179. Steadman, Levi		1	1	1	1	1
180. Steadman, Thomas					1	1
181. Steadman, Timothy		1	1	1	1	1
182. Stephenson, Frederick	1	1				
183. Stephenson, Fredinand					1	1

INDEX OF RENTERS, 1823 - 1828

1 = one entry for year
2 = two entries for same year

Name of Renter	1823	1824	1825	1826	1827	1828
184.Stevens, Jeremiah			1	1	1	1
185. Stipes, Benjamin			1	1	1	1
186.Stipes,Ezekiel	1	1	1	1	1	1
187.Stipes, Henry	1	1	1			
188. Stipes, Reuben	1	1	1	1	1	
189.Stipes, Thomas	1					
190. Sturdy, Oswin	1				1	1
191. Tally, John		1	1	1		
192. Taylor, Joseph					1	
193. Thompson, Pelathiah	1	1	1	1	1	1
194. Thropp, James		1	1	1	1	1
195. Thropp, John			1			
196.Thropp, Samuel	1	1	1	1	1	1
197.Tompkins, Jonah H,	1	1	1			
198. Tucker, Edwin					1	1
199. Turk, Nathan	1	1	1	1	1	1
200. Unseld, John C.		1	1	1		
201. VanVactor, Absolom	1	1	1	1	1	1
202. Wager, Edward	1					
203. Warner, Thornton		1				
204. Washburn, Paul					1	
205. Waters, Richard A.				1	1	1
206. Weaning, John				1	1	1
207. Wiggington,John	1	1	1	1	1	1
208. Wintersmith, Charles	1	1	1	1	1	1
209. Wintzell,Alexander	1					
210. Wintzell,Benjamin		1	1	1	1	1
211. Wood, Isaac	1	1	1	1	1	1
212. Wright, Joseph						1
213. Yeaman, Nathan	1	1	1	1	1	1
214. Yeaman, Wm.				1	1	1
215. Zoger, George	1	1	1	1	1	1
GRAND TOTAL OF RENTERS PER YEAR	98	135	132	134	141	130

APPENDIX NO. 2

Location of extant Harper's Ferry Armory Rent Rolls from 1822 to 1851 in the National Archives, Washington, D.C., Record Group 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury, 1st, 2nd, and 3rd Series (Records for 1852-1861 no longer extant), together with the total of rents collected quarterly.

Note: Rent rolls from 1822 to 1840 carry the name of the renter and the amount of the rent due and paid, or owed.

Rent rolls from 1841 to 1851 carry the same data as above, plus a House Identification Number that can be tied to a definite house lot. Dwellings carried the same house number to identify it in the rent rolls from 1841 to 1859.

HARPER'S FERRY ARMORY RENT ROLLS, 1822 - 1851

RECORD GROUP 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury Department, Washington, D.C., SERIES NO. 1st Series.

File No.	Renters	Rent Collected	File No.	Renters	Rent Collected
1st Quarter 6274		missing	1st Q. 9057	108	$ 348.75
2nd Quarter 6274		missing	2nd Q. 9057	105	352.25
3rd Quarter 6410	94	$ 305.25	3rd Q. 9310	98	316.25
4th Quarter 6606		291.25	4th Q. 9621		missing
1822 Total: (1)	1822	596.50	(4) 1825 Total:	1825	$ 1,017.25
1st Q. 6909		330.25	1st Q. 9851	107	412.25
2nd Q. 7207	99	309.00	2nd Q. 10053		missing
3rd Q. 7356	124	376.00	3rd Q. 10559		missing
4th Q. 7624			4th.Q. 10604		missing
1823 Total: (2)	1823	1,015.25	(5) 1826 Total:	1826	$ 412.25
1st Q. 7899	108	399.75	1st.Q. 10876		missing
2nd Q. 8108	90	288.25	2nd Q. 11127	115	365.00
3rd Q. 8371	110	465.25	3rd Q. 11127		350.37
4th Q. 8693	95	319.25	4th Q. 12013		352.50
1824 Total: (3)	1824	$ 1,472.50	(6)1827 Total	1827	$ 1,067.87

HARPER'S FERRY ARMORY RENT ROLLS, 1822 - 1851

RECORD GROUP 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury Department, Washington, D.C., SERIES NO. 1st Series.

File No.	Renters	Rent Collected	File No.	Renters	Rent Collected
1st Quarter 12013		$ 388.00	1st Q. 15260	118	$ 395.08
2nd Quarter missing			2nd Q. 15603	118	402.08
3rd Quarter 12579		114.50	3rd Q. 15936	119	692.31
4th Quarter 12579			4th Q. 16094	121	624.22
1828 Total: (1)	1828	$ 1,322.00	(4)1831 Total:	1831	$ 2,113.69
1st Q. 12908		Missing	1st Q. 16388	123	$ 472.63
2nd Q. 13478		Missing	2nd Q. 16657	124	587.64
3rd Q. 13626		$ 293.03	3rd Q.		621.65
4th Q. 13750		$ 259.34	4th Q. 17153	126	862.05
1829 Total: (2)	1829	$ 552.37	(5) 1832 Total:	1832	$ 2,543.97
1st Q. 14486		$ 278.09	1st Q. 17163	128	$ 984.44
2nd Q.		Missing	2nd Q. 17644		missing
3rd Q. 14723		Missing	3rd Q. 17895	128	706.83
4th Q. 14819	120	$ 257.33	4th Q. 17895		262.85
1830 Total: (3)	1830	$ 535.42	(6)1833 Total	1833	1,954.12

HARPER'S FERRY ARMORY RENT ROLLS, 1822 - 1851

RECORD GROUP 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury Department, Washington, D.C., SERIES NO. 1st and 2nd Series.

File No.	Renters	Rent Collected	File No.	Renters	Rent Collected
1st Quarter		Missing	1st Q. 951	135	$ 674.91
2nd Quarter 18712	136	$ 714.40	2nd Q. 1423	147	794.10
3rd Quarter 19021	136	732.32	3rd Q. 1716	148	910.80
4th Quarter 19257	137	866.08	4th Q. 2092	149	1,026.14
1834 Total: (1)	1834	$ 2,312.80	(4) 1837 Total:	1837	$ 3,405.95
1st Q. 19514	136	$ 833.17	1st Q. 2364	172	$ 1,321.73
2nd Q. missing		Missing	2nd Q. 2364	173	1,274.28
3rd Q. 20041	136	727.60	3rd Q. 2729	171	1,156.56
4th Q. 20281	136	798.66	4th.Q. 3429		Missing
1835 Total: (2)	1835	$ 2,359.43	(5) 1838 Total:	1838	$ 3,725.57
1st Q. 20761	133	$ 809.47	1st.Q. 3695	169	$ 1,165.75
2nd Q. 20954	133	767.73	2nd Q. 3695	169	1,208.26
3rd Q.2nd series 677	133	745.98	3rd Q. 3971	168	1,195.75
4th Q. 761	133	751.45	4th Q. 4246		
1836 Total: (3)	1836	$ 3,074.63	(6) 1839 Total	1839	$ 3,569.76

HARPER'S FERRY ARMORY RENT ROLLS, 1822 - 1851

RECORD GROUP 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury Department, Washington, D.C., SERIES NO. 2nd and 3rd Series.

File No.	Renters	Rent Collected	File No.	Renters	Rent Collected
1st Quarter 5,252	168	$ 2.580.41	1st Q. 8190		$ 1,636.49
2nd Quarter 5252	171	1,377.03	2nd Q. 8190		954.42
3rd Quarter 5624	168	1,312.49	3rd Q. 440 3rd	series	1,195.38
4th Quarter 5785	170	1,446.58	4th Q. 630	169 houses	1,610.75
1840 Total: (1)	1840	$ 6,716.51	(4) 1843 Total:	1843	$ 5,497.04
1st Q. 6195	171 renters 169 houses	$ 1,522.99	1st Q. 970	3rd Series	1,623.11
2nd Q. 6465	170	1,512.34	2nd Q. 1165		1,624.10
3rd Q. 6718		Missing	3rd Q. 1613		1,311.73
4th Q. 7045	170	1,577.74	4th.Q. 1844	169 houses to 169 fam.	1,629.94
1841 Total: (2)	1841	$ 4,613.07	(5) 1844 Total:	1844	$ 6,188.87
1st Q. 7654		$ 1348.34	1st.Q. 2213		1,634.83
2nd Q. 7654		1,351.30	2nd Q. 2474		1,552.73
3rd Q. 8011		1,390.19	3rd Q. 2841		1,418.38
4th Q. 8011	(7)	807.72	4th Q. 3122		1,463.02
1842 Total: (3)	1842	$ 4,897.55	(6) 1845 Total	1845	$ 6,068.96

(7) plus $ 355.04 credited to the 1st quarter of 1843- see file 8,190.

HARPER'S FERRY ARMORY RENT ROLLS, 1822 - 1851

RECORD GROUP 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury Department, Washington, D.C., SERIES NO. 3rd Series.

File No.	Renters	Rent Collected	File No.	Renters	Rent Collected
1st Quarter 3858		$ 1,446.55	1st Q. 9093	160 houses	$ 1,616.79
2nd Quarter 4403		1,568.99	2nd Q. 9307		1,612.33
3rd Quarter 4837	1846	1,356.83	3rd Q. 9895		1,460.60
4th Quarter 4967	162 houses to 166 families	1,357.37	4th Q. 10276		1,528.26
1846 Total: (1)	Ferry, 2 stables,	$ 5,229.74	(4) 1849 Total:	1849	$ 6,217.98
1st Q. 4967		$ 1,332.50	1st Q. 10673		$ 1,653.47
2nd Q. 5623		1,394.19	2nd Q. 11000		1,477.69
3rd Q. missing		missing	3rd Q. 12169		1,468.59
4th Q. missing	1847	missing	4th.Q. 12169	141 houses	1,432.00
1847 Total: (2)	$ 2,726.69	* ($ 6,000.00)	(5) 1850 Total:	1850	$ 6,032.25
1st Q. missing 8737		$ missing	1st.Q. 12		$ 1,393.57
2nd Q. 8737 missing		missing	2nd Q. 12680		1,350.75
3rd Q. 8737 missing		missing	3rd Q. 12680		1,359.55
4th Q. 8737 missing	160 houses	missing	4th Q. 13017	124 houses	1,298.62
1848 Total: (3)	1848	($ 6,000.00)*	(6) 1851 Total	1851	$ 5,402.49

* Estimated

HARPER'S FERRY ARMORY RENT ROLLS, 1852 - 1851

RECORD GROUP 217- Records of the General Accounting Office, Records of the Second Auditor of the Treasury Department, Washington, D.C., SERIES NO.

File No.	Renters	Rent Collected	File No.	Renters	Rent Collected
1st Quarter	125		1st Q.	48 houses	
2nd Quarter			2nd Q.		
3rd Quarter	56 houses sold		3rd Q.		
4th Quarter	62 houses	left	4th Q.		
Total: (1)	1852		(4) Total:	1855	
1st Q.			1st Q.		
2nd Q.			2nd Q.		
3rd Q.			3rd Q.		
4th Q.	60 houses		4th.Q.		
Total: (2)	1853		(5) Total:	1856	
1st Q.			1st.Q.		
2nd Q.			2nd Q.		
3rd Q.			3rd Q.		
4th Q.	48 houses		4th Q.	33 houses	1859-61.
Total: (3)	1854		(6) Total	1857	

Rent Rolls for the Harpers Ferry Armory for the period January 1,1852 to April 19, 1861 were destroyed by the staff of the National Archives during the 1940's in order to save space.

APPENDIX 3

Schedule A prepared by Major John Symington,
Superintendent,U.S. Armory at Harper's Ferry,Virginia, December 12,1844

From Congressional Serial No. 464, Document No. 43, pp. 9 - 12

Schedule of lot, and improvements thereon, owned by private individuals, adjoining the public buildings at the Harper's Ferry armory, with description of the improvements on each lot, and the price for which the whole can be purchased - these lot and parts of lots being included with the blue lines marked on the accompany plat(See Map No.4).

"Map of the Relative Position of the Reserved Land & Public Work at Harpers Ferry, Va. - 1844."

See Map No. 20, page 226

SCHEDULE A

Schedule of lots and improvements thereon, as held by private individuals, adjoining the public buildings at the Harper's Ferry armory, with description of the improvements on each lot, and the price for which the whole can be purchased—these lots being included within the yellow lines marked on the accompanying plat.

Number of lot.	Owner of ground.	Owner of buildings.	Description of the buildings, &c.	Price of ground.	Price of buildings.	Total.
11	Mrs. Swayne -	Richard D. Doran	Double brick building, 40 by 40 feet, 2 stories high, with finished garret and shingled roof; cellar underneath: an open gallery in front; back buildings of brick, 2 stories; lower story occupied as stores, upper story and garret as dwellings - - - - - - - -	$2,266	$4,000	$6,266
Part of 12	G. B. Wager -	Richard D. Doran	Two-story brick building, with finished garret and cellar, 35 by 20 feet, covered with shingles; lower story occupied part as a drug and general variety store, and part as a shoemaker's shop: the upper story, including garret, as dwellings - - - - - - - -	1,600	1,600	3,200
Part of 12	Henry Yost -	Henry Yost -	Two-story brick building, continuation of the building above-described, and under same roof, 25 by 50 feet: lower story occupied as a general variety store, upper story as a dwelling - - - - -	-	-	5,[illegible]
13	Mrs. Swayne -	- -	A large wooden stable, 60 by 20 feet, and loft above - - - -	-	-	[illegible]
17	Mrs. Swayne -	J. G. Wilson -	A small wooden house, 16 by 14 feet, 1 story - - - -	1[illegible]2	2[illegible]	[illegible]
18	G. B. Wager -	Samuel Lover -	On High street a 2-story brick house, 30 by 22 feet, covered with shingles, and cellar underneath; on the alley a stable for wood, with loft for hay	1[illegible]2	1[illegible]	[illegible]
19	G. B. Wager -	Charles Button -	On High street a 2-story brick house, 30 by 22 feet, covered with shingles, and cellar underneath; a porch in front and rear; on the alley a wooden stable, with hay loft 20 by 18 feet - - - - -	725	1,700	2,425
20	G. B. Wager -	Philip Coons -	On High street a 2-story brick house, with basement, and cellar under basement, 31 by 23½ feet, covered with slate, well finished; on the alley a 2-story stone house, 26 by 22 feet, covered with shingles - - -	725	1,700	2,425
21	G. B. Wager -	G. B. Wager -	On High street a 2-story stone house, with basement, 30 by 20 feet, [illegible] with slate, with back buildings, all well finished; on the alley a stone stable 26 by 20 feet, with hay loft; also, a stone smoke-house 10 by 9 feet	725	2,000	2,725
22	G. B. Wager -	William Megraw	On High street a 2-story stone house, with basement, 20 by 20 feet, covered with slate, well finished, and a stone corn-house 17 by 9 feet; on the alley a wooden stable 27 by 20 feet, with hay loft - - -	750	2,000	2,750
[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	[illegible]	2,950

Schedule of lots and parts of lots, &c.—Continued.

Number of lot.	Owner of ground.	Owner of buildings.	Description of the buildings, &c.	Price of ground.	Price of buildings.	Total.
23	Mary Thompson	Mary Thompson	A small wooden building of little value on the alley - - -	-	-	$900
24	Mrs. Swayne -	A. Reiley -	On High street a 2-story frame house, with basement, 21 by 20 feet, covered with shingles; in the middle of the lot a 1-story frame house 21 by 16: on the alley a wood blacksmith's shop 20 by 18 feet - -	$750	$850	1,600
25	A. & R. Cross -	A. & R. Cross -	On High street a wooden shanty of little value, 25 by 25 feet - -	600	50	650
26	Mrs. Swayne -	P. Hagan -	On High street a 2-story stone house, with basement, 24 by 20 feet, covered with shingles; on the alley a 2-story stone house, 30 by 26 feet, covered with slate, and a 1-story stone kitchen, 14 by 12 feet -	800	1,800	2,600
27	M. Foley -	M. Foley -	Vacant on High street, on the alley, a 2-story stone house, 30 by 20 feet, covered with slate, and a 2-story stone kitchen, 28 by 16 feet, shingle roof - - - - - - - - - -	-	-	2,000
28	Mrs. Swayne -	P. Hagan -	On High street a stone foundation, and a wooden building partly erected, 30 by 25 feet; on the alley a 2-story stone house, 26 by 20 feet, slated roof - - - - - - - -	800	1,200	2,000
29	Martin Grace -	M. Grace -	Vacant on High street, on the alley, a 2-story stone house, 28 by 20 feet, with a 1-story stone kitchen, 18 by 15 feet, both covered with slate -	-	-	1,500
[illegible]	[illegible]enbaugh -	M. Breitenbaugh -	A 2-story brick house, with basement, 26 by 22 feet, well finished -	-	-	1,700
[illegible]	Mrs. Swayne -	M. Grace -	Some walling and an old wood building - - - - - -	350	60	410
[illegible]	M. Grace -	M. Grace -	A 1-story wooden building of little value; good stone foundation -	-	-	1,100
[illegible]	Mrs. Swayne -	Mrs. Swayne -	A 1-story wooden building of little value - - - - -	350	40	390
34	M. Grace -	M. Grace -	On the alley a 2-story stone house, 30 by 18 feet; another stone house 2 stories, 20 by 18 feet; a 1-story wooden house, 25 by 20 feet, and another 1-story building, 20 by 12; the stone houses are partially new; the wood house of little value - - - - - -	-	-	3,000
[illegible]	United States -	Dr. N. Marmion -	A stone house 2-stories, with basement and gallery, 35 by 22 feet; also, a wooden 1-story house, 16 by 14 feet - - - -	-	-	2,000
			For payment for part of "Byrnes's island" - - - -	-	-	1,500
						50,261

HARPER'S FERRY ARMORY, *December* 12, 1841.

JOHN SYMINGTON, *Master armorer.*

INDEX TO 1841 - 1852 RENTERS

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
1.Adams, James T	-	-	45	23	22	40	40
2. Amiss, A. J.	-	-	-	-	158		
3.Anderson,Jonathan	149						
4. Apsey, Louisa		103					
5. Apsey, William	54						
6. Apsey,Wm.,machinist	103						
7. Arvin, Elias	87	87	22	22			
8. Arvin, John	129	129	129	129	37	37	37
9. Atkinson, George			43	43			
10.Augur, George L.					40		
11. Avis, Bazil		138	138	138	138	138	138,146
12. Avis, John	156	120	120				
13. Baden, William	157	157	157	157	157		
14. Baker, Corbin	151				66	66	
15.Ball, Armistead M.	25	25	25	25	32	32	32,11
16. Ball, Caspar				87			
17.Barnes, John H.	40	40					
18. Bateman, Jesse	120						
19. Bates, W.				102			
20. Baylis, John	49	49	49	49	49	49	49
21. Beale, Albert	86	42	42	178	178	178	178
22. Bell, Erasmus	128						
23.Belstirling,Anthony	79	79					
24. Berlin, Abraham	96						
25. Berlin, John		32	32	32			
26. Berry, G. W.						52	52
27. Best, Henry	139						
28. Bilson, William	91	19	48	48	48	48	48
29.Bodman, J.M.(Clerk)						182	182
30.Beelers, Benjamin F.	15						
31.Breckenbaugh, Martin	75						
32. Brittain, Joseph	104	104	104	104			
33. Brown, Adam	11	11	11	11	11	11	11.119
34. Brown, Jacob			7				
35. Buckler, Henry			148	148			
36.Burkhart, Philip		168	168	168	168	168	168,108
37.Burke, Mrs.		20					
38. Burton, James H., Master Armorer				158	2	2	2
39. Busey, Isaac			134				
40. Butler, John	142	142					
41. Butt, Zadoc	68	69	103	69			
42. Button, Charles W. Harness & Saddlemaker				174	7	7	7
43.Cameron, Charles C.	131	131	131				
44. Carbaugh, Michael			151				
45. Carbaugh, Mrs.				151	151	151	
46.Carlisle, Rhua	64	64					
47. Carney, Hiram	167						
48. Caton, James	159	8	8				
49.Cavallier, John				111			
50. Cavallier, Joshua		86	86	86			

INDEX TO 1841 - 1852 RENTERS

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
51. Chambers, Edmond	98	98	98	98			
52. Chambers, Singleton		122	122	122	122	122	122
53. Chambers, Singleton, Jr.							134
54. Chambers, William	17	17	17				
55. Chapman, John		127	127	127			
56. Chapman, Thomas		116	116				
57. Clarke, William		162					
58. Claspy, David	124						
59. Claspy, James	12	12	12	12	12	23	23
60. Claspy, John	95	95	95	95	95	95	95
61. Claspy, Mrs.		139	139				
62. Cleveland, Ralph					5	5	5
63. Cline, Albert					54	54	54
64. Clowe, Harrison L.		93	93	93	105	105	105
65. Clowe, Henry W.- machinist & Supt.	105	105	105	105	103	103	103
66. Coates, Durrett					25	25	
67. Cocke, John H.	70	145	145	145			
68. Cockwell, George						163	163
69. Cohen, Solomon				103			
70. Compton, George	74	74					
71. Compton, Mrs.			74				
72. Compton, Samuel	92	92	92	92	92		
73. Conner, James O.				181			
74. Coons, David	Ferry						
75. Coons, Philip, butcher, stable, slaughter house	50	171	171	171	170	170	170
76. Copeland, James	36	36					
77. Copeland, William		124	58	75	127	127	127
78. Cox, George W.		53					
79. Cox, Joshua	119	72-73	72-73	72/73			
80. Cross, Ambrose	106	106	106	106	106	106	106
81. Cross, Rezin	23	23	23				
82. Crowl, George		22	87				
83. Crowl, Jacob	85	85	85	85	85	134	134,98
84. Crowl, Jacob, Jr.				159			
85. Crowl, Michael	82	82	54	54			
86. Crutchley, John W. or Cruchley, John	113	113	113	100	100	100	100
87. Cruzen, George W.		117	117	117	117	117	117
88. Cruzen, William	117						
89. Cutshaw, George W.		85					
90. Daingerfield, John E. P. (Paymaster's Clerk)	46	4	3	179	179	179	129/110
91. Davidson, George W.				80			
92. Dearing, Elias	43	43		81			
93. Dearing, Notley W.		52	52	52	116	116	116
94. Decker, William	29						
95. Derry, Michael		153-Ferry					
96. Dewey, A. R.					52		
97. Dickey, John	21	21	21	21			
98. Dudran, George W.					52	52	52

INDEX TO 1841 - 1852 RENTERS

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
99. Dugan, George W.		47	47	47	47	47	47
100. Duke, James F.	109	109	109	109	109		109
101. Duke, Talcott				109	109	109	
102. Duncanson, James	Garden						
103. Earle, William			96	35			
104. Earnest, John				166	166	158	158
105. Earnshaw, J. T.						46	46
106. Earnshaw, Thomas	135	90	79	79	10	10	10
107. Earnshaw, Thomas T. merchant.			69			4	4
108. Elgin, William S.	123						
109. Engle, James P.		128	128	128	128	128	128
110. Engle, Philip	26	26	26	26			
111. Engle, Jacob	152	152	152	152			
112. Fair, John					150		
113. Faulkner, Nelson			53				
114. Ferrill, William	90						
115. Ferrills, George W.		90					
116. Fisher, James	41						
117. Fitzsimmons, James		3					
118. Fitzsimmons, Wm. F.				160	160	160	160
119. Fleming, Isaac		9	9		146	146	146,138
120. Fleming, Solomon	143	143	143	143			
121. Foley, Michael, a carpenter	53						
121. Foley, James, a carpenter		39					
122. Fossett, Alexander		53					
123. Fossett, Henry						166	166
124. Fouke, Isaac, Lawyer					189		
125. Foggett, William Also: "Froggett.					67	67	67
126. Fuss, Jeremiah, a carpenter and mayor	140	140	140	140	140	140	140
127. Gannon, Henry		57	57	57	57	57	
128. Gannon, James C.				175			
129. Gannon, Noah H.				8	8	8	8
130. Gannon, William	57						
131. Garrett, Milton, a merchant.	6	6					
132. Geary, James							3
133. Gilbert, David	97						
134. Gompf, George W.					43	43	43
135. Gompf, Jacob	14	14	36	36	36	36	36
136. Gompf, Michael	13	13	13	13			
137. Gore, Lewis E.		15	91	91			
138. Gore, Mrs.					91		
139. Graham, William	163	163	163	163	163		
140. Graham, Wm.-Estate	Ferry	Ferry					
141. Greer(Greaer) & Lawson	162						
142. Greer, William	83	83	83	83			
143. Griggs, Thomas	Ferry						

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
144. Grillett, Alex.					141	141 7	141 7
145. Grimes, Jessie							
146 Harris, Jerry, a plasterer.		63					
147.Harrison, Orison				10			
148.Herrington, Hiram		77	77	77			
149.Herrington, Timothy (also T.A.)	10	10	10				
150.Hillsborough & Harpers Ferry Turnpike Co.							153
151.Hobbs, Armistead (Also A.F.)		38	38	38	38	38	38
152.Hoffman, Philip	16	16	16	16	16	16	16
153. Holt, Charles	132	132	132	132	169	169	169
154. Holt, Joab	134	134		134	134		
155. Holt, John		139					
156.Huger,Col. Benjamin Supt., 1851-52						184	184
157.Hughes, Thomas, a merchant.		4	4				
158.Hyatt, John, a carpenter.	60	60					
159.Hyatt, J. G. W.					159	157	157
160.Jarboe, William, a carpenter.		148		177			
161.Johnson, Daniel	147	147	147				
162. Johnson, John B.							8
163.Johnson, Jospeh G.	47						
164. Johnson, Lewis					93		
165. Johnson, Richard	140	140					
166. Johnson, Thomas	63						
167. Jones, Ashfield	44						
168. Jones, Henry	80	80	80				
169. Jones, Peter			58	58	149	149	149
170. Kemp, William			153	153			
171. Kennedy, John	"163"						
172. Kilham, Samuel	18	46	46	46	46		
173. King, John H., Director, Rifle Factory	158	158	158	116			
174.Kirby, Meshac	121	97	97	97	97	97	97
175. Kirby, William		52	52	52	41	41	41
176.Kirby, Wm. C.					137	137	137
177.Kirgin, Thomas	169	169	169	169			
178.Kitzmiller, A.M,Chief (Supt.'s Clerk.	164	164	164	3	177	177	177
179. Koonce, David, a merchant.		7	7				
180. Krepps, Christian	81	81	81				
181. Krepps, James		55					
182. Krepps, Joab		81	81				
183. Krepps, John W.	65	65	65	65	65	65	65
184. Krepps, Marine J.or Kreps, Martin J.		55	55	55	55	55	145 55

Names of Renters	1841	1844	1846	1849	1850	1851	1852
185. Krout, Henry	59	59	59	59			
186. Laley, Thomas	165						
187. Laley, Thomas K.					119	119	119
188. Lawson & Grear	162	162					
189. Leese(Leece)Martin			139	139	139	139	139
190. Lenox(lennox),Joseph			124	124			
191. Lennox, William T,					136	136	136
192, Lennox, Mrs. Elizabeth							136
193. Lewis, Joshua T.		167	33	33			
194. Lindsay, Samuel J.	24	126	126		20		
195. Litle, Peter, a master stone mason.	66	66	66	66			
196. Littlejohn, P.O			4				
197 Llewellyn,John	111	111	111				
198.Llewellyn, Thomas	114	114	114	114	114	114	114
199.Llewellyn, Thomas Jr.					129	129	
200.Lucas, Edward,Jr. Supt. in 1841;Pay-master, 1848-58.	1			185	185	185	185 3,4
201.Macquire, Patrick					147	147	147
202.Mc Bee, Benjamin	125						
203.McBride, Philip	146	156	156				
204.McCabe,Bernard							48
205.McCabe, Francis							47
206.McCartney, John	148						
207.McClellan, John,Jr.					145	145	145/128
208.McCleur, William	88	88	88	88	88		
209.McCorn, Austin					90	159	159
210.McDaniel, William	84	84	84	84	84	61	61
211.McFaden, Daniel		8					
212.McForden, David				7			
213.McKann, Valentine	102						
214.McKee, Joseph	99	99	99	99	99	99	99
215.McKinsey, Samuel (McKinzie).	31	31					
216.McSherry, William,US forest ranger,LoudounH.					176	176	176
217 McGraw,William (Magraw)-Slaughter H.		170	170	170	170	170	170
218.Mahony, William					178	178	178
219. Mahoney, Mrs.					152	152	
220. Marlatt, William	150						
221. Marmion,Nicholas,Dr.	183	183	183	182			
222. Marquett, George P.					9	9	9
223.Marquett, John	19	19/54	19	19			
224. Mallory, Thomas		75	75				
225.Marsteller, Asa		146	146	146	101	101	100-101
226. Marstellar, John	101	101	101	101			
227.Martin, Joseph R.			55	126	126	126	126
228. Martin, William H.					19	19	19
229. Mason, John							52
230. Mathews, Joseph	51	44/51	18	18	18	18	17
231.Mathews, Thomas							8

Names of Renters	1841	1844	1846	1849	1850	1851	1852
232. Mauzy,George-Clerk	55						
233. Medlar, William	22		153	153	45	45	45
234. Melhorn, Francis C.		121	121	121	121	121	121
235. Merrick, James	145						
236.Methodist Episcopal Parsonage	144	144	144	144	144		
237. Miller, Henry	116						
238. Miller, Isaiah E.					143	143	143
239. Miller, Joseph W.				131	131	131	131
240. Mills, James					98	98	98/55
241.Moor, Benjamin, Master Armorer	2	2	2	2			
242.Moor, Benjamin, Jr, Clerk	107	107	107	107			
243. Moor, William H.		3	5		177		
244. Nichols, John	30	30	30	30	30		
245. Nichols, Mrs.						30	30
246. Nicholson, Robert						153	
247.Nunnamaker, Anthony and Mary							22
248.Nunnamaker, George					26	26	26
249.Nunnamaker, Henry		159	159				
250.Nunnamaker, William		76	76	76			
251. O'Boyle, Daniel	56	18	18				
252. O'Laughlin, James (J.Y. O'Laughlin).		32		17	17	17	
253. Orme, William		160	160	161	161	161	161
254. Ott, Benjamin			149	149		4	39
255. Ott, Joseph	130	130	130	130			
256. Overwater, Casper					153		
257. Parker, Richard, Paymaster	3 173	1	1				
Parsonage,Methodist	144	144	144	144	144		
258. Pollock, Addison		24					
259. Pollack Wm. T.A.	126	24		24			
260. Porter, Robert D.			141	141			
261. Potts, David	155	155	167	167			
262.Potts, Zachariah	166	166	166				
263. Price, James				71			
264. Price, John, merchant.				147		7	7
265.Price, John F., a carpenter	71	71	71	71	69	69	69
266.Price, Michael E.							132
267. Reed, George	5						
268. Reed, Henry							52
269. Rhulman, Adam	112	112	112	112	112	112	112
270. Richards, William	168			156	156	156	156
271. Ridenour John		46					
272. Ridenour, Robert			46				
273. Riley, Absalem			31	31	31	31	
274. Riley, John	133	133	133				
275. Riley, Mrs. John				133	133	133	

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
276.Riley, Joshua	122						
277.Riley, William D.				120	120	120	120
278.Rockenbaugh, John, merchant.	4						
279.Roderick, Abraham	69	70	70	70	22	22	22
280.Roderick, Hesekiah	35	35	35				
281.Roderick, John W.	28	14	14	14	32	32	32
282.Roderick, William A.		91	15	15			
283. Roderick, W.W.					21		
284.Rollins, James	27	29	29				
285. Rowe, John L.		165	165	165	118	118	118
286. Russell, Benjamin				5			
287. Russell, James				68	68	68	68
288. Russell, John						144	144
289. Russell,John(Father)				113	113	113	
290. Russell, John(of Thomas)					110	110	110
291. Russell, Richard					148	148	148
292. Russell,Thomas,Sr.	78	78	78	78			
293. Russell,Thomas,Jr.	93	68	68				
294. Sagle, Henry		151					
295. Sagle, Nathan				89	181	181	181
296. Schaarsman, Philip							105
297. Schaeffer,John A,	67	67	67	67			
298. Schaeffer, William	77						
299, Schneidewindt, Andrew		173					
300. School Room			53	53	53		
301. School Room				64	64	64	64
302. School Room				96	96	96	
303. School Room			102	102	102	102	102
304. Sheeler, John		20	20	20			
305. Shewbridge, John	89	89	89	90	130	130	130
306. Shewbridge, Samuel	9	41	41				
307.Shewbridge,Wm.		28					
308. Shope, Augustus	32	46					
309. Simpson, William			90	55	55	55	55
310. Shumaker, Casper					153		
311. Sleppy, John	136	136	136	136	59	59	59
312 Smith, Fred. C.					125	125	125
313.Smith, Joseph(merchant			3	4			
314. Smith, William S.	8						
315. Snook, Benjamin, M a tinsmith	58	58					
316. Snook, Solomon	33	33/3					
317. Snook, William S.			24	24	24	24	23-24
318.Spangler, Emanuel	137	137	137	137	104	104	104
319. Stahl, John	161	161	161				
320. Starrett, John	153						
321. Stabbs, Samuel	38						
322. Steadman, Levi	48	48	48				
323. Steaman, Wm.		27					
324. Stephenson, F. W.	141	141.					

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
325. Stephens, Jeremiah		48					
326.Stevens, William J, a merchant.	7						
327.Stipes, Benjamin	100	100				6	6
328.Stipes, Ezekial			94	94	94		
329. Stipes, Mrs.						94	94
330. Stipes, Henry	45	6	6	6	6		6
331. Stipes, John D,		94					
332. Stipes, Reuben	154	154	154	154			
333. Stipes, Mrs.					154	154	154
334. Stipes, William	94						
335. Stpes, William I.	34						
336. Storm, Anthony	20						
337. Stover, John W.					35	35	35
338. Strider, John H.		50					
339. Sturdy, Thomas	72-73	119	119	119			
340. Sullivan, T.J. W., merchant tailor				189	4		
341.Sutherland, Cyrus (Southerland, Sutterland)		125	125	125			
342.Symington, Major John,Supt.				184	184	184	
343. Taylor, Reuben		74	74				
344. Trail,Samuel(Traile)	43	43	43	43	43	43	43
345. Trail, Solomon			153	153			
346. Turk, William	127	149					
347. Unseld, John Colin		172	172	172	172	172	172
stable site + house					182		
348. Van Horn, A. H.					3	3	3
349, Vories, Ashford		44					
350. Ward, Henry H.Clerk	7	7					
351. Ward, George H.Clerk			7	180	180	180	180
352. Ward, W. D.				55			
353. Watson, James							49
354.Weaning, George W.							57
355. Weaning, John	62	62	62	62	62	62	62
356. Wentzle, Benjamin		135	135	135	135	135	135
357. Wentzle, Francis	61	100	100				
358. Wentzle, John					61		
359. Wentzle, Joseph		61	61	61			
360. Wentzle, William H.			32	32			
361. Whaley, J.T.					7		
362. Whaley, Thomas, Jr.				41			
363.Wiggington, John	37	37	37	37	37	37	37
364. Wilson, Asaph	118	118	118	118			
365. Wilson, James	138						
366. Wilson,John G.	39						
Post Office of 367.Wilson, William F.	7				124	124	124
368. Wood, William	52	52					
369. Woodhall, Peter					165	165	165
370. Woods, G. W.					132	132	132
371. Wright, Andrew J.					39	39	10
372. Wright, Jerome B.	110	110	110	110			

INDEX TO 1841 - 1852 RENTERS

Numbers of houses they were occupying is listed below

Names of Renters	1841	1844	1846	1849	1850	1851	1852
373. Yantis, Isaac	108	108	108	108			
374. Yantis, Solomon					108	108	108
375. Yeaman, William B.	115	115					
376. Yeaman, Mrs.			115	115			
377. Young, Daniel J.		45	40				
378. Young, Daniel, Jr.				40			
379 Young, Daniel J.						111	111
380. Young, James					3		
381. Young, Jerone	39	39	39	39	107	107	107
382. Zimmerman, John						53	53
383. Craig, Major Henry K.,Supt.,1841-44	1	1					

October 7, 1981

(1) Draft Ms
(2) pamphlet 10/13/

Memorandum

To: Superintendent Don Campbell, Harpers Ferry NHP

From: Historian Charles W. Snell, National Capital Team, DSC.
Room 4314, 1100 L. Street, NW, Washington, D.C.

Subject: Draft of research report on History of Armory Dwelling Houses, 1841- 1852.

Enclosed is a copy of the final draft of "A Descriptive Catalog and Directory of 187 Armory Dwelling Houses, 1841 - 1852, of the U.S. Armory at Harper's Ferry, Virginia, Including Rents Collected 1822 to 1851, Harpers Ferry National Historical Park, West Virginia,"(September 1981), 290 pp., 23 location maps.

This is the second of a projected two-volume history of Armory Dwelling Houses. Volume I will deal with the construction, repair, and disposal of Armory Dwelling Houses from 1798 to 1884.

Charles W. Snell

Charles W. Snell,
Historian

Enclosure: Section 1

October 7, 1981

Memorandum

To: Superintendent Don Campbell, Harpers Ferry NHP

From: Historian Charles W. Snell, National Capital Team, DSC.
Room 4314, 1100 L. Street, NW, Washington, D.C.

Subject: Draft of research report on History of Armory Dwelling Houses, 1841- 1852.

Enclosed is a copy of the final draft of "A Descriptive Catalog and Directory of 187 Armory Dwelling Houses, 1841 - 1852, of the U.S. Armory at Harper's Ferry, Virginia, Including Rents Collected 1822 to 1851, Harpers Ferry National Historical Park, West Virginia,"(September 1981), 290 pp., 23 location maps.

This is the second of a projected two-volume history of Armory Dwelling Houses. Volume I will deal with the construction, repair, and disposal of Armory Dwelling Houses from 1798 to 1884.

Charles W. Snell

Charles W. Snell,
Historian

Enclosure:
Section 2

October 7, 1981

Memorandum

To: Superintendent Don Campbell, Harpers Ferry NHP

From: Historian Charles W. Snell, National Capital Team, DSC.
Room 4314, 1100 L. Street, NW, Washington, D.C.

Subject: Draft of research report on History of Armory Dwelling Houses, 1841- 1852.

Enclosed is a copy of the final draft of "A Descriptive Catalog and Directory of 187 Armory Dwelling Houses, 1841 - 1852, of the U.S. Armory at Harper's Ferry, Virginia, Including Rents Collected 1822 to 1851, Harpers Ferry National Historical Park, West Virginia,"(September 1981), 290 pp., 23 location maps.

This is the second of a projected two-volume history of Armory Dwelling Houses. Volume I will deal with the construction, repair, and disposal of Armory Dwelling Houses from 1798 to 1884.

Charles W. Snell

Charles W. Snell,
Historian

Enclosure:

Section 3

October 7, 1981

Memorandum

To: Superintendent Don Campbell, Harpers Ferry NHP

From: Historian Charles W. Snell, National Capital Team, DSC.
Room 4314, 1100 L. Street, NW, Washington, D.C.

Subject: Draft of research report on History of Armory Dwelling Houses, 1841- 1852.

Enclosed is a copy of the final draft of "A Descriptive Catalog and Directory of 187 Armory Dwelling Houses, 1841 - 1852, of the U.S. Armory at Harper's Ferry, Virginia, Including Rents Collected 1822 to 1851, Harpers Ferry National Historical Park, West Virginia,"(September 1981), 290 pp., 23 location maps.

This is the second of a projected two-volume history of Armory Dwelling Houses. Volume I will deal with the construction, repair, and disposal of Armory Dwelling Houses from 1798 to 1884.

Charles W. Snell

Charles W. Snell,
Historian

Enclosure:

Section 4 - Last of 4